

**STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS**

**PAVEMENT REMOVAL SUMMARY
 (IN SQUARE YARDS)**

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	ASPHALT REMOVAL	CONCRETE REMOVAL	COMMENTS
EXISTING OUTSIDE PAVED SHOULDERS						
-L-	20+00	60+00	LT	2415.69		
-L-	63+32	68+99	LT	292.00		
-L-	77+14	90+25	LT	664.14		
-L-	63+73	69+73	RT	347.48		
-L-	83+69	90+25	RT	331.94		
EXISTING MEDIAN PAVED SHOULDERS & LEFTOVERS						
-L-	20+00	26+70	LT	272.95		
-L-	28+80	31+65	LT	109.92		
-L-	37+04	90+25	LT	2070.74		
-L-	21+50	28+79	CL	1504.12		US 29 NB LEFTOVER
-L-	28+79	31+65	RT	125.09		
-L-	31+65	37+04	CL	1196.30		US 29 SB LEFTOVER
-L-	37+04	90+25	RT	2109.76		
EXISTING ACCELERATION/DECELERATION LANES & RAMPS						
-L-	32+79	63+73	RT	6480.01		INCLUDES PS & GORE
-L-	60+00	63+32	LT	981.56		INCLUDES PS & GORE
-L-	68+99	77+14	LT	1958.25		INCLUDES PS & GORE
-L-	69+73	83+69	RT	2788.21		INCLUDES PS & GORE
-RPA-	21+10	24+90	LT & RT	652.75	2232.06	EXISTING RAMP A & D
-RPD-	17+60	23+60	LT & RT	1844.74	1611.14	EXISTING RAMP B & C
EXISTING ROADS & DRIVEWAYS						
-Y1-	10+53	19+21	RT	1881.48		EXISTING SUMMIT AVE.
-Y1-	20+65	23+95	LT	220.09		
-Y1-	29+89	33+98	RT	2181.45		EXISTING REEDY FORK PKWY.
-RPD-	15+03	15+55	LT	317.71		EXISTING REEDY FORK PKWY.
-Y2-	11+42	20+67	RT	2741.61		EXISTING REEDY FORK PKWY.
-L-	16+66	17+00	LT	85.70		PARCEL NO. 3 DRIVEWAY
-L-	20+63	23+53	LT	723.36		PARCEL NO. 1 DRIVEWAY
-L-	25+25	25+94	LT		327.80	PARCEL NO. 2 DRIVEWAY
-L-	27+06	32+06	LT	2750.93		PARCEL NO. 2 DRIVEWAY
-Y4-	10+23	14+65	RT	1273.75		PARCEL NO. 11 DRIVEWAY
-DR2A-	12+07	17+58	RT	2559.11		PARCEL NO. 12 DRIVEWAY
-DR1-	10+15	13+65	RT	1770.44		PARCEL NO. 7 DRIVEWAY
TEMPORARY PAVEMENT						
-L-	35+95	92+25	LT	6243.22		INCLUDES REMOVAL FOR WIDENING MEDIAN
-L-	32+45	92+25	RT	6802.78		INCLUDES REMOVAL FOR WIDENING MEDIAN
-Y1-	15+67	16+57	RT	570.94		-DR1- TEMPORARY CONNECTION
			TOTAL	56268.2	4171.0	SEE SHEET 2B-8 FOR DETAIL OF EXISTING PAVEMENT TO BE REMOVED AND REPLACED
			SAY	56,500	4,200	