

PROJECT REFERENCE NO.	SHEET NO.
R-4707	EC-6L/CONST.06
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

CULVERT CONSTRUCTION SEQUENCE STA. 46+08 -Y-

PHASE VI

1. Remove all Impervious dikes, temporary pipes, and diversion channels
2. Remove all Stilling Basins after Culvert Construction and Clearing and Grubbing phase.
3. Construct Roadway.

