DocuSign Envelope ID: 86DE3336E-A60F-4B6E-9D8F-1311E627EA15

PROJECT REFERENCE NO.	SHEET NO.
R-4707	SIGN-4D

APPROVED: DocuSigned by: David T. Sears 3655FB0D84B4458...

DATE: 4/16/2020

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 044558 ENGINEER DAVID T. SEARS

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SIGN NUMBER: 201,202
TYPE: A
QUANTITY: 2

SIGN WIDTH: 8'-0"
HEIGHT: 5'-0"
TOTAL AREA: 40.0 Sq.Ft.

BORDER TYPE: FLUSH
RECESS: 0"
WIDTH: 1.5"
RADII: 6"

NO. Z BARS: 2
LENGTH: 88.0

BACKG COLOR: Green
COPY COLOR: White

SYMBOL	X	Y	WID	HT
AR_Type A	67	6	18.3	29.3

MAT'L: 0.125" (3.2 mm) ALUMINUM

USE NOTES: 1,2,3

1. Legend and border(except those that are colored black) shall be direct applied Grade A sheeting.
2. Background shall be Grade C reflective sheeting.
3. Shields; A, B, and C type arrows shall be on 0.032" (0.8mm) aluminum and demountable.

DESIGN BY: A. TUTT CHECKED BY: D. SEARS Jan 24, 2020
PROJECT ID: R-4707 LOCATION: -L- STA. 50+00, -L- STA. 72+40 DIV: 7

Spacing Factor is 2.25 for "EXIT"
Spacing Factor is 1 unless specified otherwise

LETTER POSITIONS

Letter spacings are to start of next letter

																										Series/Size Text Length
		E	X	I	T																					
	26	12.7	15.7	6.6	9	26																				E 2000 44.1
		1	3	7																						
	13.4	9	16.6	14.6	42.4																					E 2000 40.1

FILENAME: R4707_SGN_DESIGNS

NORTH CAROLINA D.O.T. SIGN DETAIL

RK&K
P: (919) 878-9560
8601 Six Forks Road Forum 1 Suite 700 | Raleigh, N.C. 27615
NC License No. F-0112
Engineers | Construction Managers | Planners | Scientists
www.rkk.com
Responsive People | Creative Solutions

$SYSTIME$
DGN

SIGN DESIGNS