



**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

Color Code TIA/EIA 598-B			LEGEND		NOTES	
BL (1) Blue	RD (7) Red		X	= Fusion Splice Individual Fiber	1.	Unused fibers left coiled and stored in splice tray.
OR (2) Orange	BK (8) Black		C	= Cap and Seal	2.	Unused buffer tubes left coiled and stored in splice enclosure.
GR (3) Green	YL (9) Yellow		EXPRESS	= Express entire buffer tube/fibers through without cutting	3.	Edge switch configurations are generic. Contractor is responsible for determining/ensuring the proper terminations.
BR (4) Brown	VI (10) Violet		BUFFER SPLICE	= Splice all fibers in buffer tube color to color		
SL (5) Slate	RS (11) Rose					
WH (6) White	AQ (12) Aqua					



	Elizabeth City Signal System Fiber-Optic Splicing Details		
	Division 1 Pasquotank County Elizabeth City	PLAN DATE: April 2018	
PREPARED BY: AJ Davis	REVIEWED BY: LM Moon	REVISIONS	INIT. DATE
SCALE: N.T.S.	CADD Filename:	DATE: 8/21/2018	SEAL: Lisa M. Moon