



PILE SPLICE DETAILS






_ LIN FT. 160

NO. 7

SECTION A-A




BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETER-MINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

TEMPORARY DRAINAGE AT END BENT



CONCRETE — COLLAR ─BOTTOM OF CAP © HP 14 X 73 — STEEL PILE | 2'-2" ELEVATION


CORROSION PROTECTION FOR STEEL PILES DETAIL

B-5818 PROJECT NO. __

ANSON COUNTY

27+19.00 -L-

SHEET 3 OF 3



STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

> SUBSTRUCTURE INTEGRAL END BENT 1

				REVI	SION	IS		SHEET NO
ſī	DOCUMENT NOT CONSIDERED	NO.	BY:	DATE:	NO.	BY:	DATE:	S-18
١	FINAL UNLESS ALL	1			3			TOTAL SHEETS
	SIGNATURES COMPLETED	2			4			24

DRAWN BY :	AWN BY : M.G. SHAIKH					
CHECKED BY :	H. A. LOCK	_ DATE :	09/2020			
DESIGN ENGINEER	OF RECORD: _	REZA KOUCHEKI	_ DATE :	12/2019		