

REFERENCE: B-5818

PROJECT: 45771

**CONTENTS**

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND (SOIL & ROCK)
3	SITE PLAN
4	PROFILE
5-6	CROSS SECTIONS
7-16	BORE LOGS
17	SITE PHOTOGRAPHS

**STATE OF NORTH CAROLINA**  
**DEPARTMENT OF TRANSPORTATION**  
**DIVISION OF HIGHWAYS**  
**GEOTECHNICAL ENGINEERING UNIT**

**STRUCTURE**  
**SUBSURFACE INVESTIGATION**

COUNTY ANSON  
 PROJECT DESCRIPTION BRIDGE NO. 11 ON NC 109  
OVER DEADFALL CREEK

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	B-5818	1	17

**CAUTION NOTICE**

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

**NOTES:**

- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
- BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

**PERSONNEL**

M. ARNOLD

M. DURWAY

D. TIGNOR

R. CLARKE

W. SHENBERGER

INVESTIGATED BY F&R, Inc.

DRAWN BY D. RACEY

CHECKED BY P. ALTON, P.E.

SUBMITTED BY P. ALTON, P.E.

DATE NOVEMBER 2019

SINCE *Prepared in the Office of:*



**FROEHLING & ROBERTSON, INC.**  
*Engineering Stability Since 1881*  
 310 Hubert Street  
 Raleigh, North Carolina 27603-2302 USA  
 T 919.828.3441 F 919.828.5751  
 www.fandr.com



DocuSigned by:

*Patrick Alton*

A270EF78A6DF412/4/2019

SIGNATURE

DATE

**DOCUMENT NOT CONSIDERED FINAL  
UNLESS ALL SIGNATURES COMPLETED**

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

Table containing various geotechnical sections: SOIL DESCRIPTION, GRADATION, ROCK DESCRIPTION, TERMS AND DEFINITIONS, SOIL LEGEND AND AASHTO CLASSIFICATION, CONSISTENCY OR DENSENESS, TEXTURE OR GRAIN SIZE, SOIL MOISTURE - CORRELATION OF TERMS, PLASTICITY, COLOR, MISCELLANEOUS SYMBOLS, RECOMMENDATION SYMBOLS, ABBREVIATIONS, EQUIPMENT USED ON SUBJECT PROJECT, ROCK HARDNESS, FRACTURE SPACING, BEDDING, INDURATION.

**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
GEOTECHNICAL ENGINEERING UNIT**















---

# SUBSURFACE INVESTIGATION


**SUPPLEMENTAL LEGEND, GEOLOGICAL STRENGTH INDEX (GSI) TABLES  
FROM AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS**

AASHTO LRFD Figure 10.4.6.4-1 — Determination of GSI for Jointed Rock Mass (Marinos and Hoek, 2000)

AASHTO LRFD Figure 10.4.6.4-2 — Determination of GSI for Tectonically Deformed Heterogeneous Rock Masses (Marinos and Hoek, 2000)


<p><b>GEOLOGICAL STRENGTH INDEX (GSI) FOR JOINTED ROCKS (Hoek and Marinos, 2000)</b></p> <p>From the lithology, structure and surface conditions of the discontinuities, estimate the average value of GSI. Do not try to be too precise. Quoting a range from 33 to 37 is more realistic than stating that GSI = 35. Note that the table does not apply to structurally controlled failures. Where weak planar structural planes are present in an unfavorable orientation with respect to the excavation face, these will dominate the rock mass behaviour. The shear strength of surfaces in rocks that are prone to deterioration as a result of changes in moisture content will be reduced if water is present. When working with rocks in the fair to very poor categories, a shift to the right may be made for wet conditions. Water pressure is dealt with by effective stress analysis.</p> <p><b>STRUCTURE</b></p>	SURFACE CONDITIONS					<p><b>GSI FOR HETEROGENEOUS ROCK MASSES SUCH AS FLYSCH (Marinos, P and Hoek E., 2000)</b></p> <p>From a description of the lithology, structure and surface conditions (particularly of the bedding planes), choose a box in the chart. Locate the position in the box that corresponds to the condition of the discontinuities and estimate the average value of GSI from the contours. Do not attempt to be too precise. Quoting a range from 33 to 37 is more realistic than giving GSI = 35. Note that the Hoek-Brown criterion does not apply to structurally controlled failures. Where unfavourably oriented continuous weak planar discontinuities are present, these will dominate the behaviour of the rock mass. The strength of some rock masses is reduced by the presence of groundwater and this can be allowed for by a slight shift to the right in the columns for fair, poor and very poor conditions. Water pressure does not change the value of GSI and it is dealt with by using effective stress analysis.</p> <p><b>SURFACE CONDITIONS OF DISCONTINUITIES (Predominantly bedding planes)</b></p>													
	VERY GOOD Very rough, fresh unweathered surfaces	GOOD Rough, slightly weathered, iron stained surfaces	FAIR Smooth, moderately weathered and altered surfaces	POOR Slickensided, highly weathered surfaces with compact coatings or fillings or angular fragments	VERY POOR Slickensided, highly weathered surfaces with soft clay coatings or fillings	VERY GOOD - Very Rough, fresh unweathered surfaces	GOOD - Rough, slightly weathered surfaces	FAIR - Smooth, moderately weathered and altered surfaces	POOR - Very smooth, occasionally slickensided surfaces with compact coatings or fillings with angular fragments	VERY POOR - Very smooth, slickensided or highly weathered surfaces with soft clay coatings or fillings									
	DECREASING SURFACE QUALITY →					COMPOSITION AND STRUCTURE													
<p> INTACT OR MASSIVE - intact rock specimens or massive in situ rock with few widely spaced discontinuities</p> <p> BLOCKY - well interlocked undisturbed rock mass consisting of cubical blocks formed by three intersecting discontinuity sets</p> <p> VERY BLOCKY - interlocked, partially disturbed mass with multi-faceted angular blocks formed by 4 or more joint sets</p> <p> BLOCKY/DISTURBED/SEAMY - folded with angular blocks formed by many intersecting discontinuity sets. Persistence of bedding planes or schistosity</p> <p> DISINTEGRATED - poorly interlocked, heavily broken rock mass with mixture of angular and rounded rock pieces</p> <p> LAMINATED/SHEARED - Lack of blockiness due to close spacing of weak schistosity or shear planes</p>	DECREASING INTERLOCKING OF ROCK PIECES ↓	90	80	70	60	50	40	30	20	10	70	60	50	40	30	20	10		
		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	A	B	C	D	E	F	G	H	
						<p> <b>A.</b> Thick bedded, very blocky sandstone. The effect of pelitic coatings on the bedding planes is minimized by the confinement of the rock mass. In shallow tunnels or slopes these bedding planes may cause structurally controlled instability.</p> <p> <b>B.</b> Sandstone with thin inter-layers of siltstone</p> <p> <b>C.</b> Sandstone and siltstone in similar amounts</p> <p> <b>D.</b> Siltstone or silty shale with sandstone layers</p> <p> <b>E.</b> Weak siltstone or clayey shale with sandstone layers</p> <p><b>C, D, E, and G</b> - may be more or less folded than illustrated but this does not change the strength. Tectonic deformation, faulting and loss of continuity moves these categories to <b>F</b> and <b>H</b>.</p> <p> <b>F.</b> Tectonically deformed, intensively folded/faulted, sheared clayey shale or siltstone with broken and deformed sandstone layers forming an almost chaotic structure</p> <p> <b>G.</b> Undisturbed silty or clayey shale with or without a few very thin sandstone layers</p> <p> <b>H.</b> Tectonically deformed silty or clayey shale forming a chaotic structure with pockets of clay. Thin layers of sandstone are transformed into small rock pieces.</p>													
						→ Means deformation after tectonic disturbance													

# SITE PLAN




**SKEW = 90°**


NOTE: Bridge was drilled based on the 3-span design




JAMES THOMAS HORSLEY AND  
MARK EDWARD MAUNEY




PROJECT REFERENCE NO.	SHEET NO.
B-5818	4
PROFILE BORINGS PROJECTED ALONG -L-	



GROUNDLINE TAKEN FROM .TIN FILE RECEIVED BY NCDOT DATED 09/09/2019.  
INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH  
PROJECTED ONTO THE PROFILE




<b>PROJECT REFERENCE NO.</b>	<b>SHEET NO.</b>
B-5818	5
<b>CROSS SECTION THROUGH END BENT 1</b>	
AT -L- STATION 27+14	
SKEW=90°	




(A) **Residual: Medium Stiff to Very Stiff, Moist, Tan-Orange-Brown, Fine Sandy SILT (A-4) with Trace Organics and Clay, Trace to Some Rock Fragments**

GROUNDLINE TAKEN FROM .TIN FILE RECEIVED BY NCDOT DATED 09/09/2019.  
 INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH  
 PROJECTED ONTO THE CROSS SECTION



<b>PROJECT REFERENCE NO.</b>	<b>SHEET NO.</b>
B-5818	6
<b>CROSS SECTION THROUGH END BENT 2</b>	
AT -L- STATION 28+44	
SKEW=90°	



GROUNDLINE TAKEN FROM .TIN FILE RECEIVED BY NCDOT DATED 09/09/2019.  
 INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH  
 PROJECTED ONTO THE CROSS SECTION

# GEOTECHNICAL BORING REPORT BORE LOG

# GEOTECHNICAL BORING REPORT BORE LOG

WBS 45771.1.1		TIP B-5818		COUNTY ANSON		GEOLOGIST M. Durway										
SITE DESCRIPTION Bridge No. 11 on NC 109 over Deadfall Creek in Anson County							GROUND WTR (ft)									
BORING NO. EB1-A		STATION 27+14		OFFSET 7 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 266.2 ft		TOTAL DEPTH 17.8 ft		NORTHING 393,985		EASTING 1,641,508										
DRILL RIG/HAMMER EFF./DATE F&R3495 CME-55 82% 03/01/2019			DRILL METHOD H.S. Augers			HAMMER TYPE Automatic										
DRILLER D. Tignor		START DATE 09/23/19		COMP. DATE 09/23/19		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
270																
265	266.2	0.0	3	6	9									266.2	GROUND SURFACE	0.0
	262.7	3.5	5	9	14									264.2	<b>RESIDUAL</b> Brown-Orange, Clayey Fine to Coarse Sandy SILT (A-4) with Trace Organics and Rock Fragments	2.0
260														259.2	Brown-Tan-Red, Fine to Coarse Sandy CLAY (A-6) with Trace Rock Fragments	7.0
	257.7	8.5	100/0.2												<b>WEATHERED ROCK</b> Gray (META-ARGILLITE)	
255																
	252.7	13.5	100/0.2													
250																
	248.4	17.8	60/0.0											249.2	<b>NON-CRYSTALLINE ROCK</b> Gray (META-ARGILLITE)	17.0
														248.4	Boring Terminated with Standard Penetration Test Refusal at Elevation 248.4 ft in NON-CRYSTALLINE ROCK (META-ARGILLITE)	17.8
															Notes: Surficial Organic Soil: 0.0-0.2'	

WBS 45771.1.1		TIP B-5818		COUNTY ANSON		GEOLOGIST M. Durway										
SITE DESCRIPTION Bridge No. 11 on NC 109 over Deadfall Creek in Anson County							GROUND WTR (ft)									
BORING NO. EB1-B		STATION 27+14		OFFSET 16 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 266.0 ft		TOTAL DEPTH 19.1 ft		NORTHING 393,972		EASTING 1,641,527										
DRILL RIG/HAMMER EFF./DATE F&R3495 CME-55 82% 03/01/2019			DRILL METHOD H.S. Augers			HAMMER TYPE Automatic										
DRILLER D. Tignor		START DATE 09/23/19		COMP. DATE 09/23/19		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
270																
265	266.0	0.0	3	4	6									266.0	GROUND SURFACE	0.0
	262.5	3.5	12	30	31									264.0	<b>RESIDUAL</b> Brown-Tan, Fine Sandy SILT (A-4) with Trace Organics	2.0
260														259.0	Orange-Brown-Gray, Fine to Coarse Sandy CLAY (A-6) with Some Rock Fragments	7.0
	257.5	8.5	25	19	24									254.0	Gray-Tan, Fine to Coarse Sandy SILT (A-4) with Trace Clay and Rock Fragments	12.0
255															<b>WEATHERED ROCK</b> Gray (META-ARGILLITE)	
	252.5	13.5	79	21/0.1												
250																
	247.5	18.5	100/0.3											247.0	<b>NON-CRYSTALLINE ROCK</b> Gray (META-ARGILLITE)	19.0
	246.9	19.1	60/0.0											246.9	Boring Terminated with Standard Penetration Test Refusal at Elevation 246.9 ft in NON-CRYSTALLINE ROCK (META-ARGILLITE)	19.1
															Notes: Surficial Organic Soil: 0.0-0.1'	



# GEOTECHNICAL BORING REPORT

## BORE LOG

# GEOTECHNICAL BORING REPORT

## CORE LOG

WBS 45771.1.1		TIP B-5818		COUNTY ANSON		GEOLOGIST M. Durway									
SITE DESCRIPTION Bridge No. 11 on NC 109 over Deadfall Creek in Anson County							GROUND WTR (ft)								
BORING NO. B1-A		STATION 27+49		OFFSET 12 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 264.0 ft		TOTAL DEPTH 34.5 ft		NORTHING 394,017		EASTING 1,641,524									
DRILL RIG/HAMMER EFF./DATE F&R3495 CME-55 82% 03/01/2019			DRILL METHOD H.S. Augers		HAMMER TYPE Automatic										
DRILLER D. Tignor		START DATE 09/24/19		COMP. DATE 09/24/19		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)	
265	264.0	0.0	5	10	9								264.0	0.0	GROUND SURFACE
												M	262.0	2.0	<b>RESIDUAL</b> Orange-Brown, Fine to Coarse Sandy SILT (A-4) with Trace Clay and Rock Fragments
260	260.5	3.5	12	12	12							M	257.0	7.0	Orange-Brown, Fine Sandy Silty CLAY (A-6) with Trace Rock Fragments
													255.0	9.0	<b>WEATHERED ROCK</b> Gray (META-ARGILLITE)
255	255.5	8.5	70	30/0.1									249.5	14.5	<b>NON-CRYSTALLINE ROCK</b> Gray (META-ARGILLITE)
													249.5	14.5	<b>NON-CRYSTALLINE ROCK</b> Gray (META-ARGILLITE)
250	250.5	13.5											241.5	22.5	Gray (META-ARGILLITE)
	249.5	14.5											236.5	27.5	Gray (META-ARGILLITE)
245													229.5	34.5	Boring Terminated at Elevation 229.5 ft in NON-CRYSTALLINE ROCK (META-ARGILLITE)
240															Notes: NM=Not Measured
235															
230															




NCDOT BORE DOUBLE B-5818\_GEO\_BH\_ANSON CO.GPJ NC\_DOT.GDT 11/5/19

WBS 45771.1.1		TIP B-5818		COUNTY ANSON		GEOLOGIST M. Durway	
SITE DESCRIPTION Bridge No. 11 on NC 109 over Deadfall Creek in Anson County							GROUND WTR (ft)
BORING NO. B1-A		STATION 27+49		OFFSET 12 ft LT		ALIGNMENT -L-	
COLLAR ELEV. 264.0 ft		TOTAL DEPTH 34.5 ft		NORTHING 394,017		EASTING 1,641,524	
DRILL RIG/HAMMER EFF./DATE F&R3495 CME-55 82% 03/01/2019			DRILL METHOD H.S. Augers		HAMMER TYPE Automatic		
DRILLER D. Tignor		START DATE 09/24/19		COMP. DATE 09/24/19		SURFACE WATER DEPTH N/A	
CORE SIZE N		TOTAL RUN 20.0 ft		STRATA		DESCRIPTION AND REMARKS	
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	REC. (ft) %	RQD (ft) %	SAMP. NO.
249.48	249.5	14.5	3.0	N=60/0.0 2:23/1.0 2:04/1.0 1:56/1.0	(2.7) 90%	(2.3) 77%	(7.7) 96%
	246.5	17.5	5.0	2:38/1.0 2:01/1.0 1:49/1.0 1:51/1.0 1:57/1.0	(5.0) 100%	(2.6) 52%	(4.9) 61%
245	241.5	22.5	5.0	2:25/1.0 2:00/1.0 2:12/1.0 2:29/1.0 2:08/1.0	(4.8) 96%	(0.9) 18%	(4.8) 96%
240	236.5	27.5	5.0	2:10/1.0 2:13/1.0 2:04/1.0 2:24/1.0 2:00/1.0	(5.0) 100%	(3.5) 70%	(7.0) 100%
235	231.5	32.5	2.0	2:10/1.0 2:10/1.0	(2.0) 100%	(0.7) 35%	(4.2) 60%
230	229.5	34.5	2.0				
Begin Coring @ 14.5 ft <b>NON-CRYSTALLINE ROCK</b> Slight to Moderately Severe Weathering, Moderately Hard to Soft, Tan-Gray META-ARGILLITE, with Moderately Close to Very Close Fracture Spacing GSI=55-75 Moderate to Severe Weathering, Moderately Hard to Medium Hard, Tan-Gray META-ARGILLITE, with Very Close Fracture Spacing GSI=30-50 Slight to Moderately Severe Weathering, Hard to Medium Hard, Blue-Gray META-ARGILLITE, with Close to Very Close Fracture Spacing GSI=65-85 Boring Terminated at Elevation 229.5 ft in NON-CRYSTALLINE ROCK (META-ARGILLITE)							
Notes: NM=Not Measured							

NCDOT CORE DOUBLE B-5818\_GEO\_BH\_ANSON CO.GPJ NC\_DOT.GDT 11/5/19



**CORE PHOTOGRAPHS:  
B-5818 | 45771.1.1  
B1-A : -L- Station 27+49, 12' LT**



## GEOTECHNICAL BORING REPORT BORE LOG




## GEOTECHNICAL BORING REPORT CORE LOG

WBS 45771.1.1		TIP B-5818		COUNTY ANSON		GEOLOGIST M. Durway											
SITE DESCRIPTION Bridge No. 11 on NC 109 over Deadfall Creek in Anson County							GROUND WTR (ft)										
BORING NO. B1-B		STATION 27+49		OFFSET 12 ft RT		ALIGNMENT -L-											
COLLAR ELEV. 264.5 ft		TOTAL DEPTH 32.8 ft		NORTHING 394,004		EASTING 1,641,544											
DRILL RIG/HAMMER EFF./DATE F&R3495 CME-55 82% 03/01/2019			DRILL METHOD H.S. Augers		HAMMER TYPE Automatic												
DRILLER D. Tignor		START DATE 09/23/19		COMP. DATE 09/24/19		SURFACE WATER DEPTH N/A											
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION				
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					ELEV. (ft)	DEPTH (ft)	
265	264.5	0.0													264.5	0.0	GROUND SURFACE
			3	4	4										262.5	2.0	<b>RESIDUAL</b> Tan, Fine Sandy SILT (A-4) with Trace Organics
			6	8	8										257.5	7.0	Tan-Brown, Fine Sandy CLAY (A-6)
															255.0	8.5	<b>WEATHERED ROCK</b> Gray (META-ARGILLITE)
															254.7	9.8	<b>NON-CRYSTALLINE ROCK</b> Gray (META-ARGILLITE)
															252.7	11.8	Gray (META-ARGILLITE)
															231.7	32.8	Boring Terminated at Elevation 231.7 ft in NON-CRYSTALLINE ROCK (META-ARGILLITE)

WBS 45771.1.1		TIP B-5818		COUNTY ANSON		GEOLOGIST M. Durway					
SITE DESCRIPTION Bridge No. 11 on NC 109 over Deadfall Creek in Anson County							GROUND WTR (ft)				
BORING NO. B1-B		STATION 27+49		OFFSET 12 ft RT		ALIGNMENT -L-					
COLLAR ELEV. 264.5 ft		TOTAL DEPTH 32.8 ft		NORTHING 394,004		EASTING 1,641,544					
DRILL RIG/HAMMER EFF./DATE F&R3495 CME-55 82% 03/01/2019			DRILL METHOD H.S. Augers		HAMMER TYPE Automatic						
DRILLER D. Tignor		START DATE 09/23/19		COMP. DATE 09/24/19		SURFACE WATER DEPTH N/A					
CORE SIZE N				TOTAL RUN 23.0 ft							
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		LOG	DESCRIPTION AND REMARKS	
					REC. (ft) %	RQD (ft) %	REC. (ft) %	RQD (ft) %			
254.66	254.7	9.8	3.0	N=60/0.0 2:29/1.0 2:24/1.0 3:00/1.0	(2.9) 97%	(1.6) 53%	(2.0) 100%	(0.7) 35%			Begin Coring @ 9.8 ft
	251.7	12.8	5.0	2:17/1.0 1:56/1.0 2:10/1.0 2:40/1.0 2:29/1.0	(5.0) 100%	(3.9) 78%	(20.6) 98%	(16.8) 80%			<b>NON-CRYSTALLINE ROCK</b> Slight to Moderately Severe Weathering, Hard to Medium Hard, Blue-Gray META-ARGILLITE, with Close to Very Close Fracture Spacing GSI=45-65
	246.7	17.8	5.0	2:10/1.0 2:22/1.0 2:01/1.0 2:08/1.0 2:10/1.0	(4.8) 96%	(3.9) 78%					Very Slight to Moderate Weathering, Hard to Medium Hard, Blue-Gray META-ARGILLITE, with Moderately Close to Very Close Fracture Spacing GSI=60-80
	241.7	22.8	5.0	1:40/1.0 2:20/1.0 2:09/1.0 2:56/1.0 2:39/1.0	(5.0) 100%	(4.1) 82%					
	236.7	27.8	5.0	1:45/1.0 1:34/1.0 1:53/1.0 1:38/1.0 1:49/1.0	(4.9) 98%	(4.0) 80%					
	231.7	32.8									Boring Terminated at Elevation 231.7 ft in NON-CRYSTALLINE ROCK (META-ARGILLITE)



**CORE PHOTOGRAPHS:  
B-5818 | 45771.1.1  
B1-B : -L- Station 27+49, 12' RT**







**CORE PHOTOGRAPHS:  
B-5818 | 45771.1.1  
B2-A : -L- Station 28+09, 12' LT**

**Begin Run 1  
9.7 feet**



**End Run 1 &  
Begin Run 2  
12.7 feet**

**End Run 2  
17.7 feet**

0.0 0.2 0.4 0.6 0.8 1.0 1.2 1.4 1.6 1.8 2.0

SCALE IN FEET

**Begin Run 3  
17.7 feet**



**End Run 3 &  
Begin Run 4  
22.7 feet**

**End Run 4  
27.7 feet**

0.0 0.2 0.4 0.6 0.8 1.0 1.2 1.4 1.6 1.8 2.0

SCALE IN FEET

# GEOTECHNICAL BORING REPORT BORE LOG





# GEOTECHNICAL BORING REPORT CORE LOG

WBS 45771.1.1		TIP B-5818		COUNTY ANSON		GEOLOGIST M. Durway								
SITE DESCRIPTION Bridge No. 11 on NC 109 over Deadfall Creek in Anson County						GROUND WTR (ft)								
BORING NO. B2-B		STATION 28+09		OFFSET 12 ft RT		ALIGNMENT -L-								
COLLAR ELEV. 264.5 ft		TOTAL DEPTH 31.6 ft		NORTHING 394,053		EASTING 1,641,578								
DRILL RIG/HAMMER EFF./DATE F&R3495 CME-55 82% 03/01/2019			DRILL METHOD H.S. Augers			HAMMER TYPE Automatic								
DRILLER D. Tignor		START DATE 09/25/19		COMP. DATE 09/25/19		SURFACE WATER DEPTH N/A								
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT				SAMP. NO.	LOG MOI	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75			100	ELEV. (ft)	DEPTH (ft)
265	264.5	0.0	2	3	4	.....	.....	.....	.....	.....	M	264.5	0.0	GROUND SURFACE
260	261.0	3.5	6	6	8	.....	.....	.....	.....	.....	M	252.5	12.9	<b>ALLUVIAL</b> Brown-Red to Tan-Gray, Silty Fine SAND (A-2-4) with Trace Organics
255	256.0	8.5	6	11	15	.....	.....	.....	.....	.....	W	250.9	13.6	<b>NON-CRYSTALLINE ROCK</b> Gray (META-ARGILLITE)
250	251.0	13.5	60/0.1			.....	.....	.....	.....	.....		249.7	14.8	Gray (META-ARGILLITE)
245						.....	.....	.....	.....	.....		240.3	24.2	Gray (META-ARGILLITE)
240						.....	.....	.....	.....	.....		239.5	24.9	Gray (META-ARGILLITE)
235						.....	.....	.....	.....	.....		232.9	31.6	Boring Terminated at Elevation 232.9 ft in NON-CRYSTALLINE ROCK (META-ARGILLITE)
Notes: Surficial Organic Soil: 0.0-0.1'														

WBS 45771.1.1		TIP B-5818		COUNTY ANSON		GEOLOGIST M. Durway						
SITE DESCRIPTION Bridge No. 11 on NC 109 over Deadfall Creek in Anson County						GROUND WTR (ft)						
BORING NO. B2-B		STATION 28+09		OFFSET 12 ft RT		ALIGNMENT -L-						
COLLAR ELEV. 264.5 ft		TOTAL DEPTH 31.6 ft		NORTHING 394,053		EASTING 1,641,578						
DRILL RIG/HAMMER EFF./DATE F&R3495 CME-55 82% 03/01/2019			DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER D. Tignor		START DATE 09/25/19		COMP. DATE 09/25/19		SURFACE WATER DEPTH N/A						
CORE SIZE N		TOTAL RUN 18.0 ft										
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)	
					REC. (%)	RQD (%)	REC. (%)	RQD (%)				ELEV. (ft)
250.9	250.9	13.6	3.0	1:37/1.0 1:41/1.0 1:51/1.0	(2.1) 70%	(1.2) 40%	(0.3) 25%	(0.0) 0%		250.9	13.6	Begin Coring @ 13.6 ft
250	247.9	16.6	5.0	2:03/1.0 2:27/1.0 1:58/1.0 1:40/1.0 1:48/1.0	(5.0) 100%	(4.5) 90%	(9.4) 100%	(7.4) 79%		249.7	14.8	Moderately Severe to Complete Weathering, Medium Hard to Very Soft, Blue-Gray META-ARGILLITE, with Very Close Fracture Spacing GSI=5-15
245	242.9	21.6	5.0	1:59/1.0 1:40/1.0 1:38/1.0 2:42/1.0 2:30/1.0	(5.0) 100%	(3.4) 68%	(0.7) 100%	(0.0) 0%		240.3	24.2	Very Slight to Moderate Weathering, Moderately Hard to Soft, Blue-Gray META-ARGILLITE, with Close to Very Close Fracture Spacing GSI=65-85
240	237.9	26.6	5.0	2:17/1.0 1:48/1.0 1:50/1.0 1:54/1.0 2:15/1.0	(5.0) 100%	(4.6) 92%	(6.7) 100%	(6.3) 94%		239.5	24.9	Moderately Severe to Very Severe Weathering, Medium Hard to Very Soft, Blue-Gray META-ARGILLITE, with Very Close Fracture Spacing GSI=15-25
235	232.9	31.6								232.9	31.6	Very Slight to Moderate Weathering, Moderately Hard to Medium Hard, Blue-Gray META-ARGILLITE, with Close to Very Close Fracture Spacing GSI=50-70
Boring Terminated at Elevation 232.9 ft in NON-CRYSTALLINE ROCK (META-ARGILLITE)												
Notes: Surficial Organic Soil: 0.0-0.1'												



**CORE PHOTOGRAPHS:  
B-5818 | 45771.1.1  
B2-B : -L- Station 28+09, 12' RT**





# GEOTECHNICAL BORING REPORT

## BORE LOG

# GEOTECHNICAL BORING REPORT

## BORE LOG

WBS 45771.1.1		TIP B-5818		COUNTY ANSON		GEOLOGIST M. Durway										
SITE DESCRIPTION Bridge No. 11 on NC 109 over Deadfall Creek in Anson County							GROUND WTR (ft)									
BORING NO. EB2-A		STATION 28+44		OFFSET 5 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 263.3 ft		TOTAL DEPTH 20.9 ft		NORTHING 394,092		EASTING 1,641,583										
DRILL RIG/HAMMER EFF./DATE F&R3495 CME-55 82% 03/01/2019			DRILL METHOD H.S. Augers		HAMMER TYPE Automatic											
DRILLER D. Tignor		START DATE 09/19/19		COMP. DATE 09/19/19		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
265	263.3	0.0	2	6	5									263.3	GROUND SURFACE	0.0
														261.3	ROADWAY EMBANKMENT Red-Brown, Clayey Fine to Coarse SAND (A-2-6) with Little Gravel	2.0
260	259.8	3.5	4	4	3									256.3	ALLUVIAL Gray-Brown-Red, Clayey Fine SAND (A-2-6)	7.0
255	254.8	8.5	17	35	50									251.3	RESIDUAL Gray, Fine Sandy SILT (A-4) with Trace Rock Fragments	12.0
250	249.8	13.5	100/0.2											242.4	WEATHERED ROCK Gray (META-ARGILLITE)	20.9
245	244.8	18.5	100/0.3													
	242.4	20.9	60/0.0													
Boring Terminated with Standard Penetration Test Refusal at Elevation 242.4 ft on NON-CRYSTALLINE ROCK (META-ARGILLITE)  Notes: Surficial Organic Soil: 0.0-0.1'																

WBS 45771.1.1		TIP B-5818		COUNTY ANSON		GEOLOGIST M. Durway										
SITE DESCRIPTION Bridge No. 11 on NC 109 over Deadfall Creek in Anson County							GROUND WTR (ft)									
BORING NO. EB2-B		STATION 28+44		OFFSET 16 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 264.7 ft		TOTAL DEPTH 22.2 ft		NORTHING 394,080		EASTING 1,641,601										
DRILL RIG/HAMMER EFF./DATE F&R3495 CME-55 82% 03/01/2019			DRILL METHOD H.S. Augers		HAMMER TYPE Automatic											
DRILLER D. Tignor		START DATE 09/19/19		COMP. DATE 09/19/19		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
265	264.7	0.0	2	4	3									264.7	GROUND SURFACE	0.0
														261.2	ALLUVIAL Tan-Gray, Silty Fine SAND (A-2-4)	3.5
260	261.2	3.5	8	9	11									257.7	Orange-Tan, Clayey Fine SAND (A-2-6)	7.0
255	256.2	8.5	6	4	5									253.7	RESIDUAL Gray, Fine Sandy SILT (A-4) with Trace Rock Fragments	11.0
250	251.2	13.5	48	27	58									247.7	WEATHERED ROCK Gray (META-ARGILLITE)	17.0
245	246.2	18.5	52	48/0.3										243.9	NON-CRYSTALLINE ROCK Gray (META-ARGILLITE)	20.8
	242.5	22.2	60/0.0											242.5	NON-CRYSTALLINE ROCK Gray (META-ARGILLITE)	22.2
Boring Terminated with Standard Penetration Test Refusal at Elevation 242.5 ft in NON-CRYSTALLINE ROCK (META-ARGILLITE)  Notes: Surficial Organic Soil: 0.0-0.1'																



Bridge No. 11 on NC 109 over Deadfall Creek  
SITE PHOTOGRAPHS



Photograph No. 1: View at End Bent 1 looking north



Photograph No. 3: View of End Bent 2 looking north



Photograph No. 2: View looking south at End Bent 1