PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.04.10391.1, etc.	30	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2484000000-E CONCRETE FLUME WITH GRATE	2549000000-E 2'-6" CURB & GUTTER	2591000000-E 4" CONCRETE SIDEWALK	2600000000-N RETROFIT EXISTING CURB RAMP	2605000000-N CONCRETE CURB RAMP	2613000000-N REMOVE AND REPLACE CURB RAMPS	2752000000-E REMOVE AND REPLACE 2' - 6" CURB & GUTTER	2752000000-E CURB AND GUTTER REMOVAL	2759000000-N REMOVE CURB RAMPS	2815000000-N ADJUST DROP INLET	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX
									MI	FT	SY	TONS	TONS	TON	TONS	LF	LF	SY	EA	EA	EA	LF	LF	EA	EA	EA	EA
2021 CPT.	Gran	1	NC 96 - MLK JR AVE	3RD ST PVT JOINT TO US 15 - HILLSBORO ST	2,4	2	NO	NO	0.58	36-40	125		2,279	153							1						
		2	US 158 BUS - WILLIAMSBORO ST	US 15 - COLLEGE ST TO OXFORD LOOP	3	2	NO	NO	2.22	24-96	512	200	3,772	262	50		9	20	1		1			1			
TOTAL FOR PROJ NO. 2021CPT.05.04.10391.1									**2.8**		**637**	**200**	**6,051**	**415**	**50**		**9**	**20**	**1**		**2**			**1**			
2021CPT.05.04.20391.1	Granville	3	SR 1167 - N. COUNTRY CLUB DR	SR 1170 - IVEY DAY RD TO SR 1004 - HILLSBORO ST	1	2	NO	NO	0.99	22	183		1,171	78	400											3	3
		4	SR 1169 - PINE TREE RD	SR 1195 - INDUSTRY DR TO SR 1004 - HILLSBORO ST	1	2	NO	NO	0.68	20	330		724	49	250											11	
		5	SR 1170 - IVEY DAY RD/GOSHEN ST	US 158 - ROXBORO RD TO SR 1232 - QUAIL RIDGE RD	1	2	NO	NO	1.37	22-36	1,494		1,753	117	150											2	
		6	SR 1206 - BROAD ST	US 15 - HILLSBORO ST TO SR 1232 - ALEXANDER AVE	3	2	NO	NO	0.56	40	211		1,160	78							5						
		7	SR 1207 - W. SPRING ST	SR 1602 - MAIN ST TO SR 1004 - HILLSBORO ST	3	2	NO	NO	0.55	45-60	578		1,460	98			70	62		4	13			4			1
		8	SR 1232 - E. QUALRIDGE RD/ALEXANDER RD	SR 1167 - N. COUNTRY CLUB DR TO US 15	1	2	NO	NO	0.82	20	606		916	61	300												5
		9	SR 1236 - PENN AVE	US 15 TO STANDARD ST	3	2	NO	NO	0.21	48	790		582	39			15	6		2	2			1			
		10	SR 1241 - FARMINGTON DR	US 158 TO CUL-DE-SAC	1	2	NO	NO	0.6	20	84		649	44	250												
		11	SR 1247 - ELLIOTT ST	SR 1241 - FARMINGTON DR. TO CUL-DE-SAC	1	2	NO	NO	0.41	20			442	30	15												
		12	SR 1522 - SALEM RD	US 158 BUS TO US 158 BYP	1	2	NO	NO	0.88	20	163		914	61	150												
		13	SR 1528 - EDGEWOOD RD	SR 1522 - SALEM RD TO SR 1530 - GLENDALE RD	1	2	NO	NO	0.33	20			356	24	20												
		14	SR 1530 - GLENDALE RD	SR 1528 - EDGEWOOD RD TO SR 1531 - HOLLY DR	1	2	NO	NO	0.1	20			102	7	20												
		15	SR 1531 - HOLLY DR	SR 1530 - GLENDALE RD TO CUL-DE-SAC	1	2	NO	NO	0.25	20			299	20	20												
		16	SR 1532 - HICKORY HILL	SR 1531 - HOLLY DR TO SR 1528 - EDGEWOOD RD	1	2	NO	NO	0.07	20			72	5	50												
		17	SR 1535 - TOBACCO RD	US 15 TO DEAD END	1	2	NO	NO	0.19	20	89		194	13	400												
		18	SR 1536 - COUNTRY LN	US 15 TO END MAINT	1	2	NO	NO	0.33	20	82		338	23	200												
		19	SR 1540 - E. MCCLANAHAN ST	NEW COLLEGE ST TO LANIER ST	3	2	NO	NO	0.09	46			211	14													
		20	SR 1602 - HENDERSON/FRONT/MAIN ST	SR 1646 - INDUSTRY DR TO US 158 BUS	3	2	NO	NO	1.5	20	1,057		2,305	154	200				1								
		21	SR 1646 - INDUSTRY DR	NC 96 TO PVT CHANGE	3	2	NO	YES	1.08	26	801		1,733	116													
		22	SR 1665 - E. SPRING ST	US 158 TO PARKER ST	3	2	NO	NO	0.25	44			561	38													
		23	SR 1666 - CRITCHER RD	INDUSTRY DR TO DEAD END	1	2	NO	NO	0.31	20	84		317	21													
TOTAL FOR PROJ NO. 2021CPT.05.04.20391.1									**11.57**		**6,552**		**16,259**	**1,090**	**2,425**		**85**	**68**	**1**	**6**	**20**			**5**		**16**	**9**
2021CPT.05.04.30391.1	Granville	24	E. MCCLANAHAN ST/W. MCCLANAHAN ST	BROAD ST TO NEW COLLEGE ST	6	2	NO	NO	0.28	40			571	38	229							34				1	
		25	E. SPRING ST	MAIN ST TO BELLE ST	5	2	NO	NO	0.16	36	422		330	22	45					3						1	4
		26	E. SPRING ST	BELLE ST TO PARKER ST	1	2	NO	NO	0.39	44	244		932	62	209							64				16	14
		27	E. THORNDALE DR	PINE TREE RD TO DEAD END	1	2	NO	NO	0.12	32	89		196	13	240							9				2	2
		28	GILL ST	WEST OF HUNT ST INTERSECTION TO END MAINT	3	2	NO	NO	0.109	26	144		145	10	22							72				1	1
		29	GOSHEN ST	IVEY DAY RD TO ROXBORO RD	1	2	NO	NO	0.44	25	139		593	40	99							11				7	7
		30	GOSHEN ST	E. QUAIL RIDGE DR TO CHERRY ST	6	2	NO	NO	0.26	27			358	24	164							32				4	4
		31	HANCOCK ST	FRONT ST TO S OF FRANKLIN ST INTERSECTION	6	2	NO	NO	0.22	16			180	12	16							57			2	4	2
		32	HAYS ST	BROAD ST TO COLLEGE ST	6	2	NO	NO	0.13	19			126	8	60							17				2	
		33	HICKS MILL RD	COLLEGE ST TO 25' WEST OF RAIL ROAD TRACKS	1	2	NO	NO	0.051	33	183		103	7	185											1	4
		34	HICKS MILL RD (ALTERNATE B)	DANIEL ST TO 25' WEST OF RR	1	2	NO	NO	0.273	24	300		335	22	175										1	4	5
		35	HICKS MILL RD (ALTERNATE A)	NC 96 TO DANIEL ST	1	2	NO	NO	0.251	24	255		308	21	175											7	4
		36	HUNT DR	MLK, JR. AVE TO WALL ST	6	2	NO	NO	0.08	37			151	10	70												
		37	WALL ST	E SPRING ST TO HILLSBORO ST	3	2	NO	NO	0.104	24			128	9	111											5	2
		38	OLD BAKER ST	GOSHEN ST TO CRESCENT DR	1	2	NO	NO	0.16	25	138		204	14	183							37				9	2
		39	PENN AVE	STANDARD ST TO BROAD ST	3	2	NO	NO	0.1	40			204	14	179							97				1	1
		40	RALEIGH ST	8TH ST TO E. INDUSTRY DR	1	2	NO	NO	0.24	21	117		272	18	14											2	6
		41	SEAMAN ST	E. THORNDALE DR TO WHITFIELD DR	1	2	NO	NO	0.14	33	186		236	16	103							70				3	3
		42	W. THORNDALE DR	S COUNTRY CLUB DR TO PINE TREE RD	3	2	NO	NO	0.13	32			212	14	197							36				1	2
		43	WATKINS ST	COLLEGE ST TO NEW COLLEGE ST	3	2	NO	NO	0.13	20			133	9	88							33				2	
		44	WHITFIELD DR	W OF WARD AVE INTERSECTION TO DEAD END	1	2	NO	NO	0.032	32	84		59	4	22												1
		45	8TH ST	WILMINGTON AVE TO RALEIGH ST		2	NO	NO	0.223	20																	
		46	RALEIGH ST	HIGH ST TO EIGHTH ST		2	NO	NO	0.62	21																	
		47	TUPELO CIR	MEADOW HEIGHTS TO CUL-DE-SAC	1	2	NO	NO	0.03	18			57	4	15											1	1
		48	SR 1602 - MAIN ST	US 158 - WILLIAMSBORO ST TO LITTLE JOHN ST		2	NO	NO	0.08	74						100	180	65		2			115	2			
TOTAL FOR PROJ NO. 2021CPT.05.04.30391.1									**4.753**		**2,301**		**5,833**	**391**	**2,601**	**100**	**180**	**65**		**5**		**569**	**115**	**2**	**3**	**74**	**65**
GRAND TOTAL									**19.123**		**9,490**	**200**	**28,143**	**1,896**	**5,076**	**100**	**274**	**153**	**2**	**11**	**22**	**569**	**115**	**8**	**3**	**90**	**74**