PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.04.10391.1, etc.	32	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING	4457000000-N TEMPORARY TRAFFIC CONTROL	4685000000-E 4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	688000000- 6" X 90 M WHITE THERMO	4695000000-E 8" X 90 M WHITE THERMO	8" X 90 M YELLOW THERMO	4720000000-E THERMO MSG SCHOOL 90 M	THERMO MSG ONLY 90 M	THERMO MSG RXR 90 M	THERMO MSG STOP 90 M	4725000000-E THERMO LT ARROW 90 M	THERMO STR & RT ARROW 90 M	THERMO RT ARROW 90 M	THERMO STR ARROW 90 M	THERMO STR & LT ARROW 90 M	THERMO SYMBOL (SHARROW)	THERMO YIELD TRIANGLE 90M	THERMO HANDICAP PARKING 90 M	4726110000-E HEATED-IN-PLACE THERMO SYMBOL 90 M (HELMETED BICYCLIST)	HEATED-IN-PLACE THERMO SYMBOL 90 MIL (BIKE STR ARROW)	4810000000-E 4" WHITE PAINT	4" YELLOW PAINT
							MI	FT	SF	LS	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF
2021 CPT.	Gran	1	NC 96 - MLK JR AVE	3RD ST PVT JOINT TO US 15 - HILLSBORO ST	2,4	2	0.58	36-40	65	*	241	3,350		490						5	5										
		2	US 158 BUS - WILLIAMSBORO ST	US 15 - COLLEGE ST TO OXFORD LOOP	3	2	2.22	24-96	249		21,455	23,260		700	124					12	5	11	9	2						21,455	23,260
TOTAL FOR PROJ NO. 2021CPT.05.04.10391.1							**2.8**		**314**	*	**21,696**	**26,610**		**1,190**	**124**					**17**	**10**	**11**	**9**	**2**						**21,455**	**23,260**
											48,306			**1,314**						**49**										**44,715**	
2021CPT.05.04.20391.1	Granville	3	SR 1167 - N. COUNTRY CLUB DR	SR 1170 - IVEY DAY RD TO SR 1004 - HILLSBORO ST	1	2	0.99	22	111	*	10,652	10,454																			
		4	SR 1169 - PINE TREE RD	SR 1195 - INDUSTRY DR TO SR 1004 - HILLSBORO ST	1	2	0.68	20	76		7,493	6,970																			
		5	SR 1170 - IVEY DAY RD/GOSHEN ST	US 158 - ROXBORO RD TO SR 1232 - QUAIL RIDGE RD	1	2	1.37	22-36	154		15,005	14,682			87	12				2											
		6	SR 1206 - BROAD ST	US 15 - HILLSBORO ST TO SR 1232 - ALEXANDER AVE	3	2	0.56	40	63		620	6,505		424						8	6											
		7	SR 1207 - W. SPRING ST	SR 1602 - MAIN ST TO SR 1004 - HILLSBORO ST	3	2	0.55	45-60	61		6,673	5,850		632			28			8	6	9	2	10	31			4	4		
		8	1232 - E. QUALRIDGE RD/ALEXANDER	SR 1167 - N. COUNTRY CLUB DR TO US 15	1	2	0.82	20	91		9,000	8,560		40				4							14						
		9	SR 1236 - PENN AVE	US 15 TO STANDARD ST	3	2	0.21	48	23		478	2,478		231			4	4		6	3										
		10	SR 1241 - FARMINGTON DR	US 158 TO CUL-DE-SAC	1	2	0.6	20	67																						
		11	SR 1247 - ELLIOTT ST	SR 1241 - FARMINGTON DR. TO CUL-DE-SAC	1	2	0.41	20	46																						
		12	SR 1522 - SALEM RD	US 158 BUS TO US 158 BYP	1	2	0.88	20	85		8,205	8,026										1		1							
		13	SR 1528 - EDGEWOOD RD	SR 1522 - SALEM RD TO SR 1530 - GLENDALE RD	1	2	0.33	20	36																						
		14	SR 1530 - GLENDALE RD	SR 1528 - EDGEWOOD RD TO SR 1531 - HOLLY DR	1	2	0.1	20	11																						
		15	SR 1531 - HOLLY DR	SR 1530 - GLENDALE RD TO CUL-DE-SAC	1	2	0.25	20	28																						
		16	SR 1532 - HICKORY HILL	SR 1531 - HOLLY DR TO SR 1528 - EDGEWOOD RD	1	2	0.07	20	8																						
		17	SR 1535 - TOBACCO RD	US 15 TO DEAD END	1	2	0.19	20	21									2													
		18	SR 1536 - COUNTRY LN	US 15 TO END MAINT	1	2	0.33	20	37																						
		19	SR 1540 - E. MCCLANAHAN ST	NEW COLLEGE ST TO LANIER ST	3	2	0.09	46	10		50	809		115						1	1										
		20	SR 1602 - HENDERSON/FRONT/MAIN ST	SR 1646 - INDUSTRY DR TO US 158 BUS	3	2	1.5	20	168		10,005	9,880	480	850	510					4		3	6			5	2				
		21	SR 1646 - INDUSTRY DR	NC 96 TO PVT CHANGE	3	2	1.08	26	121		11,540	10,100		140	260					5		4	2								
		22	SR 1665 - E. SPRING ST	US 158 TO PARKER ST	3	2	0.25	44	28		5,860	2,640								3	3				1			4	4		
		23	SR 1666 - CRITCHER RD	INDUSTRY DR TO DEAD END	1	2	0.31	20	34																						
TOTAL FOR PROJ NO. 2021CPT.05.04.20391.1							**11.57**		**1,279**	*	**85,581**	**86,954**	**480**	**2,432**	**857**	**12**	**32**	**10**		**37**	**19**	**17**	**10**	**11**	**46**	**5**	**2**	**8**	**8**		
											172,535			**3,289**		**54**				**147**								**16**			
2021CPT.05.04.30391.1	Granville	24	. MCCLANAHAN ST/W. MCCLANAHAN S	BROAD ST TO NEW COLLEGE ST	6	2	0.28	40	31	*	895	2,760		282						7	7										
		25	E. SPRING ST	MAIN ST TO BELLE ST	5	2	0.16	36	19					417											15						
		26	E. SPRING ST	BELLE ST TO PARKER ST	1	2	0.39	44	44		9,017	2,096								2	2				2			11	11		
		27	E. THORNDALE DR	PINE TREE RD TO DEAD END	1	2	0.12	32	13																						
		28	GILL ST	WEST OF HUNT ST INTERSECTION TO END MAINT	3	2	0.109	26	8																						
		29	GOSHEN ST	IVEY DAY RD TO ROXBORO RD	1	2	0.44	25	50		360	721																			
		30	GOSHEN ST	E. QUAIL RIDGE DR TO CHERRY ST	6	2	0.26	27	30																						
		31	HANCOCK ST	FRONT ST TO S OF FRANKLIN ST INTERSECTION	6	2	0.22	16	25					45																	
		32	HAYS ST	BROAD ST TO COLLEGE ST	6	2	0.13	19	15					76																	
		33	HICKS MILL RD	COLLEGE ST TO 25' WEST OF RAIL ROAD TRACKS	1	2	0.051	33	6									2													
		34	HICKS MILL RD (ALTERNATE B)	DANIEL ST TO 25' WEST OF RR	1	2	0.273	24	31									2													
		35	HICKS MILL RD (ALTERNATE A)	NC 96 TO DANIEL ST	1	2	0.251	24	29																						
		36	HUNT DR	MLK, JR. AVE TO WALL ST	6	2	0.08	37	9		410	575		80																	
		37	WALL ST	E SPRING ST TO HILLSBORO ST	3	2	0.104	24	12					103					4												
		38	OLD BAKER ST	GOSHEN ST TO CRESCENT DR	1	2	0.16	25	18																						
		39	PENN AVE	STANDARD ST TO BROAD ST	3	2	0.1	40	11		80	1,062		91						3	2										
		40	RALEIGH ST	8TH ST TO E. INDUSTRY DR	1	2	0.24	21	27		2,248	1,127													13						
		41	SEAMAN ST	E. THORNDALE DR TO WHITFIELD DR	1	2	0.14	33	15																						
		42	W. THORNDALE DR	S COUNTRY CLUB DR TO PINE TREE RD	3	2	0.13	32	15																						
		43	WATKINS ST	COLLEGE ST TO NEW COLLEGE ST	3	2	0.13	20	15					56																	
		44	WHITFIELD DR	W OF WARD AVE INTERSECTION TO DEAD END	1	2	0.032	32	1																						
		45	8TH ST	WILMINGTON AVE TO RALEIGH ST		2	0.223	20	25		2,390	977																			
		46	RALEIGH ST	HIGH ST TO EIGHTH ST		2	0.62	21	70		2,669	2,982		259											37						
		47	TUPELO CIR	MEADOW HEIGHTS TO CUL-DE-SAC	1	2	0.03	18	4																						
		48	SR 1602 - MAIN ST	US 158 - WILLIAMSBORO ST TO LITTLE JOHN ST		2	0.08	74	8																						
TOTAL FOR PROJ NO. 2021CPT.05.04.30391.1							**4.753**		**531**	*	**18,069**	**12,300**		**1,409**				**4**	**4**	**12**	**11**				**67**			**11**	**11**		
											30,369			**1,409**		**8**				**90**								**22**			
GRAND TOTAL							**19.123**		**2,124**	**1.00**	**125,346**	**125,864**	**480**	**5,031**	**981**	**12**	**32**	**14**	**4**	**66**	**40**	**28**	**19**	**13**	**113**	**5**	**2**	**19**	**19**	**21,455**	**23,260**
											251,210			**6,012**		**62**				**286**								**38**		**44,715**	