



- CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 08**
- NOTE:** PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE:** PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE:** INSTALL FABRIC INSERT INLET PROTECTION DEVICE IN LIEU OF ROCK INLET SEDIMENT TRAP TYPE 'C' AS DIRECTED.

-L- CURVE DATA

PI Sta 58+73.49	PI Sta 63+53.16
$\Delta = 48^{\circ} 58' 28.3" (RT)$	$\Delta = 33^{\circ} 33' 45.4" (LT)$
$D = 19^{\circ} 25' 20.3"$	$D = 4^{\circ} 46' 28.7"$
$L = 252.16'$	$L = 702.93'$
$T = 134.36'$	$T = 361.87'$
$R = 295.00'$	$R = 1,200.00'$
$DS = 20 \text{ MPH} **$	$DS = 40 \text{ MPH}$
$e = \text{EXIST.}$	$e = \text{EXIST.}$

\*\* DESIGN EXCEPTION FOR HORIZONTAL CURVE REQUIRED

5/18/2020 8:44:41 AM U:\5887\_Env\_EC8.dgn