


BM #1: R.R. SPIKE IN 18" GUM TREE, 59.06' RT. OF STA. 23+89.93 -L-, EL. 38.64



LOCATION SKETCH

NOTES

ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING.  
 THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 8TH EDITION.  
 THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.  
 FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.  
 FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.  
 FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.  
 FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.  
 FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.  
 THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE SAMPLE BARS SHOULD COME FROM STEEL ACTUALLY USED IN THE PROJECT AND THE SAMPLE BARS SHOULD BE REPLACED BY SPLICED BARS AS SPECIFIED IN THE SAMPLE BAR REPLACEMENT CHART. PAYMENT FOR THE SAMPLE BARS AND REPLACEMENT REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.  
 PRESTRESSED CONCRETE DECK PANELS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.  
 REMOVABLE FORMS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.  
 NEEDLE BEAMS WILL NOT BE ALLOWED UNLESS OTHERWISE CALLED FOR ON THE PLANS OR APPROVED BY THE ENGINEER.  
 INASMUCH AS THE PAINT SYSTEM ON THE EXISTING STRUCTURAL STEEL CONTAINS LEAD, THE CONTRACTOR'S ATTENTION IS DIRECTED TO ARTICLE 107-1 OF THE STANDARD SPECIFICATIONS. ANY COSTS RESULTING FROM COMPLIANCE WITH APPLICABLE STATE OR FEDERAL REGULATIONS PERTAINING TO HANDLING OF MATERIALS CONTAINING LEAD BASED PAINT SHALL BE INCLUDED IN THE BID PRICE FOR "REMOVAL OF EXISTING STRUCTURE AT STATION 30+80.00 -L-."  
 FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.  
 MATERIAL SHOWN IN THE HATCHED AREA ON SHEET 1 OF 3 SHALL BE EXCAVATED TO A DISTANCE OF 40 FT± LEFT AND 42 FT± RIGHT OF CENTERLINE ROADWAY AT END BENT 1, AND 32 FT± LEFT AND 41 FT± RIGHT AT END BENT 2 AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR UNCLASSIFIED STRUCTURE EXCAVATION. SEE SECTION 412 OF THE STANDARD SPECIFICATIONS.  
 THE EXISTING STRUCTURE CONSISTING OF 9 SPANS (50'-3", 7 @ 50'-0", 50'-3"); CLEAR ROADWAY WIDTH OF 22'-0" ON A REINFORCED CONCRETE DECK AND STEEL I-BEAM SUPERSTRUCTURE; END BENTS AND INTERIOR BENTS WITH REINFORCED CONCRETE CAPS STEEL H-PILES, AND LOCATED AT THE SITE OF THE PROPOSED STRUCTURE SHALL BE REMOVED. THE EXISTING BRIDGE IS PRESENTLY POSTED FOR LOAD LIMIT. SHOULD THE STRUCTURAL INTEGRITY OF THE BRIDGE DETERIORATE DURING CONSTRUCTION OF THE PROPOSED BRIDGE, A LOAD LIMIT MAY BE POSTED AND MAY BE REDUCED AS FOUND NECESSARY DURING THE LIFE OF THE PROJECT.  
 THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE, SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.  
 REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED IN A MANNER THAT PREVENTS DEBRIS FROM FALLING INTO THE WATER. THE CONTRACTOR SHALL SUBMIT DEMOLITION PLANS FOR REVIEW AND REMOVE THE BRIDGE IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.  
 THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH "HEC 18-EVALUATING SCOUR AT BRIDGES."  
 FOR ASBESTOS ASSESSMENT FOR BRIDGE DEMOLITION AND RENOVATION ACTIVITIES, SEE SPECIAL PROVISIONS.  
 FOR CONSTRUCTION, MAINTENANCE AND REMOVAL OF TEMPORARY ACCESS, SEE SPECIAL PROVISIONS.  
 PILE CUSHIONS ARE REQUIRED FOR DRIVING STEEL PILES FOR THE TEMPORARY WORK BRIDGE AND THE DRILLED SHAFT CASING TEMPLATES. THE COST OF PILE CUSHIONS SHALL BE CONSIDERED INCIDENTAL TO THE TEMPORARY WORK BRIDGE, SEE SPECIAL PROVISIONS.

TOTAL BILL OF MATERIAL

|                | CONSTRUCTION, MAINTENANCE & REMOVAL OF TEMPORARY ACCESS AT STA. 30+80.00 -L- | REMOVAL OF EXISTING STRUCTURE AT STA. 30+80.00 -L- | ASBESTOS ASSESSMENT | 4'-6" Ø DRILLED PIERS | PERMANENT STEEL CASING FOR 4'-6" Ø DRILLED PIER | PDA TESTING | SID INSPECTION | SPT TESTING | CSL TESTING | UNCLASSIFIED STRUCTURE EXCAVATION AT STA. 30+80.00 -L- | REINFORCED CONCRETE DECK SLAB | GROOVING BRIDGE FLOORS | CLASS A CONCRETE | BRIDGE APPROACH SLABS STA. 30+80.00 -L- | REINFORCING STEEL | SPIRAL COLUMN REINFORCING STEEL |
|----------------|------------------------------------------------------------------------------|----------------------------------------------------|---------------------|-----------------------|-------------------------------------------------|-------------|----------------|-------------|-------------|--------------------------------------------------------|-------------------------------|------------------------|------------------|-----------------------------------------|-------------------|---------------------------------|
|                | LUMP SUM                                                                     | LUMP SUM                                           | LUMP SUM            | LIN. FT.              | LIN. FT.                                        | EACH        | EACH           | EACH        | EACH        | LUMP SUM                                               | SQ. FT.                       | SQ. FT.                | CU. YDS.         | LUMP SUM                                | LBS.              | LBS.                            |
| SUPERSTRUCTURE |                                                                              |                                                    |                     |                       |                                                 |             |                |             |             |                                                        | 17,592                        | 15,633                 |                  |                                         |                   |                                 |
| END BENT 1     |                                                                              |                                                    |                     |                       |                                                 |             |                |             |             | LUMP SUM                                               |                               |                        | 30.4             |                                         | 4,241             |                                 |
| BENT 1         |                                                                              |                                                    |                     | 184.0                 | 44.0                                            |             |                |             | 1           |                                                        |                               |                        | 44.3             |                                         | 26,080            | 6,064                           |
| BENT 2         |                                                                              |                                                    |                     | 184.0                 | 44.0                                            |             |                |             | 1           |                                                        |                               |                        | 44.5             |                                         | 26,123            | 6,079                           |
| BENT 3         |                                                                              |                                                    |                     | 184.0                 | 44.0                                            |             |                |             | 1           |                                                        |                               |                        | 44.5             |                                         | 26,123            | 6,079                           |
| BENT 4         |                                                                              |                                                    |                     | 177.0                 | 35.0                                            |             |                |             | 1           |                                                        |                               |                        | 42.9             |                                         | 25,230            | 5,772                           |
| END BENT 2     |                                                                              |                                                    |                     |                       |                                                 |             |                |             |             | LUMP SUM                                               |                               |                        | 30.4             |                                         | 4,241             |                                 |
| TOTAL          | LUMP SUM                                                                     | LUMP SUM                                           | LUMP SUM            | 729.0                 | 167.0                                           | 1           | 2              | 3           | 4           | LUMP SUM                                               | 17,592                        | 15,633                 | 237.0            | LUMP SUM                                | 112,038           | 23,994                          |

SAMPLE BAR REPLACEMENT

|     |         |
|-----|---------|
| #3  | 6'-2"   |
| #4  | 7'-4"   |
| #5  | 8'-6"   |
| #6  | 9'-8"   |
| #7  | 10'-10" |
| #8  | 12'-0"  |
| #9  | 13'-2"  |
| #10 | 14'-6"  |
| #11 | 15'-10" |

NOTE: SAMPLE BAR REPLACEMENT LENGTHS BASED ON 30" (SAMPLE LENGTH) PLUS TWO SPLICE LENGTHS AND fy = 60KSI.

HYDRAULIC DATA

DESIGN DISCHARGE = 32,400 CFS  
 FREQUENCY OF DESIGN DISCHARGE = 25 YEARS  
 DESIGN HIGH WATER ELEVATION = 48.8  
 DRAINAGE AREA = 2,600 SQ. MI.  
 BASE DISCHARGE (Q100) = 44,000 CFS  
 BASE HIGH WATER ELEVATION = 51.2

OVERTOPPING DATA

OVERTOPPING DISCHARGE = 24,500 CFS  
 FREQUENCY OF OVERTOPPING = 10- YEARS  
 \* OVERTOPPING ELEVATION = 46.8  
 \* OVERTOPPING WOULD OCCUR AT STA. 55+30.00 -L-

TOTAL BILL OF MATERIAL

|                | PILE DRIVING EQUIPMENT SETUP FOR HP 12 X 53 STEEL PILES | HP 12 X 53 STEEL PILES | PILE REDRIVES | CONCRETE BARRIER RAIL | RIP RAP CLASS II (2'-0" THICK) | GEOTEXTILE FOR DRAINAGE | ELASTOMERIC BEARINGS | FOAM JOINT SEALS | 36" FLORIDA I-BEAM (FIB) GIRDERS |     |          |
|----------------|---------------------------------------------------------|------------------------|---------------|-----------------------|--------------------------------|-------------------------|----------------------|------------------|----------------------------------|-----|----------|
|                | EACH                                                    | NO.                    | LIN. FT.      | EACH                  | LIN. FT.                       | TONS                    | SQ. YDS.             | LUMP SUM         | LUMP SUM                         | NO. | LIN. FT. |
| SUPERSTRUCTURE |                                                         |                        |               |                       | 919.5                          |                         |                      |                  |                                  | 20  | 1,833.33 |
| END BENT 1     | 7                                                       | 7                      | 539           | 4                     |                                | 211                     | 234                  |                  |                                  |     |          |
| BENT 1         |                                                         |                        |               |                       |                                |                         |                      |                  |                                  |     |          |
| BENT 2         |                                                         |                        |               |                       |                                |                         |                      |                  |                                  |     |          |
| BENT 3         |                                                         |                        |               |                       |                                |                         |                      |                  |                                  |     |          |
| BENT 4         |                                                         |                        |               |                       |                                |                         |                      |                  |                                  |     |          |
| END BENT 2     | 7                                                       | 7                      | 539           | 4                     |                                | 254                     | 283                  |                  |                                  |     |          |
| TOTAL          | 14                                                      | 14                     | 1,078         | 8                     | 919.5                          | 465                     | 517                  | LUMP SUM         | LUMP SUM                         | 20  | 1,833.33 |



111 E. Hargett Street Suite 300 Raleigh, NC 27601 919-714-8670 meadhunt.com NC License No. F-1235



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PROJECT NO. B-5619

LENOIR COUNTY

STATION: 30+80.00 -L-

SHEET 3 OF 3

STATE OF NORTH CAROLINA  
 DEPARTMENT OF TRANSPORTATION  
 RALEIGH  
**GENERAL DRAWING**  
 FOR BRIDGE OVER NEUSE RIVER  
 ON SR 1389 BETWEEN  
 SR 1300 AND SR 1307

| REVISIONS |     |       |     |     |       | SHEET NO.    |
|-----------|-----|-------|-----|-----|-------|--------------|
| NO.       | BY: | DATE: | NO. | BY: | DATE: | S1-03        |
| 1         |     |       | 3   |     |       | TOTAL SHEETS |
| 2         |     |       | 4   |     |       | 40           |

DRAWN BY : J.S. HOBSON DATE : 12/17/20  
 CHECKED BY : J.A. BOYER DATE : 12/20/20  
 DESIGN ENGINEER OF RECORD : J.S. HOBSON DATE : 02/09/21