

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
B-5626	X-1A

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)														
L																
18+50.00	0	0														
19+00.00	2	13														
19+50.00	3	32														
20+00.00	1	58														
20+50.00	0	102														
21+00.00	0	141														
21+50.00	0	159														
22+00.00	0	191														
22+50.00	0	191														
23+00.00	0	160														
23+02.75	0	9														
23+14.01	0	18														
			Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing asphalt pavement will be paid for at the contract lump sum price for "Grading".													
Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)														
L																
24+29.02	0	0														
24+40.25	0	14														
24+50.00	0	24														
25+00.00	0	111														
25+50.00	1	104														
26+00.00	8	91														
26+50.00	15	52														
27+00.00	14	25														
27+50.00	13	17														
28+00.00	6	7														

Earthwork quantities are calculated by the Roadway Design Unit. These quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.