PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.22.20921.1	26	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW	0264000000-E SHOULDER GRADING	1220000000-E INCIDENTAL STONE BASE	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1.25" MILLING	1297000000-E 1½" MILLING	1308000000-E 0" TO 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1519000000-E SURFACE COURSE, S9.5B	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2549000000-E 2'-6" CURB & GUTTER	2591000000-E 4" CONCRETE SIDEWALK	2600000000-N RETROFIT EXISTING CURB RAMP	2613000000-N REMOVE AND REPLACE CURB RAMPS	2759000000-N GENERIC PAVING ITEM, REMOVE CURB RAMPS	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE	6084000000-E SEED & MULCHING	6117000000-N RESPONSE FOR EROSION CONTROL	7444000000-E INDUCTIVE LOOP SAWCUT
								D	MI	FT	CY	SMI	TONS	TON	SY	SY	SY	SY	TONS	TON	TONS	LF	SY	EA	EA	EA	EA	EA	LF	LF	AC	EA	LF
2021CPT.05.22.20921.1	Wake	1	SR 1003 - ROLESVILLE RD	SR 2324 - ROBERTSON POND TO SR 5446 - KIOTI DR	2	2	NO	NO	0.56	36-52	11	1.12	28	83				663	1,193	80	240								16	50	0.16		
		2	SR 2045 - BURLINGTON MILLS RD	US 1 TO SR 2049 - FORESTVILLE RD	2	2	NO	NO	2.59	24-48	59	4.00	99	255			2,889	966	5,224	350	465	40	16		4	2	2	9	86	220	0.86	1	1,944
		3	SR 2050 - LILLIE LILES RD	SR 2049 - FORESTVILLE RD TO US 401 - LOUISBURG RD	2	2	NO	NO	0.86	21	65	1.72	43	40				123	965	65	326								94	240	0.94		
		4	SR 2327 - PRIVETTE RD	SR 2300 - EDGEMONT RD TO END MAINT	1	2	NO	NO	0.33	20	3	0.65	16	54				231	278	19	295								5	20	0.05		
		5	SR 2337 - PIPPIN RD/DEBNAM RD	NC 39 TO BEG C&G	1	2	NO	NO	3.36	20	168	7.00		310	781			250	2,909	195	380								244	620	2.44	1	
		6	SR 2339 - ROSINBURG RD	FRANKLIN CO TO DEAD END	1	2	NO	NO	3.05	20	152	6.00	152	281	184			981	2,681	180	15								222	560	2.22	1	
		7	SR 2340 - OAKLEY RD	SR 2339 - ROSINBURG RD TO SR 2449 - PATRICIAN WAY	1	2	NO	NO	1.93	20	145	4.00	96	89				554	1,670	112	20								210	530	2.10	1	
		8	SR 2341 - PARKS VILLAGE RD	SR 2337 - DEBNAM RD TO SR 2320 - OLD BUNN RD	1	2	NO	NO	1.30	20	130	2.60	70					387	1,129	76									189	480	1.89	1	
		9	SR 2345 - E HORTON ST	NC 96 TO END C&G	4	2	NO	NO	0.13	20			7	14		1,525		163	133	9				2									
		10	SR 2345 - E HORTON ST	END C&G TO RR	2	2	NO	NO	0.57	20	23	1.14	29	63				176	591	40	10			1			3	2	33	90	0.33		
		11	SR 2361 - OLD NOWELL RD/COLONIAL DR	SR 2424 - WYTHE LN TO SR 1003 EAGLE ROCK RD	1	2	NO	NO	1.06	20	105	2.10	53					300	930	62	186								153	390	1.53	1	
		12	SR 2362 - INDUSTRIAL DR	US 64 BUS -WENDELL BLVD TO EAST ST	2	2	NO	NO	0.29	18	29	0.42	15					353	269	18	158						2	1	42	110	0.42		
		13	SR 2363 - INDUSTRIAL DR	EAST ST TO END PVMT	2	2	NO	NO	0.10	20	10	0.20	5					75	102	7	19						2	3	15	40	0.15		
		14	SR 2364 - LILES DEAN RD	US 64 BUS - WENDELL BLVD TO US 64 BUS -WENDELL BLVD	1	2	NO	NO	1.13	20	113	2.27	57					139	984	66	350			3	3				165	420	1.65	1	220
		15	SR 2388 - RIDGE HAVEN DR	SR 1003 - ROLESVILLE RD TO SR 2396 - DAMASCUS DR	1	2	NO	NO	0.69	22	69	1.37	34					153	643	43	330								100	250	1.00		
		16	SR 2424 - WYTHE LN	END MAINT TO CUL-DE-SAC	1	2	NO	NO	0.53	20	53	1.06	27					133	483	32	280								77	200	0.77		
		17	SR 2453 - SANDY WOODS DR	SR 2307 - LASSITER RD TO CUL-DE-SAC	1	2	NO	NO	0.41	18	41	0.82	21					63	343	23	160								60	150	0.60		
		18	SR 2454 - MARCY CT	SR 2453 - SANDY WOODS DR TO CUL-DE-SAC	1	2	NO	NO	0.09	18	9	0.18	5						94	6	5								13	40	0.13		
		19	SR 2907 - GREENBROOK DR	SR 2217 - OLD MILBURNIE TO CUL-DE-SAC	1	2	NO	NO	0.62	18	62	1.24	31					125	506	34	295								90	230	0.90		
		20	SR 2926 - OAKWOOD CT	SR 2907 - GREENBROOK DR TO CUL-DE-SAC	1	2	NO	NO	0.05	16	5	0.11	3						59	4	5								8	20	0.08		
		21	SR 2927 - PINEWOOD CT	SR 2907 - GREENBROOK DR TO CUL-DE-SAC	1	2	NO	NO	0.07	16	7	0.14	3						69	5	5								10	30	0.10		
		22	SR 2928 - VALLEY CT	SR 2907 - GREENBROOK DR TO CUL-DE-SAC	1	2	NO	NO	0.07	16	7	0.13	3						64	4	10								10	30	0.10		
		23	SR 3608 - DEERCHASE TRL	SR 2045 - BURLINGTON MILLS RD TO CUL-DE-SAC	1	2	NO	NO	0.17	20	17	0.33	8					100	188	13	30						3	6	24	60	0.24		
		24	SR 3609 - BUCK RUN TRL	CUL-DE-SAC TO CUL-DE-SAC	1	2	NO	NO	0.61	20	61	1.22	31						563	38	235						16	2	89	230	0.89		
		25	SR 3610 - BAMBI CT	SR 3609 - BUCK RUN TRL TO CUL-DE-SAC	1	2	NO	NO	0.06	20	6	0.13	3						81	5	20						1	4	9	30	0.09		
		26	SR 3661 - TROPHY TRL	SR 2045 - BURLINGTON MILLS RD TO SR 3609 - BUCK RUN TRL	1	2	NO	NO	0.16	20	16	0.32	8					47	146	10	60						3		23	60	0.23		
		27	SR 3662 - DASHER CT	SR 3609 - BUCK RUN TRL TO CUL-DE-SAC	1	2	NO	NO	0.05	20	5	0.11	3						48	3	5						1		8	20	0.08		
		28	SR 3663 - TEN POINT TRL	SR 3664 - DONNER TRAIL TO DEAD END	1	2	NO	NO	0.26	20	26	0.52	13						223	15	60						3		38	100	0.38		
		29	SR 3664 - DONNER TRL	CUL-DE-SAC TO CUL-DE-SAC	1	2	NO	NO	0.39	20	39	0.78	20						387	26	70						9		57	150	0.57		
		30	SR 3665 - PRANCER CT	SR 3664 - DONNER TRL TO CUL-DE-SAC	1	2	NO	NO	0.09	20	9	0.17	4						101	7	16						3	2	12	40	0.12		
		31	SR 3666 - WHITE FLAG WAY	SR 3664 - DONNER TRAIL TO CUL-DE-SAC	1	2	NO	NO	0.10	20	10	0.19	5						109	7	6								14	40	0.14		
		32	SR 3667 - DEER LAKE TRL	SR 3609 - BUCK RUN TRL TO END MAINT	1	2	NO	NO	0.26	20	26	0.52	13					69	235	16	140						3	2	38	100	0.38		
		33	SR 3668 - CLOVEN CT	SR 3663 - TEN POINT TRL TO CUL-DE-SAC	1	2	NO	NO	0.09	20	9	0.17	4						106	7	35						3		11	40	0.13		
		34	SR 3669 - ELF CT	SR 3663 - TEN POINT TRL TO CUL-DE-SAC	1	2	NO	NO	0.08	20	8	0.16	4						93	6	7						4		11	30	0.11		
		35	SR 4318 - CATLETT FARM RD	SR 1003 - ROLESVILLE RD TO END MAINT	1	2	NO	NO	0.30	18	30	0.60	15					149	262	18	175								44	110	0.44		
		36	SR 5144 - HERITAGE LAKE RD	SR 2052 - ROGERS RD TO PVMT JOINT	3	2	NO	NO	0.90	32--65	90	1.80	45			22,199		768	1,995	134	470	91	39	9	9	5	2		131	330	1.31		1,184
TOTAL FOR PROJ NO. 2021CPT.05.22.20921.1									**23.29**		**1,618**	**45.29**	**973**	**1,189**	**965**	**23,724**	**2,889**	**6,968**	**25,856**	**1,735**	**4,883**	**131**	**55**	**15**	**16**	**7**	**60**	**31**	**2,351**	**6,060**	**23.53**	**7**	**3,348**
GRAND TOTAL									**23.29**		**1,618**	**45.29**	**973**	**1,189**	**965**	**23,724**	**2,889**	**6,968**	**25,856**	**1,735**	**4,883**	**131**	**55**	**15**	**16**	**7**	**60**	**31**	**2,351**	**6,060**	**23.53**	**7**	**3,348**