PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.22.20921.1	27	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING	4447000000-E PEDESTRIAN CHANNELIZING DEVICES	4457000000-N TEMPORARY TRAFFIC CONTROL	4685000000-E 4" X 90 M WHITE THERMO	4685000000-E 4" X 90 M YELLOW THERMO	4695000000-E 8" X 90 M YELLOW THERMO	4695000000-E 8" X 90 M WHITE THERMO	4700000000-E 12" X 90 M YELLOW THERMO	4720000000-E THERMO MSG SCHOOL 90 M	4720000000-E THERMO MSG STOP 90 M	4720000000-E THERMO MSG AHEAD 90 M	4720000000-E THERMO HANDICAP SYMBOL 90 M	4720000000-E THERMO MSG RXR 90 M	4720000000-E THERMO MSG ONLY 90 M	4725000000-E THERMO RT ARROW 90 M	4725000000-E THERMO LT ARROW 90 M	4725000000-E THERMO STR ARROW 90 M	4725000000-E THERMO STR & RT ARROW 90 M	4810000000-E 4" YELLOW PAINT	4810000000-E 4" WHITE PAINT	4820000000-E 8" WHITE PAINT	4820000000-E 8" YELLOW PAINT	4835000000-E 24" WHITE PAINT	4850000000-E 4" LINE REMOVAL	4890000000-E HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES, 4", 50 MIL	4891000000-E GENERIC MARKING. 24" X 90 M WHITE THERMO	4891000000-E GENERIC MARKING. 16" X 90 M WHITE THERMO
							MI	FT	SF	LF	LS	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	LF	LF	LF	LF	LF
2021CPT.05.22.20921.1	Wake	1	SR 1003 - ROLESVILLE RD	SR 2324 - ROBERTSON POND TO SR 5446 - KIOTI DR	2	2	0.56	36-52	63		0.07	7,436	7,546	102			6						6	9										20	
		2	SR 2045 - BURLINGTON MILLS RD	US 1 TO SR 2049 - FORESTVILLE RD	2	2	2.59	24-48	290		0.20	27,868	39,950			1,500							4	18	4	1						1,470	1,470	68	
		3	SR 2050 - LILLIE LILES RD	SR 2049 - FORESTVILLE RD TO US 401 - LOUISBURG RD	2	2	0.86	21	93		0.04	9,254	9,082		160								1											22	
		4	SR 2327 - PRIVETTE RD	SR 2300 - EDGEMONT RD TO END MAINT	1	2	0.33	20	37		0.01																								
		5	SR 2337 - PIPPIN RD/DEBNAM RD	NC 39 TO BEG C&G	1	2	3.36	20	376		0.07	36,132	32,753			68																			
		6	SR 2339 - ROSINBURG RD	FRANKLIN CO TO DEAD END	1	2	3.05	20	341		0.05	32,775	32,166					8	10															40	
		7	SR 2340 - OAKLEY RD	SR 2339 - ROSINBURG RD TO SR 2449 - PATRICIAN WAY	1	2	1.93	20	216		0.05	20,756	20,370																						
		8	SR 2341 - PARKS VILLAGE RD	SR 2337 - DEBNAM RD TO SR 2320 - OLD BUNN RD	1	2	1.30	20	145		0.04	13,966	13,706																						
		9	SR 2345 - E HORTON ST	NC 96 TO END C&G	4	2	0.13	20	15		0.01	120	1,372	276	250						1						1,372	120	250	276	22			22	
		10	SR 2345 - E HORTON ST	END C&G TO RR	2	2	0.57	20	64		0.02	6,133	6,020									6												80	182
		11	SR 2361 - OLD NOWELL RD/COLONIAL DR	SR 2424 - WYTHE LN TO SR 1003 EAGLE ROCK RD	1	2	1.06	20	118		0.04	8,200	8,292																						
		12	SR 2362 - INDUSTRIAL DR	US 64 BUS -WENDELL BLVD TO EAST ST	2	2	0.29	18	32		0.01	3,120	3,062																						
		13	SR 2363 - INDUSTRIAL DR	EAST ST TO END PVMT	2	2	0.10	20	11		0.01	1,076	1,056																						
		14	SR 2364 - LILES DEAN RD	US 64 BUS - WENDELL BLVD TO US 64 BUS -WENDELL BLVD	1	2	1.13	20	127		0.04	12,191	11,964				12																		
		15	SR 2388 - RIDGE HAVEN DR	SR 1003 - ROLESVILLE RD TO SR 2396 - DAMASCUS DR	1	2	0.69	22	77		0.03																								
		16	SR 2424 - WYTHE LN	END MAINT TO CUL-DE-SAC	1	2	0.53	20	60		0.02																								
		17	SR 2453 - SANDY WOODS DR	SR 2307 - LASSITER RD TO CUL-DE-SAC	1	2	0.41	18	46		0.01																								
		18	SR 2454 - MARCY CT	SR 2453 - SANDY WOODS DR TO CUL-DE-SAC	1	2	0.09	18	10		0.01																								
		19	SR 2907 - GREENBROOK DR	SR 2217 - OLD MILBURNIE TO CUL-DE-SAC	1	2	0.62	18	69	60	0.02																								
		20	SR 2926 - OAKWOOD CT	SR 2907 - GREENBROOK DR TO CUL-DE-SAC	1	2	0.05	16	6		0.01																								
		21	SR 2927 - PINEWOOD CT	SR 2907 - GREENBROOK DR TO CUL-DE-SAC	1	2	0.07	16	8		0.01																								
		22	SR 2928 - VALLEY CT	SR 2907 - GREENBROOK DR TO CUL-DE-SAC	1	2	0.07	16	8		0.01																								
		23	SR 3608 - DEERCHASE TRL	SR 2045 - BURLINGTON MILLS RD TO CUL-DE-SAC	1	2	0.17	20	18		0.01																								
		24	SR 3609 - BUCK RUN TRL	CUL-DE-SAC TO CUL-DE-SAC	1	2	0.61	20	68		0.02																								
		25	SR 3610 - BAMBI CT	SR 3609 - BUCK RUN TRL TO CUL-DE-SAC	1	2	0.06	20	7		0.01																								
		26	SR 3661 - TROPHY TRL	SR 2045 - BURLINGTON MILLS RD TO SR 3609 - BUCK RUN TRL	1	2	0.16	20	18		0.01																								
		27	SR 3662 - DASHER CT	SR 3609 - BUCK RUN TRL TO CUL-DE-SAC	1	2	0.05	20	6		0.01																								
		28	SR 3663 - TEN POINT TRL	SR 3664 - DONNER TRAIL TO DEAD END	1	2	0.26	20	29		0.01																								
		29	SR 3664 - DONNER TRL	CUL-DE-SAC TO CUL-DE-SAC	1	2	0.39	20	44		0.02																								
		30	SR 3665 - PRANCER CT	SR 3664 - DONNER TRL TO CUL-DE-SAC	1	2	0.09	20	10		0.01																								
		31	SR 3666 - WHITE FLAG WAY	SR 3664 - DONNER TRAIL TO CUL-DE-SAC	1	2	0.10	20	11		0.01																								
		32	SR 3667 - DEER LAKE TRL	SR 3609 - BUCK RUN TRL TO END MAINT	1	2	0.26	20	29		0.01																								
		33	SR 3668 - CLOVEN CT	SR 3663 - TEN POINT TRL TO CUL-DE-SAC	1	2	0.09	20	9		0.01																								
		34	SR 3669 - ELF CT	SR 3663 - TEN POINT TRL TO CUL-DE-SAC	1	2	0.08	20	9		0.01																								
		35	SR 4318 - CATLETT FARM RD	SR 1003 - ROLESVILLE RD TO END MAINT	1	2	0.30	18	127		0.01																								
		36	SR 5144 - HERITAGE LAKE RD	SR 2052 - ROGERS RD TO PVMT JOINT	3	2	0.90	32-65	101		0.07	9,784	11,181	105	1,082							20	10	18	8	2								150	
TOTAL FOR PROJ NO. 2021CPT.05.22.20921.1							**23.29**		**2,698**	**60**	**1.00**	**188,811**	**198,520**	**483**	**1,492**	**1,568**	**18**	**8**	**10**	**1**	**6**	**20**	**21**	**45**	**12**	**3**	**1,372**	**120**	**250**	**276**	**22**	**1,470**	**1,470**	**402**	**182**
												387,331		**1,975**			**63**						**81**				**1,492**		**526**						
GRAND TOTAL							**23.3**		**2,698**	**60**	**1.00**	**188,811**	**198,520**	**483**	**1,492**	**1,568**	**18**	**8**	**10**	**1**	**6**	**20**	**21**	**45**	**12**	**3**	**1,372**	**120**	**250**	**276**	**22**	**1,470**	**1,470**	**402**	**182**
												387,331		**1,975**			**63**						**81**				**1,492**		**526**						