

TIP NO.	SHEET NO.
B-5980	PMP-01
APPROVED: _____	
DATE: _____	
SEAL	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

**STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION**

**PAVEMENT MARKING PLAN
NASH COUNTY**

LOCATION: I-95 INTERCHANGE IMPROVEMENTS AT HALIFAX ROAD (SR 1544)

T.I.P.: B-5980

CONTRACT: C204350

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS
1205.03	PAVEMENT MARKINGS - EXIT AND ENTRANCE RAMP
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.05	PAVEMENT MARKINGS - TURN LANES
1205.08	PAVEMENT MARKINGS - SYMBOLS AND WORD MESSAGES
1205.12	PAVEMENT MARKINGS - BRIDGES
1205.13	PAVEMENT MARKINGS - LANE REDUCTIONS
1250.01	RAISED PAVEMENT MARKERS - INSTALLATION SPACING
1251.01	RAISED PAVEMENT MARKERS - PERMANENT AND TEMPORARY
1253.01	RAISED PAVEMENT MARKERS - SNOWPLOWABLE
1205.06	PAVEMENT MARKINGS - LANE DROPS
1205.09	PAVEMENT MARKINGS - PAINTED ISLANDS
1205.14	PAVEMENT MARKINGS - ROUNDABOUTS
1261.02	GUARDRAIL & BARRIER DELINEATORS
1262.01	GUARDRAIL END DELINEATION
1264.01	OBJECT MARKERS - TYPES
1264.02	OBJECT MARKERS - INSTALLATION

INDEX

SHEET NO.	DESCRIPTION
PMP-1	PAVEMENT MARKING PLAN TITLE AND SCHEDULE SHEET
PMP-02-PMP-07	PAVEMENT MARKING DETAILS

**FINAL PAVEMENT
MARKING SCHEDULE**

SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
THERMOPLASTIC		POLYUREA	
T2	WHITE STOPBAR (24" 90 MIL)	VA	WHITE EDGE LINE (4")
T6	WHITE EDGE LINE (6" 90 MIL)	VB	YELLOW EDGE LINE (4")
T7	YELLOW EDGE LINE (6" 90 MIL)	V6	WHITE EDGE LINE (6")
T13	3 FT.-9 FT. WHITE MINISKIP (8" 90 MIL)	V7	YELLOW EDGE LINE (6")
TA	WHITE EDGE LINE (4" 90 MIL)	V10	3 FT.-9 FT. WHITE MINISKIP (12")
TB	YELLOW EDGE LINE (4" 90 MIL)	VS	WHITE GORELINE (12")
TC	10 FT. WHITE SKIP (4" 90 MIL)	THERMOPLASTIC SYMBOLS	
TD	3 FT.-9 FT. WHITE MINISKIP (4" 90 MIL)	UA	LEFT TURN ARROW (90 MIL)
TE	WHITE SOLID LANE LINE (4" 90 MIL)	UB	RIGHT TURN ARROW (90 MIL)
TH	YELLOW SINGLE CENTER (4" 90 MIL)	UC	STRAIGHT ARROW (90 MIL)
TI	YELLOW DOUBLE CENTER (4" 90 MIL)	UE	COMBO RIGHT / STRAIGHT ARROW (90 MIL)
TJ	10 FT. WHITE SKIP (6" 90 MIL)	UI	ALPHANUMERIC CHAR. (90 MIL)
TP	YELLOW DIAGONAL (8" 90 MIL)	UP	MERGE ARROW (90 MIL)
TR	WHITE SOLID LANE LINE (8" 90 MIL)	UQ	RAMP ARROW (90 MIL)
TS	WHITE GORELINE (12" 90 MIL)		

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
I-95	THERMOPLASTIC	NON-CAST IRON
NC-4 (CONCRETE)	POLYUREA	NON-CAST IRON
NC-4 (ASPHALT)	THERMOPLASTIC	NON-CAST IRON
NC-48	THERMOPLASTIC	NON-CAST IRON
SR 1544	THERMOPLASTIC	NONE

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES

C) STOP BAR LOCATION AT NON-SIGNALIZED INTERSECTIONS MAY BE ADJUSTED AS DIRECTED BY THE ENGINEER.

D) UNLESS OTHERWISE SPECIFIED, HEATED-IN-PLACE THERMOPLASTIC MAY BE USED IN LIEU OF EXTRUDED THERMOPLASTIC FOR STOP BARS, SYMBOLS, CHARACTERS AND DIAGONALS. IF HEATED-IN-PLACE IS USED, IT SHALL BE PAID FOR USING THE EXTRUDED THERMOPLASTIC PAY ITEM.

E) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

PLAN PREPARED BY: **AECOM**

NC FIRM LICENSE No. F-0342
701 Corporate Center Drive, Suite 475
Raleigh, NC 27607
(919) 854-1600 - (919) 854-6259 (FAX)

JEFFREY KOONTZ, PE PROJECT ENGINEER

KASEY MCCOY PROJECT DESIGNER