



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

July 8, 2021

Addendum No. 1

RE: Contract # C204543

WBS # 47532.3.3

FA# STATE FUNDED

Harnett and Johnston Counties

I-95 FROM SR-1002 (EXIT 71) TO I-40 (EXIT 81)

July 20, 2021 Letting

To Whom It May Concern:

Reference is made to the plans and proposal form furnished to you on this project.

The following revisions have been made to the Structure plans.

Sheet No.	Revision
(I-5986B) S4-2	Added Notes for Class II Surface Preparation, Class III Surface Preparation, and Concrete Deck Repair for PC Overlay as Extra Work. "Epoxy Coating as Extra work" statement under notes removed.
(I-5986B) S4-5	"Polyester" removed from labels that list "Polyester Polymer Concrete Overlay".
(I-5878) W-12	Updated quantity boxes to indicated Gravity Retaining Wall rather than MSE wall.

Please void the above listed Sheet in your plans and staple the revised Sheet thereto.

The following revisions have been made to the Roadway plans.

Sheet No.	Revision
(I-5883) 2G-5	Detail added to depict the Class A Rip Rap only at the top of Class II Rip Rap.
(I-5883) 2G-6	Revised SR13 profile and drainage to save pond on Parcel 102, added rock embankment detail.
(I-5878) 3B-1	Earthwork quantity sheet updated to reflect earthwork quantity changes shown below.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
CONTRACT STANDARDS AND DEVELOPMENT
1591 MAIL SERVICE CENTER
RALEIGH, NC 27699-1591

Telephone: (919) 707-6900
Fax: (919) 250-4127
Customer Service: 1-877-368-4968

Location:
1020 BIRCH RIDGE DR.
RALEIGH, NC 27610

Website: www.ncdot.gov

(I-5883) 3B-2	Earthwork quantity sheet updated to reflect earthwork quantity changes shown below.
(I-5986B) 3B-4	Earthwork quantity sheet updated to reflect earthwork quantity changes shown below
(I-5986B) 3B-8	Guardrail quantity sheet updated to reflect guardrail quantity changes shown below.
(I-5878) 3D-1 thru 3D-19	Drainage summary sheets updated to reflect drainage quantity changes shown below.
(I-5883) 3D-20, 3D-34	Drainage summary sheets updated to reflect drainage quantity changes shown below.
(I-5883) 3P-2	Revised SR13 profile and drainage to save pond on parcel 102, added rock embankment detail.
(I-5986B) 3P-3	Incorporated R/W revision for Parcel 266, 266A, and 267, revised paved shoulder under NC 50 bridge.
(I-5878) 16-17, 102	Added drives for Parcels 45, 46, and 47, updated surveys for Parcel 46.
(I-5878) 17, 19, 57	Additional drainage notes were added.
(I-5878) 19	Added note to save sign on Parcel 93.
(I-5883) 23-24, 26-27, 29, 32, 62, 64-65	Additional drainage notes were added.
(I-5883) 23-25, 59	Revised SR13 profile and drainage to save pond on parcel 102, added rock embankment detail.
(I-5883) 27-28	Hatched area for pavement removal updated.
(I-5986B) 35-36, 40, 42, 44-45, 68	Additional drainage notes were added.
(I-5986B) 42	Incorporated R/W revision for Parcel 266, 266A, and 267, revised paved shoulder under NC 50 bridge.
(I-5878) 56A	Added notes to save signs on Parcels 302 & 303, added TCE on Parcels 302, 303, & 307.
(I-5878) 58	Revised pavement radius at SR12/NC55 intersection.
(I-5878 / I-5883) 118-119	Revised SR13 profile and drainage to save pond on parcel 102, added rock embankment detail.
(I-5878 / I-5883 / I-5986B) TMP-1C	A number of items in the lists were removed.
(I-5878 / I-5883 / I-5986B) TMP-1G	All the pavement marking general notes were revised.
(I-5878) TMP-17B	Cross section revised due to SR13 profile change.
(I-5878) TMP-18A	Cross section revised due to SR13 profile change.
(I-5878) UC-7C, UC-14, UC-27	Added fluoroelastomer gaskets along water line PW700 through and past contaminated soils. No quantity changes.
(I-5878) UC-16, UC-30	Revised water line to avoid signs on Parcels 302 & 303.
(I-5878) UO-4 thru UO-5	Updated due to revised drainage for drives added to Parcels 45, 46, & 47.
(I-5878) UO-14	Updated to show additional TCE.
(I-5878) X-1A, X-1F thru X-1G	Cross section summary sheets updated to reflect earthwork quantity changes shown below.

(I-5883) X-1H, X-1O	Cross section summary sheets updated to reflect earthwork quantity changes shown below.
(I-5986B) X-1R, X-1U	Cross section summary sheets updated to reflect earthwork quantity changes shown below.
(I-5878) X-229 thru X-232, X-394	Added drives for Parcels 45, 46, and 47, updated surveys for Parcel 46.
(I-5878) X-318 thru X-319	Updated to show “fill to elevation” for drainage.
(I-5878) X-405	Revised pavement radius at SR12/NC55 intersection.
(I-5883) X-504 thru X-509, X-662	Revised SR13 profile and drainage to save pond on parcel 102, added rock embankment detail.
(I-5986B) X-846 thru X-849	Incorporated R/W revision for Parcel 266, 266A, and 267, revised paved shoulder under NC 50 bridge.

Please void the above listed Sheets in your plans and staple the revised Sheets thereto.

The following revisions have been made to the proposal:

Page No.	Revisions
Proposal Cover	Note added that reads “Includes Addendum No. 1 Dated 07-08-2021”
Table of Contents	Revised the MINORITY BUSINESS ENTERPRISE AND WOMEN BUSINESS ENTERPRISE provision page number.
G-14	Revised the SPECIALTY ITEMS provision
G-14 thru G-25	Updated FUEL PRICE ADJUSTMENT provision
G-33 thru G-35	Added broadband project I-5986A/I-5877 project to the COOPERATION BETWEEN CONTRACTORS provision.
TC-1 thru TC-37	Unit Project Special Provision entitled WORK ZONE TRAFFIC PATTERN MASKING removed. “Measurement and Payment” section added to Unit Project Special Provision entitled TRAFFIC CONTROL SUPERVISOR to show item as incidental.
UBO-2A	Note added that reads "The Town of Benson will need two months' notice and one week to back feed the aerial span over I-95 at -L-1328+40 for noise wall 33-1 construction"
ST-62A	Revised Unit Project Special Provision entitled POLYMER CONCRETE BRIDGE DECK OVERLAY to remove “in North Carolina” requirement for System Provider Qualifications
ST-6B	Revised Unit Project Special Provision entitled ELECTRICAL CONDUIT SYSTEM FOR SIGNALS to include separate pay items for the 2 stations
P-1	Revised to reflect the Department’s receipt of the permits
New Pages P-2 thru P-173	Pages added to include project permit in the proposal

Please void the above listed existing Pages in your proposal and staple the revised Pages thereto. Staple New Pages P-2 thru P-173 after revised Page P-1 in your proposal.

On the item sheets the following pay item revisions have been made:

<u>Item</u>	<u>Description</u>	<u>Old Quantity</u>	<u>New Quantity</u>
0005-0022000000-E-225	UNCLASSIFIED EXCAVATION	498,000 CY	504,000 SY
0014-0106000000-E-230	BORROW EXCAVATION	786,000 CY	779,000 CY
0021-0194000000-E-265	SELECT GRANULAR MATERIAL, CLASS III	65,350 CY	64,500 CY
0022-0196000000-E-270	GEOTEXTILE FOR SOIL STABILIZATION	672,500 SY	671,200 SY
0024-0220000000-E-SP	ROCK EMBANKMENTS	225 TON	1,925 TON
0025-0222000000-E-SP	GEOTEXTILE FOR ROCK EMBANKMENTS	460 SY	1,660 SY
0038-0344000000-E-310	18" SIDE DRAIN PIPE	7,820 LF	7,876 LF
0039-0345000000-E-310	24" SIDE DRAIN PIPE	5,272 LF	5,324 LF
0048-0372000000-E-310	18" RC PIPE CULVERTS, CLASS III	760 LF	820 LF
0053-0402000000-E-310	48" RC PIPE CULVERTS, CLASS III	352 LF	368 LF
0099-1077000000-E-SP	#57 STONE	160 TON	760 TON
0102-1121000000-E-520	AGGREGATE BASE COURSE	87,370 TON	96,470 TON
0104-1275000000-E-600	PRIME COAT	31,9000 GAL	29,540 GAL
0108-1491000000-E-610	ASPHALT CONC BASE COURSE, TYPE B25.0C	420,590 TON	415,640 TON
0109-1503000000-E-610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	214,660 TON	215,250 TON

0110-1519000000-E-610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	24,840 TON	24,040 TON
0111-1523000000-E-610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	51,610 TON	52,510 TON
0112-1524200000-E-610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	127,060 TON	127,130 TON
0113-1575000000-E-620	ASPHALT BINDER FOR PLANT MIX	33,995 TON	33,925 TON
0114-1577000000-E-620	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	7,245 TON	7,250 TON
0129-2209000000-E-838	ENDWALLS	348.5 CY	349.5 CY
0166-2724000000-E-857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	3,692 LF	3,777 LF
0172-3030000000-E-862	STEEL BEAM GUARDRAIL	21,975 LF	22,250 LF
0181-3287000000-N-SP	GUARDRAIL END UNITS, TYPE TL-3	57 EA	58 EA
0183-3317000000-N-SP	GUARDRAIL ANCHOR UNITS, TYPE B-77	42 EA	43 EA
0195-3635000000-E-876	RIP RAP, CLASS II	3,295 TON	5,795 TON
0196-3642000000-E-876	RIP RAP, CLASS A	100 TON	650 TON
0274-4815000000-E-1205	PAINT PAVEMENT MARKING LINES (6")	773,510 LF	1,512,354 LF
0276-4825000000-E-1205	PAINT PAVEMENT MARKING LINES (12")	49,590 LF	99,176 LF
0283-4848000000-E-SP	WORK ZONE TRAFFIC PATTERN MASKING	6,969,600 SF	DELETED

0285-4855000000-E-1205	REMOVAL OF PAVEMENT MARKING LINES (6")	4,400 LF	743,244 LF
0539-8504000000-E-460	CONCRETE BARRIER RAIL WITH MOMENT SLAB	250 LF	158.74 LF
0549-8801000000-E-SP	MSE RETAINING WALL NO W2-1 (I-5883)	3,000 SF	3,500 SF
0552-8801000000-E-SP	MSE RETAINING WALL NO W2-2 (I-5883)	3,300 SF	3,800 SF
0556-8847000000-E-SP	ARCHITECTURAL CONCRETE SURFACE TREATMENT	40,791 SF	41,241 SF
0581-8175000000-E-420	CLASS AA CONCRETE (BRIDGE)	276.7 CY	205.7 CY
0591-8224000000-E-425	EPOXY COATED REINFORCING STEEL (BRIDGE)	21,566 LB	9,487 LB
0627-4865000000-E-1205	REMOVAL OF PAVEMENT MARKING LINES (12")	NEW ITEM	49,586 LF
0628-6045000000-E-SP	48" TEMPORARY PIPE	NEW ITEM	1,200 LF

The Contractor's bid must include these pay item revisions.

The electronic bidding file has been updated to reflect these revisions. Please download the Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

The contract will be prepared accordingly.

Sincerely,

DocuSigned by:

 F81B6038A47A442...

Ronald E. Davenport, Jr., PE
 State Contract Officer

RED/jjr

Attachments

cc: Mr. Lamar Sylvester, PE
Mr. Kevin Bowen, PE
H.L. "Drew" Cox, PE
Mr. Boyd Tharrington, PE
Mr. Jon Weathersbee, PE
Mr. Ken Kennedy, PE
Project File (2)

Mr. Ray Arnold, PE
Ms. Jaci Kincaid
Ms. Lori Strickland
Mr. Mike Gwyn
Ms. Penny Higgins
Mr. Kyle Kempf