
CLEAR 2 FT MIN. 3 FT MIN. DISTANCE EDGE OF PAVEMENT TOP OF WALL EDGE OF **PAVEMENT SECTION** _____ TRAFFIC LANE REINFORCED ZONE REINFORCEMENT EXISTING OR **FINISHED** GRADE ____ BOTTOM **OF WALL BOTTOM OF REINFORCED ZONE** NOTE: WALL OR SHORING HEIGHT = A - B FIGURE A NOTES 1- REFER TO THE TRAFFIC CONTROL PLANS FOR TEMPORARY SHORING LOCATIONS AND NOTES. 2- REFER TO THE "TEMPORARY SHORING" PROJECT SPECIAL PROVISION FOR INFORMATION ABOUT TEMPORARY SHORING AND PORTABLE CONCRETE BARRIER (PCB). 3- PCB IS REQUIRED IF TEMPORARY SHORING IS LOCATED WITHIN THE CLEAR ZONE IN ACCORDANCE WITH THE AASHTO ROADSIDE DESIGN GUIDE. DO NOT PLACE BARRIER DIRECTLY ON ANY SURFACE OTHER THAN ASPHALT OR CONCRETE. (CONTACT NCDOT PAVEMENT MANAGEMENT UNIT FOR APPLICABLE PAVEMENT DESIGN). 4- BASED ON THE CLEAR DISTANCE, OFFSET, DESIGN SPEED AND PAVEMENT TYPE, CHOOSE AN UNANCHORED OR ANCHORED PCB FROM THE TABLE SHOWN IN FIGURE B. CLEAR DISTANCE IS DEFINED AS SHOWN IN FIGURE A AND OFFSET IS DEFINED AS SHOWN IN FIGURE B.

REQUIRED CLEAR DISTANCE IS REQUIRED ABOVE TEMPORARY WALLS.

OF THE STANDARD SPECIFICATIONS.


NAIL WALLS.



rrier	Pavement	UM REQUI Offset *				ed, mph			
Гуре	Туре	ft	<30	31-40	41-50	51-60	61-70	71-80	
Unanchored PCB	Asphalt	<8	24	26	29	32	36	40	
		8-14	26	28	31	35	38	42	
		14-20	27	29	34	36	39	43	
		<u>20-26</u> 26-32	28 29	31 32	35	38 39	40 42	44	
		32-38	<u> </u>	32	36 38	<u> </u>	42	45 46	
		38-44	<u> </u>	34	41	43	45	48	
		44-50	<u> </u>	35	41	43	46	49	
		50-56	32	36	42	44	47	50	
		>56	32	36	42	45	47	51	
	Concrete	<8	17	18	21	22	25	26	
		8-14	<u> </u>	20	23	25	26	29	
		<u>14-20</u> 20-26	$\frac{22}{22}$	22	24	26	28 30	31	
		26-32	23 24	24 25	26 27	27 28	30	<u>34</u> 35	
		32-38	24	23	27	30	33	36	
		38-44	25	26	28	30	34	37	
		44-50	26	26	28	32	35	37	
		50-56	26	26	28	32	35	38	
		>56	26	27	29	32	36	38	
Anchored PCB	Asphalt	All Offsets 24 for All Design Speeds							
Anchored PCB	Concrete (including bridge approach slabs)	All Offsets 12 for All Design Speeds							









E TRAFFIC



PORTABLE CONCRETE BARRIER AT TEMPORARY SHORING LOCATIONS