TIP NO.	SHEET NO.
I-5986B	SIGN-20

APPROVED: William J. Hamilton
DATE: 3/15/2021

SEAL

NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 21396 WILLIAM J. HAMILTON

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

RAMEY KEMP ASSOCIATES
5808 Faringdon Place
Raleigh, North Carolina 27609
Phone: 919-872-5115
NC License No. C-0910
rameykemp.com

PROPOSED SIGNS

MATCHLINE –L– STA. 1382+00.00
SEE SHEET SIGN–21

RELOCATE EXISTING SIGN
ON NEW SUPPORTS
NC Aquarium
EXIT 81
-L- STA. 1379+50 +/-
915

427 35 MPH
426

Overhead Assembly "H"
-L- STA. 1377+00 +/-
210" X 156"
88
Benson
Newton Grove
1/2 MILE
50
242
8A EXIT 79
114" X 30"

NAD 83/2011

RELOCATE EXISTING SIGN
ON NEW SUPPORTS
Southeastern NC Beaches
USS North Carolina
Battleship Memorial
EXIT 81
914
-L- STA. 1373+00 +/-

407 (FIVE SIGN ASSEMBLIES)
408

-L- STA. 1372+81
MILE 80 TWO SIGNS

SPEED LIMIT 65
403

407 (FOUR SIGN ASSEMBLIES)
408

-L- STA. 1369+00 +/-
913
FOOD-EXIT 79
RELOCATE EXISTING SIGN
ON NEW SUPPORTS

114" X 30"
EXIT 81
7A

INTERSTATE 40
Raleigh
Wilmington
EXIT ONLY
7B
216" X 162"

NORTH
INTERSTATE 95
503

Overhead Assembly "G"
-L- STA. 1367+00 +/-

-L- STA. 1361+00 +/-
912
GAS-EXIT 79
FOOD-EXIT 79
RELOCATE EXISTING SIGN
ON NEW SUPPORTS

MATCHLINE –L– STA. 1356+00.00
SEE SHEET SIGN–18

DocuSign Envelope ID: A0AF9111-4543-4678-8C0B-46B30D17B088