



GENERAL NOTES:

- FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM, CONTACT THE DIVISION 6 TRAFFIC ENGINEER AT (910) 364-0606 TO ARRANGE FOR THE DIVISION TRAFFIC ENGINEER TO PROGRAM THE NEW FIELD ETHERNET SWITCHES WITH THE NECESSARY NETWORK CONFIGURATION DATA, INCLUDING BUT NOT LIMITED TO: THE PROJECT IP ADDRESS, DEFAULT GATEWAY, SUBNET MASK AND VLAN ID INFORMATION. NOTIFY THE DIVISION TRAFFIC ENGINEER WHEN WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.
- ONCE FIBER HAS BEEN INSTALLED AND THE SYSTEM IS UP AND OPERATIONAL, REMOVE EXISTING WIRELESS EQUIPMENT AND YAGI ANTENNA AND RETURN TO DIVISION 6 AT 450 TRANSPORTATION DRIVE, FAYETTEVILLE, NC 28301.

Michael Baker INTERNATIONAL
 8000 Regency Pkwy, Ste. 600, Cary, NC 27518
 Phone: (919) 463-5490 · M·BAKERINTL.COM
 NC License No. : F-1084

Prepared for:

 750 N. Greenfield Pkwy, Garner, NC 27529
 SCALE: 0 60
 1" = 60'

| | |
|------------------------------------|-----------------------|
| SIGNAL COMMUNICATIONS PLANS | |
| SIGNAL SYSTEM #D06-02 DUNN | |
| FINAL | |
| DIVISION 06 | HARNETT CO. DUNN |
| PLAN DATE: March 2021 | REVIEWED BY: K M Cory |
| PREPARED BY: S Tamm | REVIEWED BY: |
| REVISIONS | INIT. DATE |
| | |
| | |
| | |

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL
 NORTH CAROLINA PROFESSIONAL ENGINEER
 SEAL 038970
 KELLY M. CORY
 4/26/2021
 CADD Filename: