



**1. THE PROPOSED UTILITY CONSTRUCTION** SHALL MEET THE APPLICABLE REQUIREMENTS OF THE NC DEPARTMENT OF TRANSPORTATION'S "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" DATED JANUARY 2018.

2. THE EXISTING UTILITIES BELONG TO EITHER THE CITY OF DUNN OR HARNETT REGIONAL WATER (HRW). PW700 ON SHEETS UC-7C AND UC-14 BELONGS TO HRW. ALL OTHER WATER AND SEWER LINES BELONG TO THE CITY OF DUNN.

3. ALL WATER LINES TO BE INSTALLED WITHIN COMPLIANCE OF THE RULES AND **REGULATIONS OF THE NORTH CAROLINA** DEPARTMENT OF ENVIRONMENTAL QUALITY, DIVISION OF WATER RESOURCES, PUBLIC WATER SUPPLY SECTION. ALL SEWER LINES TO BE INSTALLED WITHIN COMPLIANCE OF THE RULES AND REGULATIONS OF THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT QUALITY, DIVISION OF WATER **RESOURCES, WATER QUALITY SECTION.** PERFORM ALL WORK IN ACCORDANCE WITH THE APPLICABLE PLUMBING CODES.

4. THE UTILITY OWNERS OWN THE EXISTING UTILITY FACILITIES AND WILL OWN THE NEW UTILITY FACILITIES AFTER ACCEPTANCE BY THE DEPARTMENT. THE DEPARTMENT OWNS THE CONSTRUCTION CONTRACT AND HAS ADMINISTRATIVE AUTHORITY. COMMUNICATIONS AND DECISIONS BETWEEN THE CONTRACTOR AND UTILITY OWNERS ARE NOT BINDING UPON THE DEPARTMENT OR THIS CONTRACT UNLESS AUTHORIZED BY THE ENGINEER. AGREEMENTS BETWEEN THE UTILITY OWNERS AND CONTRACTOR FOR THE WORK THAT IS NOT PART OF THIS CONTRACT OR IS SECONDARY TO THIS CONTRACT ARE ALLOWED, BUT ARE NOT BINDING UPON THE DEPARTMENT.

5. PROVIDE ACCESS FOR THE DEPARTMENT PERSONNEL AND THE OWNERS' REPRESENTATIVES TO ALL PHASES OF CONSTRUCTION. NOTIFY DEPARTMENT PERSONNEL AND THE UTILITY OWNERS TWO WEEKS PRIOR TO COMMENCEMENT OF ANY WORK AND ONE WEEK PRIOR TO SERVICE INTERRUPTION. KEEP UTILITY OWNERS' REPRESENTATIVES INFORMED OF WORK PROGRESS AND PROVIDE OPPORTUNITY FOR INSPECTION OF CONSTRUCTION AND TESTING.

6. THE PLANS DEPICT THE BEST AVAILABLE INFORMATION FOR THE LOCATION, SIZE, AND TYPE OF MATERIAL FOR ALL EXISTING UTILITIES. MAKE INVESTIGATIONS FOR DETERMINING THE EXACT LOCATION, SIZE, AND TYPE MATERIAL OF THE EXISTING FACILITIES AS NECESSARY FOR THE CONSTRUCTION OF THE PROPOSED UTILITIES AND FOR AVOIDING DAMAGE TO EXISTING FACILITIES. REPAIR ANY DAMAGE INCURRED TO EXISTING FACILITIES TO THE ORIGINAL OR BETTER CONDITION AT NO ADDITIONAL COST TO THE DEPARTMENT.

## UTILITY CONSTRUCTION

7. MAKE FINAL CONNECTIONS OF THE NEW WORK TO THE EXISTING SYSTEM WHERE INDICATED ON THE PLANS, AS REQUIRED TO FIT THE ACTUAL CONDITIONS, OR AS DIRECTED.

8. MAKE CONNECTIONS BETWEEN EXISTING AND PROPOSED UTILITIES AT TIMES MOST CONVENIENT TO THE PUBLIC, WITHOUT ENDANGERING THE UTILITY SERVICE, AND IN ACCORDANCE WITH THE UTILITY OWNER'S REQUIREMENTS, MAKE CONNECTIONS ON WEEKENDS, AT NIGHT, AND ON HOLIDAYS IF NECESSARY, LINE STOPS AND INSERT VAVLES WILL BE REQUIRED WHERE INDICATED ON THE PLANS, WHERE THE UTILITY OWNER CANNOT ISOLATE THE EXISTING LINES WITHOUT MAJOR DISRUPTION OF SERVICE TO MANY USERS.

9. ALL UTILITY MATERIALS SHALL BE APPROVED BY HRW OR THE CITY OF DUNN AND NCDOT PRIOR TO DELIVERY TO THE PROJECT. SEE 1500-7, "SUBMITTALS AND RECORDS" IN SECTION 1500 OF THE STANDARD SPECIFICATIONS.

## **PROJECT SPECIFIC NOTES:**

1. UNLESS OTHERWISE NOTED, FOR PROPOSED WATER MAINS AND SEWER MAINS 4" THRU 12" DIAMETER, PIPE SHALL BE PVC C900, DR 18, DUCTILE IRON, PC 350, OR RESTRAINED JOINT WHERE INDICATED ON PROFILES. SEWER MAINS 16" AND LARGER SHALL BE DUCTILE IRON. PC 250, RESTRAINED JOINT, OR FPVC WHERE INDICATED ON PROFILES. HRW DOES NOT APPROVE EBAA IRON "MEGALUG" TYPE RESTRAINED RETAINER GLANDS. HRW PREFERS ROMAC "GRIP RINGS" OR APPROVED EQUAL. WATER SERVICE LINES SHALL BE PE, SDR 9.


2. FUSIBLE PVC SHALL BE EXTRUDED WITH PLAIN ENDS. THE ENDS SHALL BE SQUARE TO THE PIPE AND FREE OF ANY BEVEL OR CHAMFER. THERE WILL BE NO BELL OR GASKET OF ANY KIND **INCORPORATED INTO THE PIPE. THE PIPE SHALL BE MANUFACTURED IN STANDARD 40' NOMINAL** LENGTHS OR CUSTOM LENGTHS AS SPECIFIED, AND SHALL BE COLORED BLUE FOR WATER AND GREEN FOR SEWER. FUSIBLE PVC SHALL BE BUTT-FUSED BY QUALIFIED, CERTIFIED, AND LICENSED TECHNICIANS. A DATA LOGGER SHALL BE AFFIXED TO THE FUSION MACHINE AND ALL PRESSURE/TIME DATA COLLECTED FOR USE BY THE ENGINEER. THE FUSIBLE PVC WILL BE INSTALLED IN A MANNER SO AS TO NOT EXCEED THE RECOMMENDED BENDING RADIUS AS SHOWN ON THE PLANS, AND THE RECOMMENDED SAFE PULLING FORCE ESTABLISHED BY THE PIPE MANUFACTURER SHALL NOT BE EXCEEDED. CONNECTIONS TO OTHER MATERIALS SHALL BE AS SHOWN ON THE PLANS. PVC PIPE ENDS SHALL NOT BE BENT INTO POSITION WITH HEAVY EQUIPMENT BUT INSTEAD SHALL BE ACCOMPLISHED WITH FUSIBLE FITTINGS.

3. DUCTILE IRON PIPE WITH FLUOROELASTOMER OR NITRILE GASKETS AND POLYWRAP SHALL BE INSTALLED IN ALL AREAS WITH HAZARDOUS SOILS AS SHOWN ON PLAN PROFILES. ALL UNSUITABLE SOIL SHALL BE REMOVED AND DISPOSED OF.

4. DUCTILE IRON PIPE FOR SEWER LINES SHALL BE INTERIOR LINED WITH CERAMIC EPOXY LINING.

5. WATER LINE VALVES SHALL BE RESILIENT-SEAT GATE VALVES CONFORMING TO ANSI/AWWA C509, RATED FOR 200 PSI MINIMUM WORKING PRESSURE. HRW VALVES SHALL BE MUELLER, FLOW CONTROL, WATEROUS, M&H, KENNEDY, OR APPROVED EQUAL. DUNN VALVES SHALL BE CLOW, KENNEDY, MUELLER, OR APPROVED EQUAL.

6. FIRE HYDRANTS SHALL MEET NCDOT STANDARD SPECS. HRW HYDRANTS SHALL BE MUELLER A-423, AMERICAN DARLING MARK B-84-B. WATEROUS PACER B-67-250. OR APPROVED EQUAL. DUNN HYDRANTS SHALL BE MUELLER CENTURION (A-421) OR APPROVED EQUAL.



WWW.DMP-INC.COM LICENSE; F-0245