


ELEVATION AT EXPANSION JOINTS BARRIER RAIL DETAILS

## NOTES

THE BARRIER RAIL IN THE SPAN SHALL NOT BE CAST UNTIL ALL SLAB CONCRETE IN THE SPAN HAS BEEN CAST AND HAS REACHED A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI.

ALL REINFORCING STEEL IN BARRIER RAILS SHALL BE EPOXY COATED.

GROOVED CONTRACTION JOINTS,  $\frac{1}{2}$ "IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE BARRIER RAIL AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. THE CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN BARRIER RAIL EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF BARRIER RAIL SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.



ALL BAR DIMENSIONS ARE OUT TO OUT

BILL OF MATERIAL							
FOR CONCRETE BARRIER RAIL ONLY							
STAGE I							
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT		
<b>₩</b> B1	22	#5	STR.	25' - 1"	576		
<b></b> ₩ B2	44	#5	STR.	14' - 5"	662		
<b>*</b> S1	104	#5	1	4' - 6"	488		
<b>*</b> S2	104	#5	2	7' - 0"	759		
* EPC	OXY CO	ATED					
REINFORCING STEEL LBS. 2,485							
CLAS	S AA	CONCRE	CU. YDS.	13.9			
CONCRETE BARRIER RAIL LIN. FT. 102.29							
STAGE II							
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT		
<b>*</b> B3	22	#5	STR.	25' - 1"	576		
<b></b> ₩ B4	44	#5	STR.	14' - 5"	662		
<b>*</b> S3	104	#5	1	4' - 6"	488		
<b>*</b> S4	104	#5	2	7 '- 0"	759		
* EPOXY COATED							
REINFORCING STEEL LBS. 2,485							
CLASS AA CONCRETE CU. YDS. 13.9							
CONCRETE BARRIER RAIL LIN. FT. 102.29							

QUANTITIES DO NOT INCLUDE BARRIER RAILS ON THE APPROACH SLABS. FOR BARRIER RAILS ON THE APPROACH SLABS, SEE "BRIDGE APPROACH SLAB DETAILS 1" SHEET.

PROJECT NO. I-5878 HARNETT COUNTY

STATION: 1002+79.68 -LREV

SHEET 2 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

STANDARD

CONCRETE BARRIER RAIL

Michael Baker Engineering 8000 Regency Parkway, Suite 600 Cary, North Carolina 27518 INTERNATIONAL NC License No.: F-1084

DocuSigned by:

By

C41A3F8ECA3C434... 4/22/2021 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

OR ENGINEER

			SHEET NO.				
0	NO.	BY:	DATE:	NO.	BY:	DATE:	S2-I6
	1			8			TOTAL SHEETS
	2			4			34

STD. NO. CBR1

ASSEMBLED BY : N. B. SPEAK		: 4-11-19	
CHECKED BY : B. J. BELL	DATE	: 5-10-19	
DNAWN DI & AND 3701	REV. 7/I2 REV. 6/I3	MAA/ MAA/	
CHECKED BY : SJD 9/87	REV. 12/17	MAA/T	