




6/2/2019

BRIDGE No. 650015

PROJECT REFERENCE NO. 17BP.J.R.90	SHEET NO. 2A-2
ROADWAY DESIGN ENGINEER	PAVEMENT DESIGN ENGINEER
	
<p>DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED</p>	
PREPARED IN THE OFFICE OF:  KCA KISINGER CAMPO & ASSOCIATES	NC FIRM LICENSE No: C-1506 301 Fayetteville St., Suite 1500 Raleigh, NC 27601 (919)882-7839

FINAL PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD.
C2	PROP. APPROX. 2.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 138 LBS. PER SQ. YD. IN EACH OF THE TWO LAYERS.
C3	PROP. VARIABLE DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 110.0 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 1" OR TO EXCEED 1.5" IN DEPTH.
E1	PROP. APPROX. 4.0" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 456 LBS PER SQ. YD.
R1	SHOULDER BERM GUTTER
T	EARTH MATERIAL.
U	EXISTING PAVEMENT.
V	INCIDENTAL MILLING

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE
 NOTE: FINAL PAVEMENT DESIGN PER PAVEMENT DESIGN MEMO DATED 07/31/2019 FROM CLARK S. MORRISON, PhD, P.E.



TYPICAL SECTION NO. 2 ON STRUCTURE

BRIDGE 650015 OVER WILDCAT CREEK
 -L- STA. 15+03.35 TO STA. 16+10.72
 ** SEE STRUCTURES PLANS FOR AWS THICKNESS

07_MAR_2020 15:56
 17BP.J.R.90_2A-2.dgn
 idebone