PROJECT REFERENCE NO.	SHEET NO.
B-5666	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	13+00	14+50	LT	100
4	-L-	14+50	16+61.4	LT	110
4	-L-	20+50	20+83.6	LT	15
4	-L-	20+83.9	23+00	LT	170
4	-L-	23+00	23+85	LT	55
4	-L-	20+62	22+00	RT	70
				SUBTOTAL	520
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					1515
				TOTAL	2035
				SAY	2050

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	20+00	20+50	LT	25
			SUBTOTAL		25
		ADDITIONAL PSRM TO BE INSTALLED			0
				TOTAL	25
				SAY	30