	INDEX OF SHEETS
SHEET NUMBER	SHEET
1	TITLE SHEET
1 A	INDEX OF SHEETS, GENERAL NOTES, AND STANDARD DRAWINGS
1 B	CONVENTIONAL SYMBOLS
2A-1 TO 2A-8	TYPICAL SECTIONS AND PAVEMENT SCHEDULE
2B-1 TO 2B-6	ROUNDABOUT AND INTERSECTION DETAIL SHEETS
2C-1	DETAIL OF TRANSITION FROM 2'-6" CURB AND GUTTER TO VALLEY GUTTER
2C-2	DETAIL TO CONVERT EXISTING DI, CB, OTCB OR GI TO JUNCTION BOX
2C-3	DETAIL OF CONCRETE JUNCTION BOX WITH 6"-12" PIPE PASSING THRU
2C-4	PEDESTRIAN SAFETY RAIL DETAIL
2C-5	DETAIL OF TRANSITION FROM SHOULDER BERM GUTTER TO 2'-6" CURB AND GUTTER
2C-6	DETAIL OF MINIMUM DEPTH CONCRETE CATCH BASIN - 12" THRU 84" PIPE
2C-7	DETAIL OF CONCRETE GRATED DROP INLET TYPE 'A' MINIMUM DEPTH - 12" THRU 72" PIPE
2C-8	DETAIL OF 2" ROLLED CURB
2C-9	CURB RAMP DETAIL- DIRECTIONAL RAMPS
2C-10	CURB RAMP DETAIL- PARALLEL RAMPS
2C-11	CURB RAMP DETAIL- SHARED LANDING
2C-12	W BEAM GUARDRAIL SECTION INSTALLATION DETAIL
2C-13	METHOD OF CLEARING - MODIFIED METHOD II DETAIL
2C-14	2-GI IN VALLEY GUTTER DETAIL
2D-1 TO 2D-2	DRAINAGE STRUCTURE DETAIL SHEETS
2G-1 TO 2G-2	STANDARD REINFORCED SOIL SLOPE WITH HIGH GROUNDWATER STANDARD
2G-3	STANDARD TEMPORARY SHORING
2G-4 TO 2G-6	STANDARD TEMPORARY WALL
3B-1	SUMMARIES OF GUARDRAIL, PAVEMENT REMOVAL, VALLEY GUTTER, AND CONCRETE CURB
3B-2	EARTHWORK SUMMARY
3D-1 TO 3D-16	DRAINAGE SUMMARIES
3G-1	GEOTECHNICAL SUMMARIES
3P-1	PARCEL INDEX SHEET
4 TO 14	PLAN SHEETS
15 TO 24	PROFILE SHEETS
RW01	RIGHT-OF-WAY TITLE SHEET
RWO2C-1 TO RWO2C-11	SURVEY CONTROL SHEETS
RWO2D-1 TO RWO2D-2	PROPOSED ALIGNMENT CONTROL SHEETS
RWO3E-1 TO RWO3E-3	RIGHT-OF-WAY AND PERMANENT EASEMENT CONTORL SHEETS
RW-04 TO RW-14	RIGHT OF WAY SHEETS
TMP-1 TO TMP-6I	TRANSPORTATION MANAGEMENT PLANS
PMP-1 TO PMP-14	PAVEMENT MARKING PLANS
EC-1 TO EC-25	EROSION CONTROL PLANS
SIGN-1 TO SIGN-25	SIGNING PLANS
SIG-1.0 TO SIG-29.0	SIGNAL PLANS
SIG.MI TO SIG.M8	METAL POLE DESIGN PLANS
SCP-1 TO SCP-33	COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS
ITS-1 TO ITS-3	ITS PLANS
UC-1 TO UC-39	UTILITIES CONSTRUCTION PLANS
UO-1 TO UO-10	UTILITIES BY OTHERS PLANS
X-1 A	INDEX OF CROSS-SECTIONS
X-1B TO X-1C	CROSS-SECTION SUMMARY SHEETS
X-1 TO X-97	CROSS-SECTIONS
C-1 TO C-4	CULVERT PLANS
W-1 TO W-3	RETAINING WALL DETAILS

DocuSign Envelope ID: 31523FC1-A234-4A74-AB82-1F64E1D9F523

### GENERAL NOTES:

#### 2018 SPECIFICATIONS EFFECTIVE: 01-16-2018 REVISED:

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

### CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II MODIFIED.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

# SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01 & STD. NO. 560.02

#### SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

# SUBSURFACE DRAINS:

SUBSURFACE DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 815.02 AT LOCATIONS DIRECTED BY THE ENGINEER.

#### SHOULDER DRAINS:

SHOULDER DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 816.02 AND DETAILS IN PLANS AT LOCATIONS DIRECTED BY THE ENGINEER.

#### DRIVEWAYS:

DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 848.02 USING 3 FOOT RADII OR RADII AS SHOWN ON THE PLANS. LOCATIONS OF DRIVES WILL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

#### STREET TURNOUT:

STREET RETURNS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 848.04 USING THE RADII NOTED ON PLANS.

## GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

# TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC NOT SHOWN ON THE PLANS WILL BE PAID FOR AT THE CONTRACT PRICE FOR "TEMPORARY SHORING".

#### UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE PIEDMONT NATURAL GAS COMPANY, DUKE POWER, CENTURY LINK, SPECTRUM, MCNC, AND CITY OF WHITEVILLE.

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS, EXCEPT

# RIGHT-OF-WAY MARKERS:

AS SHOWN ON THE PLANS.

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY OTHERS.

# CURB RAMPS:

CURB RAMPS ARE SHOWN ON THE PLANS AT APPROXIMATE LOCATIONS CONSTRUCT ALL CURB RAMPS IN ACCORDANCE WITH STD 848.05 AND/OR 848.06

STD.NO.

816.01 840.02 840.03 840.14 840.17 840.32 840.34 840.72 Pipe Collar

PROJECT REFERENCE NO. SHEET NO. R-5020B IA ROADWAY DESIGN ENGINEER 6/24/2020 EFF. 01-16-2018 REV. 2018 ROADWAY ENGLISH STANDARD DRAWINGS The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch -N. C. Department of Transportation - Raleigh, N. C., Dated January, 2018 are applicable to this project and by reference hereby are considered a part of these plans: TITLE DIVISION 2 - EARTHWORK 225.01 Guide for Grading Subgrade - Interstate and Freeway 225.02 Guide for Grading Subgrade - Secondary and Local 225.04 Method of Obtaining Superelevation - Two Lane Pavement 225.06 Method of Grading Sight Distance at Intersections DIVISION 3 - PIPE CULVERTS 300.01 Method of Pipe Installation 310.10 Driveway Pipe Construction DIVISION 5 - SUBGRADE, BASES AND SHOULDERS 560.01 Method of Shoulder Construction - High Side of Superelevated Curve - Method I 560.02 Method of Shoulder Construction - High Side of Superelevated Curve - Method II DIVISION 6 - ASPHALT BASES AND PAVEMENTS 654.01 Pavement Repairs DIVISION 8 - INCIDENTALS 815.02 Subsurface Drain Concrete Pads - for Shoulder Drain Installation 816.02 Aggregate Shoulder Drain 816.04 Markers for Drainage Structure and Concrete Pad 838.01 Concrete Endwall for Single and Double Pipe Culverts - 15" thru 48" Pipe 90 Skew 838.11 Brick Endwall for Single and Double Pipe Culverts - 15" thru 48" Pipe 90 Skew 838.80 Precast Endwalls - 12" thru 72" Pipe 90 Skew 840.00 Concrete Base Pad for Drainage Structures 840.01 Brick Catch Basin - 12" thru 54" Pipe Concrete Catch Basin - 12" thru 54" Pipe Frame, Grates and Hood – for Use on Standard Catch Basin Concrete Drop Inlet - 12" thru 30" Pipe 840.15 Brick Drop Inlet - 12" thru 30" Pipe 840.16 Drop Inlet Frame and Grates - for use with Std. Dwg 840.14 and 840.15 Concrete Grated Drop Inlet Type 'A' - 12" thru 72" Pipe 840.18 Concrete Grated Drop Inlet Type 'B' - 12" thru 36" Pipe 840.19 Concrete Grated Drop Inlet Type 'D' - 12" thru 36" Pipe 840.20 Frames and Wide Slot Flat Grates 840.22 Frames and Wide Slot Sag Grates 840.24 Frames and Narrow Slot Sag Grates 840.25 Anchorage for Frames - Brick or Concrete or Precast 840.26 Brick Grated Drop Inlet Type 'A' - 12" thru 72" Pipe 840.27 Brick Grated Drop Inlet Type 'B' - 12" thru 36" Pipe 840.28 Brick Grated Drop Inlet Type 'D' - 12" thru 36" Pipe 840.29 Frames and Narrow Slot Flat Grates 840.31 Concrete Junction Box - 12" thru 66" Pipe Brick Junction Box - 12" thru 66" Pipe Traffic Bearing Junction Box - for Use with Pipes 42" and Under 840.35 Traffic Bearing Grated Drop Inlet - for Cast Iron Double Frame and Grates 840.45 Precast Drainage Structure 840.46 Traffic Bearing Precast Drainage Structure 840.54 Manhole Frame and Cover 840.66 Drainage Structure Steps 840.71 Concrete and Brick Pipe Plug 846.01 Concrete Curb, Gutter and Curb & Gutter 846.04 Drop Inlet Installation in Shoulder Berm Gutter 848.01 Concrete Sidewalk 848.02 Driveway Turnout - Radius Type 848.04 Street Turnout 848.05 Curb Ramp - Proposed Curb & Gutter 848.06 Curb Ramp - Existing Curb & Gutter 852.01 Concrete Islands 852.04 Method for Placement of Drop Inlets in Grass Median - Using 1'-6" Curb and Gutter 852.06 Method for Placement of Drop Inlets in Concrete Islands 852.10 Median Construction - with Curb and Gutter 862.01 Guardrail Placement 862.02 Guardrail Installation 862.03 Structure Anchor Units 876.01 Rip Rap in Channels 876.02 Guide for Rip Rap at Pipe Outlets 876.04 Drainage Ditches with Class 'B' Rip Rap

\_\_\_\_\_