


Version: 3.1 Posted: 6/2/2017

NUMBER	SIGN			ROADWAY STATION	NUMBER OF SUPPORTS	BEAM SECTION	SUPPORT TYPE BA or S	OMNI COUPLER	ATTACHMENT METHOD	MOUNTING METHOD	HORIZONTAL CLEARANCE* (ft.)	SUPPORT SPACING	LENGTH (ft)			LEFT SUPPORT (ft)			CENTER SUPPORT (ft)			RIGHT SUPPORT (ft)			SUPPORT WEIGHTS		FOOTINGS				FIELD VERIFIED SEE NOTE 2 (mm/dd/yy)	
	TYPE	SIZE (in.)											SNS HT	MTG HT	EMBED-MENT	S	L	LENGTH	S	L	LENGTH	S	L	LENGTH	B/A (lbs.)	SIMPLE (lbs.)	DIAMETER (ft.)	DEPTH (ft.)	REINFORCED (c.y.)	PLAIN (c.y.)		
		w	x																													h
901	A	180	x	120	-RPA- 18+50	2	W6x16	BA	N/A	N/A	N/A	12.00	8.79	10.00	7.00	4.0	2.74	19.74	23.74	0.00	0.00	0.00	1.28	18.28	22.28	830.32	0	1.5	4.5	0.59	0.00	
902	A	180	x	120	-RPA- 17+50	2	W6x16	BA	N/A	N/A	N/A	12.00	8.79	10.00	7.00	4.5	2.98	19.98	24.48	0.00	0.00	0.00	1.52	18.52	23.02	854.00	0	1.5	5	0.65	0.00	
903	A	180	x	120	-RPA- 16+50	2	W6x16	BA	N/A	N/A	N/A	12.00	8.79	10.00	7.00	4.0	2.86	19.86	23.86	0.00	0.00	0.00	1.40	18.40	22.40	834.16	0	1.5	4.5	0.59	0.00	
																	TOTAL	TOTAL		TOTAL	TOTAL											
																	2518.48	0.00		1.83	0.00											
																	USE:	2519.00	0.00		2.00	0.00										



TYPICAL ELEVATION GORE MOUNTED SIGNS

TYPICAL ELEVATION GROUND MOUNTED SIGNS

NOTES

1. DIMENSION "S" REPRESENTS AN INCREASE (+), OR A DECREASE (-) IN POLE LENGTH, RELATIVE TO THE ELEVATION OF THE EDGE OF PAVEMENT.
2. FIELD VERIFICATIONS SHALL BE REQUIRED FOR ALL SUPPORTS, SEE (*) ARTICLE 903-3. FABRICATORS SHALL BE AISC CERTIFIED IN CATEGORY 1, SEE (*) ARTICLE 1072-1. (*) = N.C.D.O.T. STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES
3. PLAN LOCATIONS FOR EXISTING UTILITIES ARE BASED ON THE BEST AVAILABLE INFORMATION AND, THEREFORE MAY NOT BE PRECISELY ACCURATE. THEREFORE, IT IS INCUMBENT UPON THE CONTRACTOR TO DETERMINE THE EXACT LOCATION OF UTILITIES BEFORE BEGINNING WORK IN A LOCATION.
4. IF GROUNDWATER IS ENCOUNTERED AT A DEPTH SHALLOWER THAN 7 FEET, THE SIGN FOUNDATION MUST BE REDESIGNED BASED UPON THE ACTUAL FIELD CONDITIONS. THE FOUNDATION DESIGN DOES NOT APPLY TO VERY SOFT OR LOOSE SOIL, MUCK, WEATHERED ROCK, OR HARD ROCK.

4/27/2017 11:13:55 AM R-5020B\TPA\Traffic\Signing\R-5020B_SIGN_2.dgn

SEPI
 1 Glenwood Avenue
 Raleigh, NC 27603
 Tel: 919.789.9977
 Fax: 919.789.9591
 License: C-2197

**TYPE "A" & "B"
 GROUND MOUNTED SIGNS**