



- Notes**
1. Record existing splice arrangements in Existing Splice Enclosures and Signal Cabinets prior to beginning work associated with splicing in the new fiber. If discrepancies exist, contact the Engineer to determine how to proceed prior to re-splicing.
  2. Contact the Division 6 Traffic Signal Supervisor at 910-364-0606, and provide a minimum of 5 working days notice prior to disturbing the existing fiber splices.
  3. After removal of the Traffic Signal at S Powell Blvd and Virgil St, remove the Existing Messenger Cable between Moore St and the Signal Cabinet.

\* ALL NCDOT ATTACHMENT POINTS ARE 40" BELOW POWER FRONT SIDE OF POLE, UNLESS OTHERWISE NOTED.  
\*\* ATTACH COMMUNICATIONS MESSENGER CABLE 12" ABOVE SIGNAL CABLE.

NC Dept of Transportation  
Division of Highways  
Final Drawing Date: \_\_\_\_\_  
ITS & Signals Unit

**SEPI**  
Engineering & Construction, Inc.  
1 Glenwood Avenue  
Raleigh, NC 27603  
Tel: 919.789.9977  
Fax: 919.789.9591  
License: C-2197

Prepared for the Offices of:  
**TRANSPORTATION MOBILITY AND LOGISTICS DIVISION**  
DEPARTMENT OF TRANSPORTATION  
Signal Design Section  
750 N. Greenfield Pkwy, Garner, NC 27529

**COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS**

DIVISION 6      COLOMBUS COUNTY      WHITEVILLE

PLAN DATE: March 2020      REVIEWED BY: G. G. Murr, Jr.

PREPARED BY: M. Ishak      REVIEWED BY: \_\_\_\_\_

REVISIONS	INIT.	DATE

SEAL  
NORTH CAROLINA  
PROFESSIONAL ENGINEER  
SEAL 14543  
G. G. MURR, JR.  
DocuSigned by:  
Gene G. Murr, Jr.  
SIGNATURE  
DATE  
CADD Filename:

