PROJ. REFERENCE NO.	SHEET NO.
B-5703	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the contract lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+26.00	0	0
12+50.00	4	9
13+00.00	9	45
13+50.00	9	78
14+00.00	8	126
14+50.00	9	204
15+00.00	11	234
15+50.00	25	227
15+94.00	25	345

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+91.30	0	0
18+00.00	6	4
18+50.00	20	19
19+00.00	41	10
19+50.00	54	1
20+00.00	61	0
20+50.00	74	0
21+00.00	50	3
21+50.00	25	5
21+57.00	1	1