Approximate quantities only. Borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJ. REFERENCE NO.	SHEET NO.
BR-0002	X-1A

Station Phase I L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+00.00	0	0
15+50.00	19	14
16+00.00	23	26
16+50.00	22	39
17+00.00	20	40
17+50.00	20	61
18+00.00	20	146
18+50.00	19	204
19+00.00	15	249
19+50.00	8	340
20+00.00	4	392
20+50.00	13	591
21+00.00	22	772
21+50.00	25	778
22+00.00	28	797
22+40.00	22	639

Station Phase I L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
25+20.00	0	0
25+50.00	0	299
26+00.00	0	319
26+50.00	0	95
27+00.00	0	46
27+50.00	4	25
28+00.00	4	6
28+50.00	21	10
29+00.00	38	10
29+50.00	26	3
30+00.00	42	6
30+50.00	215	6
31+00.00	335	0
31+50.00	265	0
32+00.00	137	0
32+25.00	13	0

Station Phase II L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+25.00	0	0
15+50.00	0	2
16+00.00	448	3
16+50.00	1724	14
17+00.00	3850	22
17+50.00	5796	19
18+00.00	5271	31
18+50.00	2704	31
19+00.00	1323	17
19+50.00	668	20
20+00.00	46	24
20+50.00	102	25
21+00.00	121	34

Station Phase II L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
21+50.00	82	31
22+00.00	69	22
22+40.00	84	15

Station Phase II L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
25+20.00	0	0
25+50.00	0	11
26+00.00	17	30
26+50.00	4	21
27+00.00	18	15
27+50.00	41	6
28+00.00	31	4
28+50.00	12	6
29+00.00	6	6
29+50.00	2	7
30+00.00	0	6
30+50.00	0	2
31+00.00	0	0
31+50.00	1	0
32+00.00	2	0
32+25.00	1	0

Station Y	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+70.00	0	0
12+00.00	26	0
12+50.00	2451	3
13+00.00	5608	0
13+50.00	7694	0
14+00.00	9913	0
14+50.00	9208	0
15+00.00	5018	0
15+58.54	2877	0

Station Dr1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+84.75	311	0

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+12.01	0	0
10+50.00	0	101
11+00.00	0	74
11+50.00	21	7
11+85.00	15	0

Station Dr1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+50.00	47	10
11+00.00	264	6
11+50.00	444	0