

# SUMMARY OF QUANTITIES - DRAINAGE

PROJECT NUMBER	COUNTY	BOX NUMBER	ROUTE	LONG	LAT	DESCRIPTION	BORROW EXCAVATION CY	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES TON	FOUNDATION CONDITIONING GEOTEXTILE SY	15" RC PIPE CULVERTS, CLASS III LF	18" RC PIPE CULVERTS, CLASS III LF	24" RC PIPE CULVERTS, CLASS III LF	30" RC PIPE CULVERTS, CLASS III LF	36" RC PIPE CULVERTS, CLASS III LF	48" RC PIPE CULVERTS, CLASS III LF	54" RC PIPE CULVERTS, CLASS III LF	6" PVC PIPE CULVERTS LF	PROJECT NO.	SHEET NO.	TOTAL NO.
																		I-5932A - 45873.3.2	13	
							INCIDENTAL STONE BASE TON	SHOULDER DRAIN LF												
I-5932A - 45873.3.1	HALIFAX	1	I-95 SB SHLD	-77.724186	36.263616	REMOVE & REPLACE DRAINAGE STRUCTURE	5	2	6				16							
		2	I-95 MED	-77.723906	36.263698	REMOVE & REPLACE DRAINAGE STRUCTURE	10	3	8	16		8								
		3	I-95 MED	-77.723632	36.264648	REMOVE & REPLACE DRAINAGE STRUCTURE	20	4	11	32										
		4	I-95 SB SHLD	-77.722728	36.268704	REMOVE & REPLACE PAVED DITCH & DAMAGED PIPE	20	2	6		16									
		5	I-95 MED	-77.722373	36.268993	REMOVE & REPLACE DRAINAGE STRUCTURE	10	3	8		24									
		6	I-95 NB SHLD	-77.722070	36.268944	REMOVE & REPLACE PAVED DITCH & DAMAGED PIPE	5	2	6		16									
		7	I-95 NB SHLD	-77.721835	36.269860	REMOVE & REPLACE DRAINAGE STRUCTURE, INSTALL PAVED DITCH	5	2	6		16									
		8	I-95 NB SHLD	-77.721411	36.271302	REMOVE & REPLACE CONCRETE APRON & DAMAGED PIPE	40	2	6		8	8								
		9	I-95 MED	-77.721678	36.271349	REMOVE & REPLACE DRAINAGE STRUCTURE	15	2	6			16								
		10	I-95 SB SHLD	-77.721954	36.271404	REMOVE & REPLACE DRAINAGE STRUCTURE	5	2	6			16								
		11	I-95 NB SHLD	-77.720798	36.273314	REMOVE & REPLACE PAVED DITCH & CONCRETE APRON	5													
		12	I-95 NB SHLD	-77.720417	36.274578	REMOVE & REPLACE PAVED DITCH														
		13	I-95 MED	-77.720671	36.274798	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	10	2	6	16										
		14	I-95 MED	-77.720279	36.276069	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	40	3	8		24									
		15	I-95 MED	-77.719123	36.279271	REMOVE & REPLACE DRAINAGE STRUCTURE	5													
		16	I-95 MED	-77.716049	36.286149	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	15													
		17	I-95 MED	-77.712057	36.294800	REMOVE & REPLACE DRAINAGE STRUCTURE	5	2	6					16				16		20
		18	I-95 SB SHLD	-77.711546	36.296975	REMOVE & REPLACE PAVED DITCH AND TRASH GRATE														
		19	I-95 NB SHLD	-77.709613	36.301504	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	60	1	3	8										
		20	I-95 NB SHLD	-77.709568	36.301598	REMOVE & REPLACE DAMAGED PIPE	35	1	3									8		
		21	I-95 MED	-77.708861	36.305455	REMOVE & REPLACE DRAINAGE STRUCTURE	5	1	3	8										
		22	I-95 SB SHLD	-77.708913	36.306375	REMOVE & REPLACE PAVED DITCH														
		23	I-95 MED	-77.707865	36.309185	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	5	1	3	8										
		24	I-95 MED	-77.706149	36.315615	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	20	3	8	24										
		25	I-95 MED	-77.705513	36.318047	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	10	2	6		16									
		26	I-95 SB SHLD	-77.705584	36.318887	REMOVE & REPLACE DAMAGED PIPE	200	5	14		40									
		27	I-95 MED	-77.705001	36.319977	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	10	2	6		16									
		28	I-95 SB SHLD	-77.704854	36.321563	REMOVE & REPLACE DRAINAGE STRUCTURE	10	2	6		16									
		29	I-95 MED	-77.704582	36.321565	REMOVE & REPLACE DAMAGED PIPE	10	1	3	8										
		30	I-95 NB SHLD	-77.697740	36.333098	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	5	2	6		16									
		31	I-95 SB SHLD	-77.698074	36.333527	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	10	3	8		24									
		32	I-95 SB SHLD	-77.697153	36.334591	REMOVE & REPLACE DAMAGED PIPE	10	2	6				16							
		33	I-95 MED	-77.696701	36.334653	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	60	2	6						16					
		34	I-95 MED	-77.695127	36.336361	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	5	2	6		16									
		35	I-95 MED	-77.692348	36.339435	REMOVE & REPLACE CONCRETE APRON & DAMAGED PIPE	15	2	6	16									16	20
		36	I-95 NB SHLD	-77.690476	36.341022	REMOVE & REPLACE DAMAGED PIPE		2	6									16		
		37	I-95 MED	-77.690481	36.341444	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	50	3	8		8						16		16	20
		38	I-95 MED	-77.689315	36.342714	REMOVE & REPLACE DRAINAGE STRUCTURE	20	2	6		16									
		39	I-95 MED	-77.688339	36.343788	REMOVE & REPLACE CONCRETE APRON AND PAVED DITCH														
		40	I-95 SB SHLD	-77.685658	36.347135	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	5	2	6		16									
		41	I-95 NB SHLD	-77.684032	36.348108	REMOVE & REPLACE DRAINAGE STRUCTURE	10	2	6		16									20
		42	I-95 SB SHLD	-77.684432	36.348473	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	5	3	8		24									
		43	I-95 MED	-77.682640	36.350116	REMOVE & REPLACE DRAINAGE STRUCTURE	20	2	6		16									
		44	I-95 MED	-77.680204	36.353339	REMOVE & REPLACE DRAINAGE STRUCTURE	5	2	6		16									
		45	I-95 SB SHLD	-77.678748	36.356051	REMOVE & REPLACE DAMAGED PIPE		2	6				16							
SAY																		500		
TOTAL							800	83	240	144	352	80	16	32	32	8	64		500	80