SUMMARY OF QUANTITIES - DRAINAGE

PROJECT NO.	SHEET NO.	TOTAL NO.
I-5932A - 45873.3.2	14	

PROJECT NUMBER	COUNTY	BOX NUMBER	ROUTE	LONG	LAT	DESCRIPTION	4" SHOULDER DRAIN PIPE	4" OUTLET PIPE FOR SHOULDER DRAINS	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	PIPE COLLARS	FLOWABLE FILL	MASONRY DRAINAGE STRUCTURES	MASONRY DRAINAGE STRUCTURES	FRAME WITH TWO GRATES, STD 840.22	GENERIC DRAINAGE ITEM-CONCRETE APRON	GENERIC DRAINAGE ITEM-TRASH GRATE FOR 24" RCP FES	4" CONCRETE PAVED DITCH	SEDIMENT CONTROL STONE	1/4" HARDWARE CLOTH
							LF	LF	EA	CY	CY	EA	LF	EA	EA	EA	SY	TON	LF
							2110000000-E	2121000000-E	2132000000-N	2253000000-E	2275000000-E	2286000000-N	2308000000-E	2365000000-N	2473000000-N	2473000000-N	2619000000-E	6012000000-E	6042000000-E
I-5932A - 45873.3.1	HALIFAX	1	I-95 SB SHLD	-77.724186	36.263616	REMOVE & REPLACE DRAINAGE STRUCTURE		10	1	1.1052		1		1				5	40
		2	I-95 MED	-77.723906	36.263698	REMOVE & REPLACE DRAINAGE STRUCTURE				1.3506		1		1				5	40
		3	I-95 MED	-77.723632	36.264648	REMOVE & REPLACE DRAINAGE STRUCTURE				1.596		1		1				5	40
		4	I-95 SB SHLD	-77.722728	36.268704	REMOVE & REPLACE PAVED DITCH & DAMAGED PIPE				0.893							20	5	40
		5	I-95 MED	-77.722373	36.268993	REMOVE & REPLACE DRAINAGE STRUCTURE				1.3395		1		1				5	40
		6	I-95 NB SHLD	-77.722070	36.268944	REMOVE & REPLACE PAVED DITCH & DAMAGED PIPE				0.893							10	5	40
		7	I-95 NB SHLD	-77.721835	36.269860	REMOVE & REPLACE DRAINAGE STRUCTURE, INSTALL PAVED DITCH				0.893		1		1			30	5	40
		8	I-95 NB SHLD	-77.721411	36.271302	REMOVE & REPLACE CONCRETE APRON & DAMAGED PIPE				0.9991					1			5	40
		9	I-95 MED	-77.721678	36.271349	REMOVE & REPLACE DRAINAGE STRUCTURE				1.1052		1		1				5	40
		10	I-95 SB SHLD	-77.721954	36.271404	REMOVE & REPLACE DRAINAGE STRUCTURE				1.1052		1		1				5	40
		11	I-95 NB SHLD	-77.720798	36.273314	REMOVE &REPLACE PAVED DITCH & CONCRETE APRON									1		20	5	40
		12	I-95 NB SHLD	-77.720417	36.274578	REMOVE & REPLACE PAVED DITCH												5	40
		13	I-95 MED	-77.720671	36.274798	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				0.798		1		1			20	5	40
		14	I-95 MED	-77.720279	36.276069	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				1.3395		1	1	1			30	5	40
		15	I-95 MED	-77.719123	36.279271	REMOVE & REPLACE DRAINAGE STRUCTURE						1	5	1				5	40
		16	I-95 MED	-77.716049	36.286149	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH						1	3	1			20	5	40
		17	I-95 MED	-77.712057	36.294800	REMOVE & REPLACE DRAINAGE STRUCTURE	20	20	1	1.528		1		1				5	40
		18	I-95 SB SHLD	-77.711546	36.296975	REMOVE & REPLACE PAVED DITCH AND TRASH GRATE										1	10	5	40
		19	I-95 NB SHLD	-77.709613	36.301504	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				0.399		1		1			20	5	40
		20	I-95 NB SHLD	-77.709568	36.301598	REMOVE & REPLACE DAMAGED PIPE				2.579								5	40
		21	I-95 MED	-77.708861	36.305455	REMOVE & REPLACE DRAINAGE STRUCTURE				0.399		1		1				5	40
		22	I-95 SB SHLD	-77.708913	36.306375	REMOVE & REPLACE PAVED DITCH											50	5	40
		23	I-95 MED	-77.707865	36.309185	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				0.399		1		1			20	5	40
		24	I-95 MED	-77.706149	36.315615	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				1.197		1		1			20	5	40
		25	I-95 MED	-77.705513	36.318047	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				0.893		1		1			20	5	40
		26	I-95 SB SHLD	-77.705584	36.318887	REMOVE & REPLACE DAMAGED PIPE				2.2325								5	40
		27	I-95 MED	-77.705001	36.319977	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				0.893		1		1			20	5	40
		28	I-95 SB SHLD	-77.704854	36.321563	REMOVE & REPLACE DRAINAGE STRUCTURE				0.893		1		1				5	40
		29	I-95 MED	-77.704582	36.321565	REMOVE & REPLACE DAMAGED PIPE				0.4465								5	40
		30	I-95 NB SHLD	-77.697740	36.333098	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				0.893		1		1			140	5	40
		31	I-95 SB SHLD	-77.698074	36.333527	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				1.3395		1		1			20	5	40
		32	I-95 SB SHLD	-77.697153	36.334591	REMOVE & REPLACE DAMAGED PIPE				1.312								5	40
		33	I-95 MED	-77.696701	36.334653	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				1.528		1	1	1			10	5	40
		34	I-95 MED	-77.695127	36.336361	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				0.798		1		1			20	5	40
		35	I-95 MED	-77.692348	36.339435	REMOVE & REPLACE CONCRETE APRON & DAMAGED PIPE	20	20		0.798					1			5	40
		36	I-95 NB SHLD	-77.690476	36.341022	REMOVE & REPLACE DAMAGED PIPE				2.026								5	40
		37	I-95 MED	-77.690481	36.341444	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH	20	20		2.4725		1	1	1			20	5	40
		38	I-95 MED	-77.689315	36.342714	REMOVE & REPLACE DRAINAGE STRUCTURE				0.893		1		1				5	40
		39	I-95 MED	-77.688339	36.343788	REMOVE & REPLACE CONCRETE APRON AND PAVED DITCH									1		10	5	40
		40	I-95 SB SHLD	-77.685658	36.347135	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				0.893		1	1	1			10	5	40
		41	I-95 NB SHLD	-77.684032	36.348108	REMOVE & REPLACE DRAINAGE STRUCTURE	20	20		0.893		1		1				5	40
		42	I-95 SB SHLD	-77.684432	36.348473	REMOVE & REPLACE DRAINAGE STRUCTURE AND PAVED DITCH				1.3395		1	1	1			20	5	40
		43	I-95 MED	-77.682640	36.350116	REMOVE & REPLACE DRAINAGE STRUCTURE				0.893		1		1				5	40
		44	I-95 MED	-77.680204	36.353339	REMOVE & REPLACE DRAINAGE STRUCTURE				0.893		1		1				5	40
		45	I-95 SB SHLD	-77.678748	36.356051	REMOVE & REPLACE DAMAGED PIPE				1.1052								5	40
		SAY								44	50								
		TOTAL					**80**	**90**	**2**	**44**	**50**	**30**	**13**	**30**	**4**	**1**	**560**	**225**	**1,800**