5/14/99

CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 4

NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE – B AND TEMPORARY ROCK SILT CHECKS TYPE – A AT DRAINAGE OUTLETS.

HNTB
HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

PROJECT REFERENCE NO.	SHEET NO.
U-4906	EC-4/CONST.4
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

BEGIN TIP PROJECT U-4906
-L- POT STA 30+50.00

-L-
PI Sta 39+57.87
△ = 9° 23' 12.8" (RT)
D = 3° 51' 19.7"
L = 243.47'
T = 122.01'
R = 1,486.09'
SE = EXISTING

NAD 83/ NSRS 2007

30 35 40

-L- PT Sta. 30+45.55

BARBARA BURWELL
DB 1769 PG 770
MB 42 PG 150

WILLIAM CUMMINGS ESTATE

MENDRA C. RHODES

WANDA D. VERNON, et al

JONNY CUMMINGS, et ux

MINNIE ELLIS CUMMINGS

ST. PAUL FREEWILL BAPTIST CHURCH

KATRINA COWAN

MINNIE ELLIS CUMMINGS

LESTINA MILLS

RALPH KINSEY, SR., et al

WD DECK W/ SWIMMING POOL

NOTE: CENTURY-LINK RECORDS INDICATE A BURIED F.O. HAND HOLE IN THIS VICINITY. UNABLE TO FIELD LOCATE THIS STRUCTURE.

CUT & EXPOSED CATV CABLES

S 60° 52' 46.5" E

-L- SR1308 BRANCH RD.
22' PAVED ROADWAY

S 51° 29' 33.7" E

-L- PC Sta. 38+35.86

-L- PT Sta. 40+79.33

MATCH LINE -L- STA 43+50.00
SEE SHEET 5

WILLIAM CUMMINGS ESTATE
DB 210 PG 217
MB 12 PG 44

MINNIE ELLIS CUMMINGS

JORE M. PARKER, et ux

MENDRA W. CUMMINGS LIFE ESTATE

GWENDOLYN CUMMINGS

ONWASA (CUMMINGS FAMILY CEMETERY)

ONWASA

LOUIS A. ADAMS, et ux

ARTHINE S. THOMAS

DESIGN EXCEPTION REQUESTED FOR LANE WIDTHS (11') AND USABLE SHOULDER (4' MINIMUM)

NOTE: ALL DRIVEWAY RADII ARE 10' UNLESS OTHERWISE NOTED.

FOR -L- PROFILE, SEE SHEET 27

1/11/2018
U-4906_EC-4_Const-4.dgn
HNTB