

PROJECT NO.	SHEET NO.	TOTAL NO.
2022CPT.05.08.10731.1, etc.	17	

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E	0264000000-E	1220000000-E	1260000000-E	1297000000-E	1330000000-E	1503000000-E	1519000000-E	1575000000-E	1704000000-E	2591000000-E	2600000000-N	2613000000-N	2830000000-N	2845000000-N	6000000000-E	6071010000-E	6084000000-E	6117000000-N	7444000000-E			
											BORROW EXCAVATION	SHOULDER GRADING	INCIDENTAL STONE BASE	AGGREGATE SHOULDER BORROW	1 1/2" MILLING	2 1/2" MILLING	INCIDENTAL MILLING	INTERMEDIATE COURSE, 119.0C	SURFACE COURSE, S9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	4" Concrete Sidewalk	Retrofit Existing Curb Ramps	Remove and Replace Curb Ramps	ADJUST MANHOLES	ADJUST METER OR VALVE BOX	TEMPORARY SILT FENCE	WATTLE	SEED & MULCHING	RESPONSE FOR EROSION CONTROL	INDUCTIVE LOOP SAWCUT		
											MI	FT	CY	SMI	TONS	TON	SY	SY	SY	TONS	TONS	TON	TONS	EA	EA	EA	EA	LF	LF	AC	EA	LF	
2022CPT.05.03.10731.1	Person	1	NC 158 - LEASBURG RD	SR 1307 - JOHN D WINSTEAD RD TO NC 49 - BURLINGTON RD	3	2	NO	NO	2.76	26-36			182		42,349		880		3,762	252	40												
		2	NC 49 - BURLINGTON RD	SR 1153 - CHRITCHER WILKERSON RD TO N SIDE OF US 158 - LEASBURG RD	3	2	NO	NO	0.48	40					11,264		870		1,113	75	30											408	
<b>TOTAL FOR PROJ NO. 2022CPT.05.03.10731.1</b>								<b>3.24</b>					<b>182</b>		<b>53,613</b>		<b>1,750</b>		<b>4,875</b>	<b>327</b>	<b>70</b>										<b>408</b>		
2022CPT.05.03.20731.1	Person	3	SR 1131 - CATES MILL RD	SR 1129 - FRANK TIMBERLAKE RD. TO US 501 - DURHAM RD.	1	2	NO	NO	1.36	26-36	7	2.72	68	238		375		2,056	138	300						10	30	0.10					
		4	SR 1134 - SATTERFIELD RD	NC 157 - HURDLE MILLS RD TO SR 1123 - DICK HOLEMAN RD	1	2	NO	NO	3.85	22	80	7.70	193	569		1,440		8,886	595	1,000						112	280	1.12					
		5	SR 1340 - CONCORD CEFFO RD	SR 1337 - MEGHEES MILL RD TO NC 57 - SEMORA RD	3	2	NO	NO	1.37	24			67		19,290		946		1,744	117	20												
		6	SR 1409 - MORGAN ST	US 158 - LEASBURG RD TO SR 1363 - REAMS AVE	3	2	NO	NO	0.978	24-42					21,261		4,090		1,848	124		9	1	3	3	2						2,214	
		7	SR 1504 - HIGH PLAINS RD	NC 49 - VIRGILINA RD TO SR 1501 - MAYO LAKE RD	2	2	NO	NO	2.65	22	40	5.30	133	417		34,203	254	4,943	2,994	438	100						58	150	0.58				
		8	SR 1504 - HIGH PLAINS RD	SR 1501 - MAYO LAKE RD TO VIRGINIA LINE	1	2	NO	NO	0.86	20	43	1.72	43	80			300		913	61	50						63	160	0.63	1			
		9	SR 1512 - BOWMANTOWN RD	NC 49 - VIRGILINA RD TO US 501 - BOSTON RD	1	2	NO	NO	4.38	24	110	8.76	218	607			635		5,509	369	1,000						160	400	1.59				
		10	SR 1568 - THOMAS STORE RD	SR 1567 - PRIXLEY PRICHARD RD TO US 158 - OXFORD RD	1	2	NO	NO	1.63	20	33	3.26	82	241			258		1,687	113	350						47	120	0.47	1			
		<b>TOTAL FOR PROJ NO. 2022CPT.05.03.20731.1</b>								<b>17.078</b>			<b>313</b>	<b>29.46</b>	<b>804</b>	<b>2,152</b>	<b>40,551</b>	<b>34,203</b>	<b>8,298</b>	<b>4,943</b>	<b>25,637</b>	<b>1,955</b>	<b>2,820</b>	<b>9</b>	<b>1</b>	<b>3</b>	<b>3</b>	<b>2</b>	<b>450</b>	<b>1,140</b>	<b>4.49</b>	<b>2</b>	<b>2,214</b>
		<b>GRAND TOTAL</b>								<b>20.318</b>			<b>313</b>	<b>29.46</b>	<b>986</b>	<b>2,152</b>	<b>94,164</b>	<b>34,203</b>	<b>10,048</b>	<b>4,943</b>	<b>30,512</b>	<b>2,282</b>	<b>2,890</b>	<b>9</b>	<b>1</b>	<b>3</b>	<b>3</b>	<b>2</b>	<b>450</b>	<b>1,140</b>	<b>4.49</b>	<b>2</b>	<b>2,622</b>