ITEM NO.

DESC. NO.

4048000000 4060000000

4066000000

4072000000 4079000000 4096000000

4108000000 4110000000 4110000000 4155000000

4158000000

SECT.

907

## STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

# SIGNING PLAN DAVIDSON COUNTY

LOCATION: US 29 /US 70 AT OLD GREENSBORO ROAD /DCCC ROAD

# TIP NO. SHEET NO. R-5737 SIGN - 1

**DOCUMENT NOT CONSIDERED FINAL** UNLESS ALL SIGNATURES COMPLETED

#### ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018, INCLUDING REVISIONS THERETO, ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901D10	TYPE 'A' SIGNS
901D20	TYPE 'B' SIGNS
901.50	ARROWS AND SHIELDS
901.70	SIGN STRINGERS AND SUPPORT SPACING
901.80	SIGN MOUNTING DETAILS - TYPE A AND TYPE B SIGNS
903.10	GROUND MOUNTED SIGN SUPPORTS
903.40	MEDIAN BARRIER SIGN SUPPORT AND ANCHORAGE
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE 'D', 'E', AND 'F' SIGNS ON 'U' CHANNEL POSTS
910.40	ROUNDABOUT SIGNING WITH PEDESTRIANS

#### PAY ITEM NOTES

- 1. DISPOSAL OF SIGN SYSTEM, U-CHANNEL
- 2. DISPOSAL OF SIGN SYSTEM, WOOD
- 3. SIGN ERECTION, TYPE A (GROUND MOUNTED)
- 4. SIGN ERECTION, TYPE B (GROUND MOUNTED)
- 5. SIGN ERECTION, TYPE D, E, AND F
- 6. SUPPORTS, BARRIER MOUNTED, SMALL
- 7. STREET NAME SIGN SYSTEM TO BE REMOVED/RELOCATED BY OTHERS
- 8. WAYFINDING SIGN SYSTEM TO BE REMOVED/RELOCATED BY OTHERS

### GENERAL NOTES

- . SIGNS FURNISHED BY STATE
- . CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE DEPARTMENT FURNISHED SIGNS WILL BE REQUIRED.
- . ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS
- OTHERWISE INDICATED ON THE PLANS.
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION SIGNING OR TEMPORARY
- PAVEMENT MARKINGS. SEE THE TRANSPORTATION MANAGEMENT PLAN (TMP).
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE
- REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING. . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.


## SUMMARY OF QUANTITIES ITEM DESCRIPTION |QUANTITY| UNIT REINFORCED CONCRETE SIGN FOUNDATION SUPPORTS, BREAKAWAY STEEL BEAM SUPPORTS, SIMPLE STEEL BEAM SUPPORTS, 3 LB STEEL U-CHANNEL SUPPORTS, BARRIER (SMALL) SIGN ERECTION, TYPE D SIGN ERECTION, TYPE E SIGN ERECTION, TYPE F SIGN ERECTION, TYPE F SIGN ERECTION, TYPE A (GROUND MOUNTED) SIGN ERECTION, TYPE B (GROUND MOUNTED) DISPOSAL OF SIGN SYSTEM, U-CHANNEL DISPOSAL OF SIGN SYSTEM, WOOD 7 C.Y. 2736 LB 1360 LB 1422 L.F 2 EA. 5 EA. 80 EA. 11 EA. 8 EA. 4 EA. 70 EA.

### **INDEX**

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2	SUPPORT INFORMATION
SIGN-2A	REVISED SIGNING ROADWAY STANDARD DRAWING 901D10
SIGN-2B	REVISED SIGNING ROADWAY STANDARD DRAWING 901D20
SIGN-3-3D	SIGN DESIGNS
SIGN-3E-3F	TYPE E AND F SIGNS
SIGN-4-6	EXISTING SIGNS
SIGN-7-14	PROPOSED SIGNING

PLAN REVIEWED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

KELVIN L. JORDAN SIGNING & DELINEATION REGIONAL ENGINEER ERIC E. WARD SIGNING & DELINEATION DESIGN ENGINEER



3 | EA.

PLAN PREPARED BY: Dewberry Engineers Inc.

J. TODD BROOKS, P.E. SIGNING PROJECT MANAGER PETER G. PADILLA, P.E SIGNING PROJECT ENGINEER Dewberry

2610 WYCLIFF ROAD