

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
STANLY, ROWAN, AND DAVIDSON COUNTY

LOCATION: Replace Bridge No.3 over the Yadkin River and Winston-Salem
Southbound Railroad on NC 49

B-4626
SIGN 1
NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
APPROVED: _____
DATE: _____
SEAL:

INCOMPLETE PLANS
DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901.50	ARROWS AND SHIELDS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS

GENERAL NOTES

- . SIGNS FURNISHED BY STATE
- . CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE DEPARTMENT FURNISHED SIGNS WILL BE REQUIRED.
- . ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- . ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

<p>401 QUANTITY REQ'D 4</p> <p>24" X 30" R4-7</p> <p>ONE "U" POSTS PER SIGN</p>	<p>402 QUANTITY REQ'D 1</p> <p>36" X 36" W1-2L</p> <p>ONE "U" POSTS PER SIGN</p>	<p>403 QUANTITY REQ'D 1</p> <p>24" X 24" W13-1</p> <p>MOUNT ABOVE SIGN 402 IN 1. INSTALLATIONS</p>	<p>404 QUANTITY REQ'D 4</p> <p>18" X 24" W1-8L</p> <p>MOUNT ABOVE SIGN 302 IN 1. INSTALLATIONS</p> <p>ONE "U" POSTS PER SIGN</p>
<p>405 QUANTITY REQ'D 3</p> <p>30" X 30" R1-1</p> <p>ONE "U" POSTS PER SIGN</p>	<p>406 QUANTITY REQ'D 8</p> <p>36" X 24" R5-1a</p> <p>ONE "U" POSTS PER SIGN</p>	<p>407 QUANTITY REQ'D 6</p> <p>36" X 36" R5-1</p> <p>ONE "U" POSTS PER SIGN</p>	<p>408 QUANTITY REQ'D 2</p> <p>36" X 36" W4-2L</p> <p>ONE "U" POSTS PER SIGN</p>
<p>409 QUANTITY REQ'D 1</p> <p>36" X 36" W9-2R</p> <p>ONE "U" POSTS PER SIGN</p>			

SUMMARY OF QUANTITIES

ITEM NO.		ITEM DESCRIPTION	QUANTITY	UNIT
DESC. NO.	SECT. NO.			
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL	966	L.F.
4096000000	904	SIGN ERECTION, TYPE D	13	EA.
4102000000	904	SIGN ERECTION, TYPE E	30	EA.
4116100000	904	SIGN ERECTION, RELOCATE SIGN TYPE E (GROUND MOUNTED)	1	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	33	EA.
4238000000	907	DISPOSAL OF SIGN, D, E OR F	1	EA.

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

KELVIN JORDAN SIGNING & DELINEATION REGIONAL ENGINEER
WALTER JOHNSON SIGNING & DELINEATION PROJECT DESIGN ENGINEER

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE AND "E" SIGNS SHEET
SIGN-2 & 2A	SIGN DESIGN
SIGN-3-6	SIGNING PLAN SHEETS

T.I.P.: B-4626