

GENERAL DRAWING INFORMATION IS TAKEN FROM THE ORIGINAL PLANS AND THE ROUTINE INSPECTION REPORT DATED 07/14/2020.

BRIDGE ORIENTATION CONFORMS TO EXISTING BRIDGE PLANS.

SCOPE OF WORK

- REMOVE ASPHALT WEARING SURFACE AND PARTIALLY REMOVE BRIDGE DECK CONCRETE BY SCARIFICATION AND SHOTBLASTING METHODS.
- OVERLAY PREPARED BRIDGE DECK WITH POLYMER CONCRETE (PC).
- GROOVE POLYMER CONCRETE (PC) BRIDGE DECK.
- CLEAN AND PAINT BEARINGS WITH HRCSA.
- CLEAN, REPAIR, AND PAINT STEEL I-BEAMS.
- INSTALL FOAM JOINT SEALS.
- REMOVE UNSOUND CONCRETE AND PROPERLY PREPARE SHOTCRETE AND CONCRETE REPAIR AREAS.
- PERFORM SHOTCRETE AND CONCRETE REPAIRS IN PREPARED AREAS.
- EPOXY INJECTION OF CONCRETE CRACKS.
- REMOVE DEBRIS FROM TOP OF BENT AND END BENT CAPS AND APPLY EPOXY COATING.

I HEREBY CERTIFY THAT THIS STRUCTURE WAS REHABILITATED ACCORDING TO THESE PLANS OR AS NOTED HEREIN.

RESIDENT ENGINEER

DATE

PROJECT NO. I-5746C

MECKLENBURG COUNTY

BRIDGE NO. 590320

SHEET 1 OF 2

DocuSigned by:

02EE938FAB674C5...

OZEE938FAB674C5...

OZEE938FAB674C5...

OZEE938FAB674C5...

SEAL

35647

OZEE938FAB674C5...

SEAL

35647

OZEE938FAB674C5...

OZEE

8/23/2021


STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION


RALEIGH

GENERAL DRAWING
FOR BRIDGE ON I-277
OVER N. BREVARD STREET

REVISIONSSHEET NODOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETEDNO. BY: DATE: NO. BY: DATE: SHEETSDATE: SHEETS



SECTION ALONG & BRIDGE



R.L.PUTEK/E. BAYISSA

H.A. LOCKLEAR

DRAWN BY : .

CHECKED BY :