

²³⁻AUG-2021 11:57 R:\Structures\FINAL PLANS\Bridge 322\405_027_I5746C_SMU_B2BNB_S5-14_590322.dgn aacole

		SPAN C
		SPAN B

AS-BUILT REPA	AS-BUILT REPAIR QUANTITY TABLE						
BENT 2 NORTHBOUND	QUANTI ESTIMATE		TIES ACTUAL				
SHOTCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.			
САР	43.3	21.7					
COLUMN & STRUTS	6.6	3.3					
CONCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.			
САР	12.0	6.0					
COLUMN & STRUTS	0.0	0.0					
EPOXY RESIN INJEC	LIN. FT.		LIN. FT.				
САР	1.0						
COLUMN & STRUTS	4.0						
EPOXY COATIN	SQ. FT.		SQ. FT.				
TOP OF BENT CAP & STRUT	316						

VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE, MINIMUM OF 1"BEHIND REBAR AND MINIMUM 2"CLEARANCE TO SAWCUT.SEE "TYPICAL CAP AND COLUMN REPAIR DETAILS" SHEET.

NOTES

REPAIR LOCATIONS AND ESTIMATE OF QUATITIES ARE GIVEN BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATION AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

CONCRETE REPAIRS MAY BE SUBSTITUTED IN LIEU OF SHOTCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.

FOR SHOTCRETE REPAIR, SEE SPECIAL PROVISION.

FOR CONCRETE REPAIR, SEE SPECIAL PROVISION.

FOR EPOXY RESIN INJECTION, SEE SPECIAL PROVISION.

CLEAN AND REMOVE DEBRIS FROM THE TOP OF THE CAP AND STRUTS.EPOXY COATING SHALL BE APPLIED TO THE TOP SURFACE OF THE CAP AND STRUTS. THE CONTRACTOR SHALL NOT COAT THE AREA OF THE CAP BENEATH THE MASONRY PLATES.FOR EPOXY COATING, SEE SPECIAL PROVISIONS.

AFTER SATISFACTORY COMPLETION OF SHOTCRETE. CONCRETE AND ERI REPAIRS, REPAIR EXISTING MURAL PAINT ON BENTS AND GIRDERS, AS APPROPRIATE.

CONCRETE REPAIR AREA

SHOTCRETE REPAIR AREA

----- EPOXY RESIN INJECTION (ERI)

	PROJ. NO		<u>I-5746C</u>					
	ME	CKLEN	NBUR	<u> </u>	DUNTY			
	BRIDGE NO. 590322							
CocuSigned by: SHEET 1 OF 2								
02EE938FAB674C5	STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH							
SEAL 35647 WILLING A. COLUMN	BENT 2 NORTHBOUND SPAN B FACE							
8/23/2021				TACL				
	REVISIONS SHEET NO.							
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	№. вт: 1 2	DATE:	NO. ВҮ: 33 44,	DATE:	S5-14 TOTAL SHEETS 274			