

NOTES:

+

+

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE. FOR SECTION B-B, SEE ``JOINT DETAILS' SHEET. FOR CONCRETE DECK REPAIR FOR PC OVERLAY, SEE SPECIAL PROVISIONS. FOR PC MATERIALS, SEE SPECIAL PROVISIONS. APPROX.CLASS II SURFACE PREPARATION ← EPOXY RESIN INJECTION (ERI)

| DRAWN BY : | R.L.PUTEK/E. BAYISSA | DATE | <u>. 07/2021</u> |
|--------------|----------------------|------|------------------|
| CHECKED BY : | H.A. LOCKLEAR | DATE | <u>. 07/2021</u> |
| | | | |

PLAN

| AS-BUILT REPAIR QU | JANTITY T | ABLE | | | |
|-------------------------------------|---------------|--------|--|--|--|
| TOP OF DECK REPAIRS | | | | | |
| | ESTIMATE | ACTUAL | | | |
| SCARIFYING BRIDGE DECK | 964 SQ.YDS. | | | | |
| CLASS II SURFACE PREPARATION | 26.3 SQ. YDS. | | | | |
| CONCRETE DECK REPAIR FOR PC OVERLAY | 26.3 SQ. YDS. | | | | |
| SHOTBLASTING BRIDGE DECK | 964 SQ.YDS. | | | | |
| PLACING AND FINISHING PC OVERLAY | 964 SQ.YDS. | | | | |
| GROOVING BRIDGE FLOORS | 8,225 SQ.FT. | | | | |
| PC MATERIALS | 44.8 CU.YDS. | | | | |

TOP OF DECK REPAIR QUANTITIES REPRESENT ESTIMATED VALUES OF CLASS II SURFACE PREPARATION AND CONCRETE DECK REPAIR FOR PC OVERLAY AFTER REMOVAL OF UNSOUND CONCRETE. (MIN. 2"CLEAR TO SAWCUT). SEE OVERLAY SURFACE PREPARATION FOR POLYMER CONCRETE SPECIAL PROVISION.

>--- 2.3 SY
CLASS II
SURFACE PREP.

| | PROJECT NO. <u>I-5746C</u> <u>MECKLENBURG</u> county BRIDGE NO. <u>590326</u> | | | | |
|--|---|--|--|--|--|
| DocuSigned by: SHEET 2 OF 3 | | | | | |
| STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH | | | | | |
| THE STONE | DECK SURFACE REPAIR | | | | |
| OFESSION A CONTINUE | SPAN B | | | | |
| 8/23/2021 | | | | | |
| | REVISIONS SHEET NO. | | | | |
| DOCUMENT NOT CONSIDERED | NO. BY: DATE: NO. BY: DATE: S6-5 | | | | |
| FINAL UNLESS ALL SIGNATURES COMPLETED | 1 3 TOTAL 3 274 | | | | |