

23-AUG-2021 11:58 R:\Structures\FINAL PLANS\Bridge 327\407_001_I5746C_SMU_GD_S7-01_590327.dgn aacole

+

+

F.A. PROJECTS NO: NHPIM-0277(19)

NOTES

GENERAL DRAWING INFORMATION IS TAKEN FROM THE ORIGINAL PLANS AND THE ROUTINE INSPECTION REPORT DATED 07/24/2020.

BRIDGE ORIENTATION CONFORMS TO EXISTING BRIDGE PLANS.

SCOPE OF WORK

REMOVE ASPHALT WEARING SURFACE AND PARTIALLY REMOVE BRIDGE DECK CONCRETE BY SCARIFICATION AND SHOTBLASTING METHODS.
OVERLAY PREPARED BRIDGE DECK WITH POLYMER CONCRETE (PC).
GROOVE POLYMER CONCRETE (PC) BRIDGE DECK.
CLEAN AND REPAIR STEEL I-BEAMS.
CLEAN BEARINGS AND APPLY HRCSA.
INSTALL FOAM JOINT SEALS.
SPOT PAINTING OF STEEL STRUCTURE REPAIR AREAS.
REMOVE UNSOUND CONCRETE AND PROPERLY PREPARE SHOTCRETE AND CONCRETE REPAIR AREAS.
PERFORM SHOTCRETE AND CONCRETE REPAIRS IN PREPARED AREAS.
EPOXY INJECTION OF CONCRETE CRACKS.
REMOVE DEBRIS FROM TOP OF END BENT AND BENT CAPS AND END BENT BACKWALLS, AND APPLY EPOXY COATING.

ITATED DATE	DocuSigned by:	PROJECT NO. <u>I-5746C</u> <u>MECKLENBURG</u> COUNTY BRIDGE NO. <u>590327</u> SHEET 1 OF 2					
	DZEE938FAB674CS	STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH GENERAL DRAWING FOR BRIDGE ON I-277 OVER N. TRYON STREET					
DO	DCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	NO. BY: 1 2	REVI DATE:	SION: NO. 3	5 BY:	DATE:	SHEET NO. S7-1 TOTAL SHEETS 274