

AS-BUILT REPAIR QUANTITY TABLE



TOP OF DECK REPAIRS		
	ESTIMATE	ACTUAL
SCARIFYING BRIDGE DECK	2004 SQ. YDS.	
CLASS II SURFACE PREPARATION	1.0 SQ. YDS.	
CONCRETE DECK REPAIR FOR PC OVERLAY	1.0 SQ. YDS.	
SHOTBLASTING BRIDGE DECK	2004 SQ. YDS.	
PC MATERIALS	97.4 CU. YDS.	
PLACING AND FINISHING PC OVERLAY	2004 SQ. YDS.	
GROOVING BRIDGE FLOORS	17130 SQ. FT.	


TOP OF DECK REPAIR QUANTITIES REPRESENT ESTIMATED VALUES OF CLASS II SURFACE PREPARATION AND CONCRETE DECK REPAIR FOR PC OVERLAY AFTER REMOVAL OF UNSOUND CONCRETE. (MIN. 2" CLEAR TO SAWCUT). SEE OVERLAY SURFACE PREPARATION FOR POLYMER CONCRETE SPECIAL PROVISION.

NOTES:

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

- FOR SECTION B-B, SEE "JOINT DETAILS" SHEET.
- THE EXISTING CONCRETE ISLAND ON SPAN F SHALL BE REMOVED.
- FOR CONCRETE DECK REPAIR FOR PC OVERLAY, SEE SPECIAL PROVISION.
- FOR PC MATERIALS, SEE SPECIAL PROVISION.


-  APPROX. CLASS II SURFACE PREPARATION
-  EPOXY RESIN INJECTION (ERI)



PLAN

PROJECT NO. I-5746C
MECKLENBURG COUNTY
 BRIDGE NO. 590332

SHEET 3 OF 11



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 DECK SURFACE REPAIR
 SPAN E & F

DRAWN BY : R.L. PUTEK/E. BAYISSA DATE : 07/2021
 CHECKED BY : H. A. LOCKLEAR DATE : 07/2021

NO.	REVISIONS			NO.	REVISIONS			SHEET NO.
	BY:	DATE:			BY:	DATE:		
1				3			S10-7	
2				4			TOTAL SHEETS 274	

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED