

+

+

23-AUG-2021 12:04 R:\Structures\FINAL PLANS\Bridge 332\410_103_I5746C_SMU_B6F_S10-52_590332.dgn aacole

REPAIR LOCATIONS AND ESTIMATE OF QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE

| AS-BUILT REPAIR QUANTITY TABLE | | | | | |
|--------------------------------|----------------|------------------|----------------|------------------|--|
| BENT 6 | QUANTITIES | | | | |
| DENIO | ESTIMATE | | ACTUAL | | |
| SHOTCRETE REPAIRS | AREA SQ.FT. | VOLUME CU.FT. | AREA SQ.FT. | VOLUME CU.FT. | |
| САР | 54.2 | 27.1 | | | |
| COLUMNS & STRUTS | 45.4 | 22.7 | | | |
| | | | | | |
| CONCRETE REPAIRS | AREA SQ.FT. | VOLUME CU.FT. | AREA SQ.FT. | VOLUME CU.FT. | |
| САР | 15.1 | 7.6 | | | |
| | | | | | |
| | | | | | |
| EPOXY RESIN INJECTION | | LIN.FT | | LIN.FT | |
| САР | | 7 . 5 | | | |
| COLUMNS & STRUTS | | 0.0 | | | |
| | | | | | |
| EPOXY COATING | | SQ.FT. | | SQ.FT. | |
| TOP OF BENT CAP & STRUTS | | 417 | | | |

VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE, MIN. OF 1" BEHIND REBAR AND 2" MIN. CLEAR TO SAWCUT. FOR REPAIR DETAILS, SEE "TYPICAL CAP AND COLUMN REPAIR DETAILS" SHEET.

-2.3 SF SHOTCRETE REPAIR

| <u> </u> | ECT NO. <u>I-5746C</u> <u>ECKLENBURG</u> county GE NO. <u>590332</u> | | | | |
|--|--|--|--|--|--|
| DocuSigned by: | 2 OF 4 | | | | |
| 02EE938FAB674C5 D | STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH | | | | |
| W 8/23/2021 | BENT 6 SPAN F FACE | | | | |
| | REVISIONS SHEET NO. | | | | |
| DOCUMENT NOT CONSIDERED | | | | | |
| FINAL UNLESS ALL 1 SIGNATURES COMPLETED 2 | 3 TOTAL SHEE TS 274 | | | | |