

23-AUG-2021 12:05 R:\Structures\FINAL PLANS\Bridge 332\410_153_I5746C_SMU_B11L_S10-77_590332.dgn

AS-BUILT REPAIR QUANTITY TABLE										
BENT 11	QUANTITIES									
	ESTI	ΜΑΤΕ	ACTUAL							
SHOTCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.						
САР	67.0	33.5								
COLUMNS & STRUTS	19.9	10.0								
CONCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.						
САР	10.5	5.3								
EPOXY RESIN INJECTION		LIN.FT.		LIN.FT.						
САР	0.0									
COLUMNS & STRUTS		0.0								
EPOXY COATING		SQ.FT.		SQ.FT.						
TOP OF BENT CAP & STRUTS	208									

VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE, MIN. OF 1" BEHIND REBAR AND 2" MIN. CLEAR TO SAWCUT. FOR REPAIR DETAILS, SEE ``TYPICAL CAP AND COLUMN REPAIR DETAILS" SHEET.

NOTES

REPAIR LOCATIONS AND ESTIMATE OF QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

CONCRETE REPAIRS MAY BE SUBSTITUTED IN LIEU OF SHOTCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.

FOR SHOTCRETE REPAIR, SEE SPECIAL PROVISIONS.

FOR CONCRETE REPAIR, SEE SPECIAL PROVISIONS.

FOR EPOXY RESIN INJECTION, SEE SPECIAL PROVISIONS.

CLEAN AND REMOVE DEBRIS FROM THE TOP OF THE CAP AND STRUTS AND APPLY EPOXY PROTECTIVE COATING.EPOXY COATING SHALL BE APPLIED TO THE TOP SURFACE OF THE CAP AND STRUTS.THE CONTRACTOR SHALL NOT COAT THE AREA OF THE CAP BENEATH THE MASONRY PLATES.FOR EPOXY COATING, SEE SPECIAL PROVISIONS.

SHOTCRETE REPAIR AREA

CONCRETE REPAIR AREA

CONTRESIN INJECTION (ERI)

PROJECT NO. <u>I-5746C</u> <u>MECKLENBURG</u> COUNTY

BRIDGE NO: 590332

SHEET 3 OF 6

DocuSigned by: DocuSigned by: 02EE938FAB674C5...

> * SEAL 35647

CINE

8/23/2021

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

BENT 11 SPAN L FACE

			SHEET NO.				
DOCUMENT NOT CONSIDERED	N0.	BY:	DATE:	NO.	BY:	DATE:	S10-77
FINAL UNLESS ALL	1			3			TOTAL SHEETS
SIGNATURES COMPLETED	2			4			274