

23-AUG-2021 12:05 R:\Structures\FINAL PLANS\Bridge 332\410_175_I5746C_SMU_B13N_S10-88_590332.dgn aacole

+

+

AS-BUILT REPAIR QUANTITY TABLE								
BENT 13	QUANTITIES							
DENTIJ	ESTI	ΜΑΤΕ	ACTUAL					
SHOTCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.				
САР	0.0	0.0						
COLUMNS & STRUTS	14.4	7.2						
CONCRETE REPAIRS	AREA SQ.FT.	VOLUME CU.FT.	AREA SQ.FT.	VOLUME CU.FT.				
САР	0.0	0.0						
EPOXY RESIN INJECTION		LIN.FT.		LIN.FT.				
САР		0.0						
COLUMNS & STRUTS		0.0						
EPOXY COATING		SQ.FT.		SQ.FT.				
TOP OF BENT CAP & STRUTS		308						

VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE, MIN. OF 1" BEHIND REBAR AND 2" MIN.CLEAR TO SAWCUT. FOR REPAIR DETAILS, SEE ``TYPICAL CAP AND COLUMN REPAIR DETAILS" SHEET.

NOTES

REPAIR LOCATIONS AND ESTIMATE OF QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE.IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

CONCRETE REPAIRS MAY BE SUBSTITUTED IN LIEU OF SHOTCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.

FOR SHOTCRETE REPAIR, SEE SPECIAL PROVISIONS.

FOR CONCRETE REPAIR, SEE SPECIAL PROVISIONS.

FOR EPOXY RESIN INJECTION, SEE SPECIAL PROVISIONS.

CLEAN AND REMOVE DEBRIS FROM THE TOP OF THE CAP AND STRUTS AND APPLY EPOXY PROTECTIVE COATING.EPOXY COATING SHALL BE APPLIED TO THE TOP SURFACE OF THE CAP AND STRUTS.THE CONTRACTOR SHALL NOT COAT THE AREA OF THE CAP BENEATH THE MASONRY PLATES.FOR EPOXY COATING, SEE SPECIAL PROVISIONS.

	SHOTCRETE REPAIR AREA
	CONCRETE REPAIR AREA
\sim	EPOXY RESIN INJECTION (ERI)

	PROJEC	T NO.	I-	57460	<u> </u>		
	MEC	CKLEN	<u>IBURG</u>	CO	UNTY		
	BRIDGE	NO: _	590	0332			
DocuSigned by:	SHEET 2 OF 6						
02EE938FAB674C5 NH CAROLINA NOF ESSION	STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH						
NOR EESSION A SEAL 35647 NCINEER KAL 35647 8/23/2021	BENT 13 SPAN N FACE						
REVISIONS							
DOCUMENT NOT CONSIDERED	NO. BY:	DATE:	NO. BY:	DATE:	S10-88		
FINAL UNLESS ALL SIGNATURES COMPLETED	1		3 4		total sheets 274		