DocuSign Envelope ID: 4EE399FD-339E-4D87-ADEF-9A6D2E127BA7

PROJ. REFERENCE NO.	SHEET NO.
15614.1075010	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station I26, LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station I26	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station I26	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
450+50.00	0	0	477+00.00	17	0	457+00.00	5	19
451+00.00	8	0	477+31.25	4	0	457+50.00	5	15
451+50.00	16	0				458+00.00	4	13
452+00.00	19	0	**Station**	**Uncl. Exc.**	**Embt**	458+50.00	3	12
452+50.00	23	0				459+00.00	4	12
453+00.00	23	0	**I26, CL**	**(cu. yd.)**	**(cu. yd.)**	459+50.00	4	12
453+50.00	22	0	483+18.56	0	0	460+00.00	3	11
454+00.00	21	0	484+00.00	36	0	460+50.00	3	11
454+50.00	24	0	484+50.00	41	0	461+00.00	3	14
455+00.00	23	0	485+00.00	40	0	461+50.00	4	16
455+50.00	17	2	485+50.00	40	0	462+00.00	4	20
456+00.00	15	4	486+00.00	38	0	462+50.00	4	29
456+50.00	15	2	486+50.00	34	1	463+00.00	3	29
457+00.00	16	0	487+00.00	31	3	463+50.00	3	27
457+50.00	18	0	487+50.00	27	7	464+00.00	4	34
458+00.00	22	0	488+00.00	23	10	464+50.00	4	32
458+50.00	24	0	488+50.00	25	8	465+00.00	3	26
459+00.00	23	0	489+00.00	40	3	465+50.00	3	22
459+50.00	23	0	489+50.00	45	2	466+00.00	3	20
460+00.00	27	0	490+00.00	32	28	466+50.00	4	21
460+50.00	32	0	490+50.00	34	26	467+00.00	4	26
461+00.00	32	0	491+00.00	43	1	467+50.00	4	29
461+50.00	27	0	491+50.00	45	1	468+00.00	4	24
462+00.00	23	0	492+00.00	44	2	468+50.00	4	15
462+50.00	24	0	492+50.00	44	2	469+00.00	4	12
463+00.00	28	0	493+00.00	45	1	469+50.00	4	13
463+50.00	31	0	493+50.00	49	0	470+00.00	3	24
464+00.00	29	0	494+00.00	52	0	470+50.00	4	22
464+50.00	25	0	494+50.00	53	0	471+00.00	4	8
465+00.00	23	0	495+00.00	53	0	471+50.00	6	5
465+50.00	24	0	495+50.00	50	0	472+00.00	37	5
466+00.00	22	0	496+00.00	45	0	472+50.00	112	4
466+50.00	20	0	496+50.00	42	0	473+00.00	193	5
467+00.00	22	0	497+00.00	37	1	473+50.00	246	6
467+50.00	22	0	497+50.00	34	1	474+00.00	317	6
468+00.00	20	0				474+50.00	314	6
468+50.00	18	0	**Station**	**Uncl. Exc.**	**Embt**	475+00.00	144	7
469+00.00	18	0				475+50.00	17	8
469+50.00	19	0	**I26, RT**	**(cu. yd.)**	**(cu. yd.)**	476+00.00	5	11
470+00.00	21	0	450+40.00	0	0	476+50.00	5	16
470+50.00	21	0	450+50.00	0	0	477+00.00	4	18
471+00.00	20	0	451+00.00	6	5	477+50.00	4	16
471+50.00	19	0	451+50.00	6	8	478+00.00	4	11
472+00.00	18	0	452+00.00	5	6	478+50.00	4	6
472+50.00	20	0	452+50.00	6	5	479+00.00	5	4
473+00.00	20	0	453+00.00	8	3	479+50.00	6	8
473+50.00	17	0	453+50.00	8	3	480+00.00	6	19
474+00.00	20	0	454+00.00	7	4	480+50.00	7	21
474+50.00	21	0	454+50.00	7	6	481+00.00	15	13
475+00.00	19	0	455+00.00	6	10	481+50.00	13	16
475+50.00	22	0	455+50.00	4	15	482+00.00	4	27
476+00.00	21	0	456+00.00	4	21	482+50.00	4	17
476+50.00	19	0	456+50.00	5	22	482+65.00	1	1