PROJECT NO.	SHEET NO.	TOTAL NO.
2022CPT.08.09.20761	12	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1.5" MILLING	1308000000-E 0" TO 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1775500000-E ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	1838500000-N VACUUM TRUCK	2143000000-E BLOTTING SAND	2549000000-E 2'-6" CURB & GUTTER	2591000000-E 4" CONCRETE SIDEWALK	2600000000-N RETROFIT EXISTING CURB RAMP	2613000000-N REMOVE AND REPLACE CURB RAMPS	2759000000-N GENERIC PAVING ITEM - REMOVE CURB RAMP	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	5255000000-N PORTABLE LIGHTING	7444000000-E INDUCTIVE LOOP SAWCUT	7456000000-E LEAD-IN CABLE (14-2 PAIR)
										MI	FT	SMI	TON	SY	SY	SY	TONS	TONS	TONS	TONS	TONS	SY	GAL	WK	TON	LF	SY	EA	EA	EA	EA	EA	LS	LF	LF
2022CPT.08.09.20761	Randolph	1	SR 1105 BURNEY MILL RD.	(FROM: SR1181 NEW HOPE RD. TO MONTGOMERY COUNTY LINE.)	1	2	2WU	NO	NO	3.56	20	7.12	1,000.00			520		3,870		259	200														
TOTAL FOR MAP NO. 1										**3.56**		**7.12**	**1,000.00**			**520**		**3,870**		**259**	**200**														
2022CPT.08.09.20761	Randolph	2	SR 1115 COX MILL RD.	(FROM: NC HWY 134 TO: PAVEMENT JOINT PAST SR -1109 PISGAH RD)	1	2	2WU	NO	NO	0.94	20	1.88	264.00			520		1,089		73	80														
TOTAL FOR MAP NO. 2										**0.94**		**1.88**	**264.00**			**520**		**1,089**		**73**	**80**														
2022CPT.08.09.20761	Randolph	3	SR 2065 WOODCREST RD.	(FROM: SR-1490 NORTHSIDE TER. TO END OF MAINTENANCE)	4	2	2WU	NO	NO	0.3	18	0.60	92.40			520	397	375		43	200	3,485	1,394	1	10										
TOTAL FOR MAP NO. 3										**0.3**		**0.60**	**92.40**			**520**	**397**	**375**		**43**	**200**	**3,485**	**1,394**	**1**	**10**										
2022CPT.08.09.20761	Randolph	4	SR 1004 CARAWAY MTN. RD.	(FROM: SR1539 EARNHARDT RD. TO: SR 1416 OLD LEXINGTON RD.)	1	2	2WU	NO	NO	3.81	20	7.62	1,067.00	548		1,142		4,317		289	367														
TOTAL FOR MAP NO. 4										**3.81**		**7.62**	**1,067.00**	**548**		**1,142**		**4,317**		**289**	**367**														
2022CPT.08.09.20761	Randolph	5	SR 1103 VOLUNTEER RESCUE RD.	(FROM:DAVIDSON COUNTY TO: SR 1181 NEW HOPE RD.)	1	2	2WU	NO	NO	3.22	20	6.44	905.00			858		3,500		235	80														
TOTAL FOR MAP NO. 5										**3.22**		**6.44**	**905.00**			**858**		**3,500**		**235**	**80**														
2022CPT.08.09.20761	Randolph	6	SR 2832 FAIRVIEW FARM RD.	(FROM: BRIDGE 0226 TO: NC HWY 42 SOUTH)	1	2	2WU	NO	NO	1.28	20	2.56	360.00			429		1,429		96	100														
TOTAL FOR MAP NO. 6										**1.28**		**2.56**	**360.00**			**429**		**1,429**		**96**	**100**														
2022CPT.08.09.20761	Randolph	7	SR 1119 LITTLE RIVER RD.	(FROM: SR 1125 MAPLE SPRINGS RD. TO: MONTGOMERY COUNTY LINE)	1	2	2WU	NO	NO	3.48	20	6.96	978.00	1,353		207		3,969		266	150														
TOTAL FOR MAP NO. 7										**3.48**		**6.96**	**978.00**	**1,353**		**207**		**3,969**		**266**	**150**														
2022CPT.08.09.20761	Randolph	8	SR 1003 HOLLY SPRING RD.	(FROM: SR 2656 HINSHAW TOWN RD. TO: SR 2607 BUFFALO FORD RD.)	1	2	2WU	NO	NO	1.86	20	3.72	522.00			520		2,069		139	300														
TOTAL FOR MAP NO. 8										**1.86**		**3.72**	**522.00**			**520**		**2,069**		**139**	**300**														
2022CPT.08.09.20761	Randolph	9	SR 1401 KENNEDY FARM RD S	(FROM: US HWY 64 W TO: SR 1344 OLD US HWY 64)	1	2	2WU	NO	NO	0.89	20	1.78	250.00			390		1,013		68	100														
TOTAL FOR MAP NO. 9										**0.89**		**1.78**	**250.00**			**390**		**1,013**		**68**	**100**														
2022CPT.08.09.20761	Randolph	10	SR-1009 S. MAIN ST.	(FROM: SR 3182 COMANCHE RD. TO: GUILFORD COUNTY LINE)	2,3	4	MU	NO	NO	2.1	60				5,986	3,575			8,537	512	200					50	55	6	59	3	51	13	1	240	240
TOTAL FOR MAP NO. 10										**2.1**					**5,986**	**3,575**			**8,537**	**512**	**200**					**50**	**55**	**6**	**59**	**3**	**51**	**13**	**1**	**240**	**240**
TOTAL FOR PROJ NO. 2022CPT.08.09.20761										**21.44**		**38.68**	**5,438.40**	**1,901**	**5,986**	**8,681**	**397**	**21,631**	**8,537**	**1,980**	**1,777**	**3,485**	**1,394**	**1**	**10**	**50**	**55**	**6**	**59**	**3**	**51**	**13**	**1**	**240**	**240**
GRAND TOTAL										**21.44**		**38.68**	**5,438.40**	**1,901**	**5,986**	**8,681**	**397**	**21,631**	**8,537**	**1,980**	**1,777**	**3,485**	**1,394**	**1**	**10**	**50**	**55**	**6**	**59**	**3**	**51**	**13**	**1**	**240**	**240**