





**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

FINAL PAVEMENT SCHEDULE	
C1	PROP. APPROX. 2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5D, AT AN AVERAGE RATE OF 224 LBS. PER SQ. YD.
C2	PROP. APPROX. 2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 224 LBS. PER SQ. YD.
D1	PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
E1	PROP. APPROX. 5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 570 LBS. PER SQ. YD.
M	MILLED RUMBLE STRIPS
T	AGGREGATE SHOULDER BORROW (SHOULDER RECONSTRUCTION)
U	EXISTING ASPHALT PAVEMENT
V1	2" MILLED ASPHALT PAVEMENT



USE TYPICAL SECTION NO. 1
-L- MILE MARKER 0 TO MILE MARKER 13



6/2/99
21 AUG 2021 09:28
I:\Projects\I-5939\I-5939 From State Line to MM 16.Rob Co\submit\I-5939_RdJ_typ.dgn