PROJECT NO.	SHEET NO.	TOTAL NO.
I-5939	3D-1	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	0318000000-E FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	0320000000-E FOUNDATION CONDTIONING GEOTEXTILE	0366000000-E 15" RC PIPE CULVERTS, CLASS III	0372000000-E 18" RC PIPE CULVERTS, CLASS III	0378000000-E 24" RC PIPE CULVERTS, CLASS III	0992000000-E REMOVE AND REPLACE FLARED END SECTION, 18"	0992000000-E REMOVE AND REPLACE FLARED END SECTION, 24"	0992000000-E REMOVE AND REPLACE FLARED END SECTION, 30"	2253000000-E PIPE COLLARS	2286000000-E MASONRY DRAINAGE STRUCTURE	2308000000-E MASONRY DRAINAGE STRUCTURES	2365000000-N FRAME WITH TWO GRATES, STD 840.22	2374000000-N FRAME WITH GRATE & HOOD, STD 840.03, TYPE E	2473000000-N REMOVE & REPLACE CONCRETE APRON	2619000000-E 4" CONCRETE PAVED DITCH	2995000000-N REMOVE & REPLACE DRAINAGE STRUCTURE
						TON		LF	LF	LF	EA	EA	EA	CY	EA	LF	EA	EA	EA	SY	EA
	Robeson	1	I-95 MM 0.26	MEDIAN DRAINAGE BOX										0.05					1.00	16.00	
	Robeson	1	I-95 MM 0.53	MEDIAN DRAINAGE BOX										0.05					1.00	16.00	
	Robeson	1	I-95 MM 0.6	MEDIAN DRAINAGE BOX										0.05					1.00	16.00	
	Robeson	1	I-95 MM 0.67	MEDIAN DRAINAGE BOX										0.06					1.00		
	Robeson	1	I-95 MM 0.74	MEDIAN DRAINAGE BOX										0.07					1.00	16.00	
	Robeson	1	I-95 MM 0.82	MEDIAN DRAINAGE BOX		0.89	2.67	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 1.15	MEDIAN DRAINAGE BOX										0.05						16.00	
	Robeson	1	I-95 MM 1.25	MEDIAN DRAINAGE BOX										0.05						16.00	
	Robeson	1	I-95 MM 1.3	MEDIAN DRAINAGE BOX		1.00	3.50		8.00								1.00			16.00	1.00
	Robeson	1	I-95 MM 1.42	MEDIAN DRAINAGE BOX																16.00	
	Robeson	1	I-95 MM 1.5	MEDIAN DRAINAGE BOX		0.89	2.67	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 1.59	MEDIAN DRAINAGE BOX		0.89	2.80	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 1.64	MEDIAN DRAINAGE BOX		0.89	2.67	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 1.73	MEDIAN DRAINAGE BOX		0.89	2.67	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 1.83	MEDIAN DRAINAGE BOX		0.89	4.10	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 1.9	MEDIAN DRAINAGE BOX		0.89	2.67	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 2	MEDIAN DRAINAGE BOX										0.05					1.00	16.00	
	Robeson	1	I-95 MM 2.07	MEDIAN DRAINAGE BOX		0.89	2.67	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 2.2	MEDIAN DRAINAGE BOX		0.89	2.67		8.00								1.00			16.00	1.00
	Robeson	1	I-95 MM 2.38	MEDIAN DRAINAGE BOX		0.89	2.80		8.00								1.00			16.00	1.00
	Robeson	1	I-95 MM 2.48	MEDIAN DRAINAGE BOX		0.89	2.67		8.00								1.00			16.00	1.00
	Robeson	1	I-95 MM 2.63	MEDIAN DRAINAGE BOX		0.89	2.67	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 2.7	MEDIAN DRAINAGE BOX		0.89	2.67		8.00								1.00			16.00	1.00
	Robeson	1	I-95 MM 4.12	MEDIAN DRAINAGE BOX															1.00	16.00	
	Robeson	1	I-95 MM 4.22	MEDIAN DRAINAGE BOX															1.00	16.00	
	Robeson	1	I-95 MM 4.82	AT WELCOME CENTER											1.00			1.00			
	Robeson	1	I-95 MM 5.17	MEDIAN DRAINAGE BOX		0.89	3.40			8.00							1.00			16.00	1.00
	Robeson	1	I-95 MM 5.43	MEDIAN DRAINAGE BOX										1.10							
	Robeson	1	I-95 MM 5.71	MEDIAN DRAINAGE BOX		0.89	2.80	8.00		8.00							1.00			16.00	1.00
	Robeson	1	I-95 MM 6.83	MEDIAN DRAINAGE BOX										0.05							
	Robeson	1	I-95 MM 6.95	MEDIAN DRAINAGE BOX		0.89	2.67	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 7.39	MEDIAN DRAINAGE BOX		1.50	5.33			16.00							1.00			16.00	1.00
	Robeson	1	I-95 MM 7.63	MEDIAN DRAINAGE BOX		0.89	2.67	8.00									1.00			16.00	1.00
	Robeson	1	I-95 MM 7.7	FLARED END PIPE SECTION - MEDIAN							1.00										
	Robeson	1	I-95 MM 7.8	FLARED END PIPE SECTION - MEDIAN							1.00										
	Robeson	1	I-95 MM 7.94	FLARED END PIPE SECTION - MEDIAN							1.00										