


AS-BUILT REPAIR QUANTITY TABLE

TOP OF DECK REPAIRS								
	SPAN 1		SPAN 2		SPAN 3		SPAN 4	
	ESTIMATE	ACTUAL	ESTIMATE	ACTUAL	ESTIMATE	ACTUAL	ESTIMATE	ACTUAL
SHOTBLASTING BRIDGE DECK	169 SY		296 SY		296 SY		185 SY	
SILANE DECK TREATMENT	169 SY		296 SY		296 SY		185 SY	



NOTES:

WHERE MULTIPLE SPANS ARE LISTED, ESTIMATED QUANTITIES ARE BASED ON THE ANTICIPATED VALUES FOR A SINGLE SPAN OF THAT CONFIGURATION.

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE GIVEN WITH THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ADJUST THE ACTUAL QUANTITIES ENTERED INTO THE AS-BUILT REPAIR QUANTITY TABLE.


CONCRETE COVER FOR TOP BARS IN THE DECK SLAB IS 1/2" PER THE EXISTING BRIDGE PLANS. ACTUAL CONCRETE COVER SHALL BE DETERMINED BY THE CONTRACTOR AND PRESENTED TO THE ENGINEER PRIOR TO BEGINNING SURFACE PREPARATION.

CURRENT AVERAGE COVER IS EXPECTED TO BE FROM 1" TO 2" BASED ON VISUAL INSPECTION.

BRIDGE DECK SHOTBLASTING AND SILANE TREATMENTS LIMITS ARE THE FULL CLEAR ROADWAY WIDTH (INSIDE FACE OF EACH BRIDGE RAIL).


FOR SILANE DECK TREATMENT AND SHOTBLASTING BRIDGE DECK, SEE SPECIAL PROVISIONS.

PROJECT NO. I-5939
ROBESON COUNTY
 BRIDGE NO. 770107



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

PLAN OF SPANS



DRAWN BY : ALLEN J. MCSWAIN	DATE : 06/2021
CHECKED BY : DIEGO A. AGUIRRE	DATE : 06/2021
DESIGN ENGINEER OF RECORD: JACOB H. DUKE	DATE : 06/2021

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

KCA
KISINGER CAMPO & ASSOCIATES
 301 FAYETTEVILLE ST., SUITE 1500
 RALEIGH, NC 27601 (919) 882-7839
 NC FIRM LICENSE: C-1506

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S11-3
2			4			TOTAL SHEETS 5