PROJECT REFERENCE NO.	SHEET NO.
U-4405	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
29	-Y5-	26+10	28+00	LT	135
4B	-L1-	102+50	107+00	LT	270
28	-SR1-	15+00	16+50	RT	105
				SUBTOTAL	510
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					59,000
				TOTAL	59,510
				SAY	60,000

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)