

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS SECTION SUMMARY SHEET

Note: Embankment does not include backfill for undercut.

Station	Uncl. Exc. (LT)	Undercut (LT)	Embt (LT)	Uncl. Exc. (CL)	Undercut (CL)	Embt (CL)	Uncl. Exc. (RT)	Undercut (RT)	Embt (RT)	Station	Uncl. Exc. (LT)	Undercut (LT)	Embt (LT)	Uncl. Exc. (CL)	Undercut (CL)	Embt (CL)	Uncl. Exc. (RT)	Undercut (RT)	Embt (RT)
-L-	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	-L-	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)	(cu. yd.)
68+50.00			18	1		67	1		103	95+00.00	31						4		4
69+00.00	1		12	1		69	2		62	95+50.00	27		9				6		6
69+50.00	3		5	1		79	2		43	96+00.00	24		9				6		8
70+00.00	12		1	1		92	2		67	96+50.00	27						5		13
70+50.00	24			1		101	3		68	97+00.00	22		1				4		20
71+00.00	21					106	4		65	97+50.00	13		7				4		25
71+50.00	8		2			106	4		65	98+00.00	7		8				3		33
72+00.00	5		3			96	2		57	98+50.00	2		2				1		21
72+50.00	4		3			74	1		45	99+00.00									2
73+00.00	4		6			60	6		45	99+50.00									
73+50.00	5		33			57	11		53	100+00.00									
74+00.00	4		58			55	10		36	100+50.00	4		5				3		4
74+50.00	3		58			55	7		14	101+00.00	25		5				8		3
75+00.00	3		60			60	4		14	101+50.00	43		2				13		
75+50.00	2		62			75	7		13	102+00.00	50		9				11		5
76+00.00	1		32			42	5		6	102+50.00	57		12				5		18
76+50.00							2		7	103+00.00	53		18				3		28
77+00.00										103+50.00	43		26				3		31
77+50.00			85				1		14	104+00.00	32		30				3		34
78+00.00			223				1		44	104+50.00	16		28				4		42
78+50.00			298						54	105+00.00	9		20				5		55
79+00.00	1		320				1		43	105+50.00	9		16				7		68
79+50.00	12		357				44		23	106+00.00	7		18				7		68
80+00.00	12		526				44		19										
80+50.00			778			11	1		37										
81+00.00			1022			31			44										
81+50.00			1111			48			46										
82+00.00			1011			61			48										
82+50.00			800			72			56										
83+00.00			603			88	1		140										
83+50.00			510			107	2		208										
84+00.00			403			118	1		241										
84+50.00			311			114	1		274										
85+00.00			246			102	1		280										
85+50.00			103	1		78	2		275										
86+00.00				3		58	2		217										
86+50.00			57	3		56	2		154										
87+00.00			99	2		57	1		124										
87+50.00			82	1		57			125										
88+00.00			72			60			125										
88+50.00	1		66			66			120										
89+00.00	1		69			70			84										
89+50.00	3		64			49			43										
90+00.00	7		50			36			60										
90+50.00	7		43			38			85										
91+00.00	2		41			31			81										
91+50.00	1		34			31			80										
92+00.00	2		55			36			78										
92+50.00	5		75			43			74										
93+00.00	9		52			38			65										
93+50.00	13		26			16			58										
94+00.00	17		7						45										
94+50.00	24		1				1		20										

Note: "Quantities are approximate only. The Resident Engineer will re-cross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid. The Embankment Column does not include backfill for Undercut"

5/28/99
05_MAR_2019_11:26
C:\cort\Roadway\NCDOT\U-4405\Roadway\XSC\4405_rdy...XSC_summary.dgn