PROJECT NO.	SHEET NO.	TOTAL NO.
2022CPT.05.12.20321.1, 2022CPT.05.12.20322.1 2022CPT.07.18.20681, ETC.	21	

THERMOPLASTIC AND PAINT QUANTITIES

									4413000-E	4457000-N	4510000-N	4685000-E		4695000-E		4720000-E	4725000-E	4850000-E	4860000-E	4890000-E		4447000-E	4600000-N	
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	LAW ENFORCEMENT	4" X 90 M YELLOW THERMO	4" X 90 M WHITE THERMO	8" X 90 M YELLOW THERMO	8" X 90 M WHITE THERMO	THERMO MSG SCHOOL 90 M	THERMO LT ARROW 90 M	4" LINE REMOVAL	8" LINE REMOVAL	24" X 90 M WHITE THERMO	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES, 4", 50 MIL	PEDESTRIAN CHANNELIZING DEVICES	GENERIC TRAFFIC CONTROL ITEM - PEDESTRIAN TRANSPORT SERVICE	TRAFFIC CONTROL ITEM - AUDIBLE WARNING DEVICE
							MI	FT	SF	LS	HR	LF	LF	LF	LF	EA	EA	LF	LF	LF	LF	LF	EA	EA
2022CPT.05.12.20321.1	Durham	1	HAMLIN RD. SR 1634	SR 1632 (RED MILL RD) TO SR 1004 (OLD OXFORD RD)	1	2	3.333	26	374	*	40	36,000	35,200	140		6	2			50		60	10	2
		2	FELLOWSHIP DR. SR 1707	SR 1634 (HAMLIN RD.) TO CDS	2	2	0.328	20	37															
		3	DEARBORN DR. SR 1666	SR 1669 (E. CLUB BLVD.) TO SR 1004 (OLD OXFORD RD.)	3	2	1.591	24	178		80	16,800	16,800		48	12			8	164				
		4	GLENN RD. SR 1636	SR 1631 (RED MILL RD.) TO SR 1671 (E. CLUB BLVD.)	3	2	3.642	21	408			40,624	38,464	150			2	480			480			
		5	SWING RD SR 1365	SR 1634 (HAMLIN RD) TO SR 1636 (GLENN RD.)	3	2	0.127	24	14			1,367	1,367											
		6	DODGE AVE. SR 1790	SR 1636 (GLENN RD.) TO EOM	2	2	0.179	18	20															
		7	ABERDEEN DR. SR 1703	SR 1636 (GLENN RD.) TO EOM	2	2	0.326	20	37															
		8	CADILLAC AVE. SR 1722	SR 1721 (FORD LN.) TO SR 1703 (ABERDEEN DR.)	2	2	0.16	18	18															
		9	FORD LN. SR 1721	SR 1636 (GLENN RD.) TO SR 1722 (CADILLAC AVE.)	2	2	0.095	18	11															
		10	ALAMEDA ST. SR 1710	SR 1636 (GLENN RD.) TO SR 1725 (CAMBERLEY DR.)	2	2	0.362	18	41															
		11	DARROW RD. SR 1747	SR 1726 (WEYBURN RD.) TO SR 1676 (DAVIE RD.)	2	2	0.41	18-20	46															
		12	WEYBURN RD. SR 1726	SR 1747 (DARROW RD.) TO SR 1725 (CAMBERLEY DR.)	2	2	0.199	18-20	23															
		13	DAVIE RD. SR 1676	SR 1636 (GLENN RD.) TO EOM	2	2	0.61	18-48	68															
		14	CAMBERLEY DR. SR 1725	EOM TO EOM	2	2	0.295	18	33															
		15	WISHART ST. SR 1746	SR 1676 (DAVIE RD.) TO EOM	2	2	0.246	20	28															
		16	WESTMINSTER AVE. SR 1714	SR 1767 (DAVIE RD.) TO EOM	2	2	0.252	20	28															
		17	THORNBERRY CIR. SR 2473	SR 2459 (OLD BUGGY TRL.) TO CDS	4	2	0.057	20-30	6															
		18	CAVENDISH CT. SR 2474	SR 2459 (OLD BUGGY TRL.) TO CDS	4	2	0.076	20-35	9															
		19	HARDSCRABBLE DR. SR 2454	SR 1002 (ST. MARYS RD.) TO SR 2455 (HARDSCRABBLE DR.)	4	2	0.575	20-58	6															
TOTAL FOR PROJ NO. 2022CPT.05.12.20321.1							**12.863**		**1,385**	**1.00**	**120**	**94,791**	**91,831**	**290**	**48**	**18**	**4**	**480**	**8**	**214**	**480**	**60**	**10**	**2**
												186,622		**338**										
2022CPT.05.12.20322.1	Durham	20	HARDSCRABBLE DR. SR 2455	SR 2454 (HARDSCRABBLE DR) TO MP 1.8 (SR 2454)	4	2	1.819	20-44	204	*														
		21	OLD BUGGY TRL. SR 2459	SR 2454 (HARDSCRABBLE DR.) TO EOM	4	2	0.27	22	56															
		22	ASHEMONT CIR. SR 2461	SR 2460 (SHOTWELL CIR.) TO CDS	4	2	0.05	20-28	6															
		23	SHOTWELL CT. SR 2460	SR 2459 (OLD BUGGY TRL.) TO CDS	4	2	0.039	20-28	4															
		24	CHATFIELD CT. SR 2457	SR 2454 (HARDSCRABBLE DR.) TO CDS	4	2	0.037	20	4															
		25	SAGAMORE PL. SR 2458	SR 2454 (HARDSCRABBLE DR.) TO CDS	4	2	0.207	20-35																
		26	BERWICK PL. SR 2475	SR 2455 (HARDSCRABBLE DR.) TO ORANGE CO. LINE	4	2	0.195	22	22															
		27	TREADWAY CT. SR 2476	SR 2455 (HARDSCRABBLE DR.) TO CDS	4	2	0.147	20	16															
		28	PENNWICK PL. SR 2477	SR 2455 (HARDSCRABBLE DR.) TO CDS	4	2	0.136	22	15															
		29	BURGESS CT. SR 2478	SR 2455 (HARDSCRABBLE DR.) TO CDS	4	2	0.119	22	13															
		30	STEEPLETON CT. SR 2479	SR 2455 (HARDSCRABBLE DR.) TO CDS	4	2	0.148	22	17															
		31	THISTLE TRACE SR 2480	SR 2455 (HARDSCRABBLE DR.) TO CDS	4	2	0.138	22	15															
		32	STOCKBRIDGE PL. SR 2456	SR 2455 (HARDSCRABBLE DR.) TO EOM	4	2	0.09	20	28															
		33	WILSFORD CT. SR 2481	SR 2456 (STOCKBRIDGE PL.) TO CDS	4	2	0.084	19-29	9															
TOTAL FOR PROJ NO. 2022CPT.05.12.20322.1							**3.479**		**409**	**1.00**														
2022CPT.07.18.20681	Orange	34	ED BURTON CT. SR 1690	CDS TO CDS	4	2	0.188	22	21	*														
TOTAL FOR PROJ NO. 2022CPT.07.18.20681							**0.188**		**21**	**1.00**														
2022CPT.07.19.20681	Orange	35	BERWICK PL. SR 1691	DURHAM CO. LINE TO SR 1690 (ED BURTON CT.)	4	2	0.047	22	5	*														
TOTAL FOR PROJ NO. 2022CPT.07.19.20681							**0.047**		**5**	**1**														
GRAND TOTAL							**16.577**		**1,820**	**1.00**	**120**	**94,791**	**91,831**	**290**	**48**	**18**	**4**	**480**	**8**	**214**	**480**	**60**	**10**	**2**
												186,622		**338**										