PROJECT NO.	SHEET NO.	TOTAL NO.
2CPT.08.12.10621, 2022CPT.08.12.20		
34352.2.S2,	27	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1.5" MILLING	1297000000-E 3.5" MILLING	1297000000-E 2" MILLING	1308000000-E 0" TO 4.75" MILLING	1330000000-E INCIDENTAL MILLING	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1524200000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5D	1575000000-E ASPHALT BINDER FOR PLANT MIX	1577000000-E POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1840000000-E MILLED RUMBLE STRIPS	2605000000-N CONCRETE CURB RAMP	2613000000-N REMOVE AND REPLACE CURB RAMPS	2753000000-E GENERIC PAVING ITEM - REMOVE AND REPLACE 2'-6" CURB AND GUTTER	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	7444000000-E INDUCTIVE LOOP SAWCUT	7456000000-E LEAD-IN CABLE (14-2 PAIR)
										MI	FT	SMI	TON	SY	SY	SY	SY	SY	TONS	TONS	TON	TONS	TONS	TONS	LF	EA	EA	LF	EA	EA	LF	LF
2022CPT.08.12.10621	Montgomery	1	US 220 ALT	PVMT JT SE OF SR 1608 (WHISKEY RD) TO PVMT JT 1MI N OF SR 1575 (YARBOROUGH RD), (I-73/74 RAMPS TO BACK OF RADIUS)	1,2,3,4,5	2	2WU	NO	NO	2.65	30			56,100				4,633	5,423			363		50	16,180							
TOTAL FOR MAP NO. 1										**2.65**				**56,100**				**4,633**	**5,423**			**363**		**50**	**16,180**							
2022CPT.08.12.10621	Montgomery	2	NC 109	FROM SR 1150 (RIVER RD) TO BRIDGE #45 @ UWHARRIE	6, 7	2	2WU	NO	NO	1.356	22			19,500				1,000		2,022		121		100								
TOTAL FOR MAP NO. 2										**1.356**				**19,500**				**1,000**		**2,022**		**121**		**100**								
2022CPT.08.12.10621	Montgomery	3	NC 731	FROM STANLY CO TO BEGIN C&G 480LF E OF SR 1107 (NORTHVIEW RD)	8	2	2WU	NO	NO	2.55	24	5.10	714.00					533	3,605			242		200								
TOTAL FOR MAP NO. 3										**2.55**		**5.10**	**714.00**					**533**	**3,605**			**242**		**200**								
TOTAL FOR PROJ NO. 2022CPT.08.12.10621										**6.556**		**5.10**	**714.00**	**75,600**				**6,166**	**9,028**	**2,022**		**726**		**350**	**16,180**							
															75,600																	
2022CPT.08.12.20621	Montgomery	4	SR 1333 (BRUTON ST)	FROM NC 134 (N. MAIN ST) TO SR 1403 (N RUSSELL ST)	9	2	2WU	NO	NO	0.18	26				2,322			122	212			14		15		4	2	100	3	3	220	220
TOTAL FOR MAP NO. 4										**0.18**					**2,322**			**122**	**212**			**14**		**15**		**4**	**2**	**100**	**3**	**3**	**220**	**220**
2022CPT.08.12.20621	Montgomery	5	SR 1333 (BRUTON ST)	FROM SR 1403 (N RUSSELL ST) TO END C&G 300LF E OF SR 1383 (WOOD ST)	10,11,12	2	2WU	NO	NO	0.15	22			740			640	61	197			13		50		4	4		2	3		
TOTAL FOR MAP NO. 5										**0.15**				**740**			**640**	**61**	**197**			**13**		**50**		**4**	**4**		**2**	**3**		
2022CPT.08.12.20621	Montgomery	6	SR 1333 (BRUTON ST)	FROM END C&G 300LF E OF SR 1383 (WOOD ST) TO SR 1332 (PAGE ST)	13,14	2	2WU	NO	NO	0.44	20			5,178				56	471			32		120					2	1		
TOTAL FOR MAP NO. 6										**0.44**				**5,178**				**56**	**471**			**32**		**120**					**2**	**1**		
2022CPT.08.12.20621	Montgomery	7	SR 1005 (PEKIN RD)	FROM SR 1578 (HICKS RD) TO SR 1565 (ONVIL RD)	8	2	2WU	NO	NO	1.89	22	3.78	529.00					427	2,226			149		300								
TOTAL FOR MAP NO. 7										**1.89**		**3.78**	**529.00**					**427**	**2,226**			**149**		**300**								
2022CPT.08.12.20621	Montgomery	8	SR 1134 (TOWER RD)	FROM SR 1303 (OPHIR RD) TO END OF PAVEMENT	8	2	2WU	NO	NO	1.127	20	2.25	316.00	222				333	1,208			81		20								
TOTAL FOR MAP NO. 8										**1.127**		**2.25**	**316.00**	**222**				**333**	**1,208**			**81**		**20**								
TOTAL FOR PROJ NO. 2022CPT.08.12.20621										**3.787**		**6.03**	**845.00**	**6,140**	**2,322**		**640**	**999**	**4,314**			**289**		**505**		**8**	**6**	**100**	**7**	**7**	**220**	**220**
															8,462																	
34352.2.S2	Montgomery	9	NC 24/27 TROY BYPASS (R-0623)	EB LEFT TURN LANE STA 87+50 - 89+50	17,18,19	2	MD	NO	NO	0.038	12					625					72		4									
TOTAL FOR MAP NO. 9										**0.038**						**625**					**72**		**4**									
34352.2.S2	Montgomery	10	NC 24/27 TROY BYPASS (R-0623)	WB LEFT TURN LANE STA 144+00 - STA 150+00	17,18,19	2	MD	NO	NO	0.11	12					835					95		5									
TOTAL FOR MAP NO. 10										**0.11**						**835**					**95**		**5**									
34352.2.S2	Montgomery	11	NC 24/47 TROY BYPASS (R-0623)	WB OUTSIDE LANE STA 205+00 - STA 227+00	15	2	MD	NO	NO	0.417	12					2,940					329		19									
TOTAL FOR MAP NO. 11										**0.417**						**2,940**					**329**		**19**									
34352.2.S2	Montgomery	12	NC 24/27 TROY BYPASS (R-0623)	WB U-TURN LANE STA 289+00 - STA 295+00	17,18,19	2	MD	NO	NO	0.17	12					1,110					125		7									
TOTAL FOR MAP NO. 12										**0.17**						**1,110**					**125**		**7**									
34352.2.S2	Montgomery	13	NC 24/27 TROY BYPASS (R-0623)	WB RT TURN LANE STA 298+00 - STA 303+00	16	2	MD	NO	NO	0.094	12					555					63		4									
TOTAL FOR MAP NO. 13										**0.094**						**555**					**63**		**4**									
TOTAL FOR PROJ NO. 34352.2.S2										**0.829**						**6,065**					**684**		**39**									
															6,065																	
GRAND TOTAL										**11.172**		**11.13**	**1,559.00**	**81,740**	**2,322**	**6,065**	**640**	**7,165**	**13,342**	**2,022**	**684**	**1,015**	**39**	**855**	**16,180**	**8**	**6**	**100**	**7**	**7**	**220**	**220**
															90,127																	